# THYROID ABSORBED DOSE FOR PEOPLE AT RONGELAP, UTIRIK, AND SIFO ON MARCH 1, 1954

# A REPORT

403551

Edward T. Lessard, Robert P. Miltenberger, Robert A. Conard, Stephen V. Musolino, Janikiram R. Naidu, Anant Moorthy, and Carl J. Schopfer

Prepared for Roger Ray, Nevada Operations Office United States Department of Energy

SAFETY AND ENVIRONMENTAL PROTECTION DIVISION

BROOKHAVEN NATIONAL LABORATORY
UPTON, LONG ISLAND, NEW YORK 11973

#### DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency, contractor or subcontractor thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency, contractor or subcontractor thereof.

Printed in the United States of America Available from National Technical Information Service U.S. Department of Commerce 5285 Port Royal Road Springfield, VA 22161

NTIS price codes: Printed Copy: A05; Microfiche Copy: A01

#### PREFACE

The purpose of this report is to document the detail and data used to estimate thyroid absorbed dose to persons exposed to high levels of early fallout. The scope of the work was defined by historical records containing environmental measurement results and testing data for detonations in the Marshall Islands, particularly reports concerning the Castle BRAVO detonation. The records were scrutinized and data were subjected to a variety of analyses. The results of this work show agreement between measured radiological results and the required radiobiological projections. The new estimated thyroid absorbed dose and the medical factors relating to health effects in the Marshall Islands may be used to estimate potential health effects in other populations exposed under similar conditions.

#### **ACKNOWLEDGMENTS**

The authors fully appreciate the efforts of Victor Bond, Robert Conard, and Charles Meinhold of Brookhaven National Laboratory to initiate this study. Nathanial Greenhouse is to be commended for planning the meteorological and archival soil studies. Bruce Wachholz, Thomas McCraw, and Roger Ray of the Department of Energy are thanked for providing funding and support for the duration of the work.

The authors gratefully acknowledge the work of Fred Brauer of Battelle Pacific Northwest Laboratory who prepared and analyzed the archival soils. We also extend thanks to Kendall Peterson of Lawrence Livermore National Laboratory for computer simulation of the behavior of the BRAVO fallout cloud.

Much calculational work was performed by Lee Kaplan, c from Yale University; the authors are grateful.

The authors thank the many persons who reviewed drafts of the manuscript. These persons contributed new ideas and better procedures along with editorial comments. They were John Baum, Donald Borg, Eugene Cronkite, William Adams, and Andrew Hull, all from Brookhaven National Laboratory, and Charles Sondhaus from the University of California.

A special thanks goes to Barbara Boccia Lessard, a physician in private practice and wife of the principal investigator. Her thoughtful and scientific comment, advice, and encouragement are warmly appreciated.

<sup>&</sup>lt;sup>a</sup>Currently with Lawrence Berkely Laboratory.

bCurrently with National Cancer Institute.

<sup>&</sup>lt;sup>C</sup>Currently with Texas Instruments Corporation.

## CONTENTS

				Page
Pref	ace	••••	***************************************	iii
Ackn	owl e	edgmen	ts	v
List	of	Table	s	ix
List	of	Illus	trations	хi
Summa	ary	• • • • •	•••••••	xiii
ı.	I	ntrodu	ction	1
u.	Me	ethods	and Results	5
	4	. 131	I Intake at Rongelap Island Based on Urine Bioassay	
		R	esults	5
	В.	. Rad	ioiodine Air Concentrations Based on Meteorology	- 5
		1.	Calculation of BRAVO Fallout Patterns	5
		2.	Comparison of Whole-Body Dose Estimates	7
		3.	Duration of Fallout	8
		4.	Rate of Rise-of-Exposure Rate	9
		5.	Comparison of Airborne Activity Concentrations	9
	C.	Rad f	ioiodine Surface Activity Based on Archival Soil Analysis or 129 I	10
		1.	The Archival Soil Sample Collection	10
		2.	Analysis of Samples	10
		3.	Estimate of Initial Surface Activity	12
		4.	Ratio of Nuclide Activity to Total Fallout Activity in	
		5.	Archival Soils	12
			for Thermonuclear Fission	14
		6.	Bikini Ash	15
		7.	Comparison of Archival Soil Measurements to Thermonuclear	IJ
		•	Fission Data and Bikini Ash Estimates	17
		8.	Estimation of Radioiodine Activity per Unit Area Based	.,
		•	on Soil Activity for 1291	18
	D.	Thy	roid Absorbed Dose Estimate Based on Bikini Ash Results	19
		1.	Surface Activity and Exposure-Rate Estimates	19
			a. Nuclide Composition	19
			b. The Decay of Fallout	21

## CONTENTS (Cont'd)

	<u>.                                     </u>	Page
	c. The Buildup of BRAVO Fallout on the Ground	22
	d. A Simple Model for Exposure-Rate History at Rongelap, Sifo, and Utirik Islands	28
	e. Activity and Exposure-Rate History Based on Bikini	
	Ash	30
	i. Areal Activity and Exposure Rate from Nuclides	
	Observed on Day 26	30
	ii. Areal Activity at Fallout Cessation	31
	iii. Areal Activity of Nuclides Without Descendants in Bikini Ash	32
	iv. Non-Fission-Fragment Nuclides Not Accounted	
	for	37
	v. Input Data to Kinetics Equations	38
•	vi. Exposure Rate on Day 0.5 and Surface Roughness	20
	Effects	38
	vii. Integrated Exposure and Whole-Body Absorbed	
	Dose	39
	2. Radioactivity in Food, Water Supplies, and Air	39
	a. Activity in Cistern Water	39
	b. Activity Ingested with Drinking Water	42
	c. Activity in Food	44 45
	d. Activity Ingested with Meals	52
	e. Activity Concentrations in Air	52
	f. Activity Intake by Inhalation	54
	g. Total Activity Intake	54
	h. Deriving 131 Intake Based on Bikini Ash, 89Sr,	54
	and <sup>140</sup> Ba in Urine on Day 45 Post-Detonation	57
	i. Absorption Through Skin	۱, د
	3. Absorbed Dose for Individuals	57
	a. Absorbed Dose per Unit Activity Intake	57
	b. Thyroid Absorbed Dose	57
	c. Maximum Thyroid Absorbed Dose	60
	d. External Sources of Thyroid Dose	60
III.	Thyroid Nodule Risk and Thyroid Cancer Risk from Exposure to	
	Fallout	62
	and the seminary of the second and the set Theorem	62
	A. Tabulation of Thyroid Effects and Age at Exposure	62
	B. Tabulation of Risk of Thyroid Cancer	62
	C. Comparison to Other Estimates of Risk of Thyroid Cancer  D. Estimate of the Uncertainty in the Derived Risk Estimate	65
	21 200	

## LIST OF TABLES

Table	<u>Title</u>	Page
1	Fraction of Initial <sup>131</sup> I Activity Ingested That Is Excreted on Given Day Post-Intake	6
2	Comparison of Cumulated Whole-Body Dose, Rad	7
3	Duration of Fallout, Hours	8
4	Measured and Predicted Rate-of-Rise of Exposure Rate at Rongerik Atoll	10
5	Air Activity Concentrations	11
6	Soil Sample Results for Rongelap and Utirik Islands	13
7	Archival Soil Results Compared to Thermonuclear Fission and Bikini Ash Results	16
8	Activity of Iodine Isotopes Based on Archival Soil Results	18
9 .	Measured BRAVO Fallout Composition and Unfractionated Composition on Day 26	20
10	BRAVO Gamma or Beta Exponent Indicated by Miller for Fission Products	23
11	BRAVO Fallout Exposure-Rate Decline Based on Miller's Decay Estimates	29
12	BRAVO Fallout Beta Activity Related to BRAVO Fallout Exposure Rate	31
13	Estimated Unweathered Activity on Surface and Exposure Rate at One Meter, Rongelap Island	33
14	Average Estimate of Razioiodine Activity in Cistern Water and Time After the BRAVO Detonation	43
15	Average Estimate of Activity Intake from Cistern Water	45
16	Surface Activity and Time After BRAVO	49
17	Average Estimate of Activity Intake with Meals	51

## LIST OF TABLES

Table	<u>Title</u>	Page
18	Air Activity Concentration of Selected Nuclides	53
19	Average Estimate of Inhaled Activity	55
20	Total Radioiodine and Radiotellurium Activity Intake and Corresponding Age	56
21	Radioiodine and Radiotellurium Thyroid Absorbed- Dose Commitment per Unit Activity Intake and Corresponding Age	58
22	Estimated Radioiodine and Radiotellurium Thyroid Absorbed Dose and Corresponding Age	59
23	Total Thyroid Absorbed-Dose Estimate	61
24	Tabulation of Thyroid Results	63
25	Summary of Thyroid Results	64

## LIST OF ILLUSTRATIONS

Figure	<u>Title</u>	Page
1	Illustration of approach	4
2	Relative location of atolls and people	7
3	Curve fit of archival soil results	15
4	Activity vs granule diameter for Bikini ash	24
5	Cumulative % of activity deposited on the 5th Lucky Dragon vs time post-BRAVO detonation	26
6	Activity vs granule diameter for Rongelap Island fallout	26
7	Cumulative % of activity deposited on Rongelap Island vs time post-BRAVO detonation	26
8	Activity vs granule diameter for Utirik Island fallout	27
9	Cumulative % of activity deposited on Utirik Island vs time post-BRAVO detonation	27
10	Exposure-Rate histories for Rongelap, Sifo, and Utirik based on Bikini ash characteristics	40
11	Integrated exposure vs time	40
12	A cistern at Rongelap Island	41
13	Photographs of food preparation techniques and living patterns at Rongelap and Utirik Islands	47

#### SUMMARY

A study was undertaken to reexamine thyroid absorbed dose estimates for people accidentally exposed to fallout at Rongelap, Sifo, and Utirik Islands from the Pacific weapon test known as Operation Castle BRAVO. The study included: 1) reevaluation of radiochemical analysis, to relate results from pooled urine to intake, retention, and excretion functions; 2) analysis of neutron-irradiation studies of archival soil samples, to estimate areal activities of the iodine isotopes; 3) analysis of source term, weather data, and meteorological functions used in predicting atmospheric diffusion and fallout deposition, to estimate airborne concentrations of the iodine isotopes: and 4) reevaluation of radioactive fallout, which contaminated a Japanese fishing vessel in the vicinity of Rongelap Island on March 1, 1954, to determine fallout components. The conclusions of the acute exposure study were that the population mean thyroid absorbed doses were 21 gray (2,100 rad) at Rongelap, 6.7 gray (670 rad) at Sifo, and 2.8 gray (280 rad) at Utirik. The overall thyroid cancer risk we estimated was in agreement with results published on the Japanese exposed at Nagasaki and Hiroshima. We now postulate that the major route for intake of fallout was by direct ingestion of food prepared and consumed outdoors.

We believed urine bioassay results for <sup>131</sup>I excreted from people exposed at Rongelap to be accurate. We extrapolated our thyroid dose estimates from measured and derived quantities which were related to urine bioassay results. The facts which related were 1) fallout arrival and observation times, 2) size and nuclide composition of BRAVO fallout (also known as Bikini ash), 3) Rongelap, Utirik and Sifo Island exposure-rate measurements and 4) diet and living pattern observations. The <sup>131</sup>I intake, which we estimated from <sup>131</sup>I measured in urine, was used by us as a normalization point to link related facts. This allowed us to estimate the intake of other iodine isotopes and the intake of radiotelluriums.

Studies used by us to deduce the amount of  $^{129}$ I deposited at Rongelap and Utirik as a result of the BRAVO detonation revealed a much greater level of  $^{129}$ I in soil than could be derived by using other methods. Additionally, the uncertainty associated with soil measurements was very great. We concluded that other weapons tests may have influenced the soil concentrations of  $^{129}$ I and that isobars rather than isotopes of  $^{129}$ I may have exhibited similar behavior. Thus, using  $^{129}$ I to derive the intake of other radioiodines was not possible.

The meteorological approach used to assess thyroid dose did not result in agreement with relatable quantities. The value for predicted increase in exposure rate based on meteorology, or the meteorological-based estimate of whole-body dose, duration of fallout, or airborne activity concentration were not consistent with values obtained by measurement or estimates derived by different methods.

The composition, specific activity and particle size of BRAVO fallout (Bikini ash) were in agreement with other observed facts. Based on BRAVO fallout composition and specific activity studies, surface activity results which we derived for varous locations downwind of the detonation site were in agreement with directly measured surface activities made at these same locations shortly

after the accident. In addition, fallout duration and fallout arrival estimates derived from BRAVO fallout studies were in agreement with the observed fallout duration and arrival times. Our estimates of surface activity were transformed into estimates of surface exposure and exposure rate on an individual nuclide basis. The measured exposure and exposure-rate results reported in the literature were used to develop surface activity at locations and times of interest. Once the surface activity was derived, the intake pathway and estimate of intake were evaluated using the average <sup>131</sup>I excreted by Rongelap adults for normalization.

Estimates of thyroid absorbed dose, age at exposure, and intake of specific nuclides were tabulated for each location. For an adult male, the thyroid absorbed dose from iodine and tellurium radionuclides was 7.7 times the absorbed dose from <sup>131</sup>I at Rongelap, 10 times that at Sifo Island, and 4.7 times that at Utirik Island. James, in an earlier attempt to estimate thyroid absorbed dose based on <sup>131</sup>I in urine, assumed the total dose was 2.6 times the dose from <sup>131</sup>I (Ja64). The factor 2.6 would be appropriate for slightly older fallout than that experienced at Rongelap, Utirik, and Sifo Islands. Our estimate of thyroid absorbed dose was based on ingestion intake. Inhalation intake and absorption through skin could not be reconciled with measurements of <sup>131</sup>I in urine or with external exposure-rate measurements.

The average and maximum estimates of total absorbed dose to the thyroid were derived. Observations of the range of 137Cs body burdens during protracted exposure (Mi79) and Eve's estimate of the range associated with the contents of the stomach in cases of sudden death (Ev66) were used to estimate maximum thyroid absorbed dose. The maximum was estimated to be four times the average. The average internal thyroid dose at Rongelap Island was based on the average 131 I activity collected in urine. The contribution to thyroid dose from external sources was estimated from the air exposure caused by the decay of 142 nuclides making up the fallout composition. The external doses were similar to original estimates by Sondhaus for persons exposed at Rongelap and Utirik Islands, 1.75 gray and 0.14 gray (175 rad and 14 rad), respectively, which were derived from survey instrument readings taken at evacuation and film badge data from a nearby military outpost (So55). The external dose estimated for people at Sifo Island, 1.1 gray (110 rad), was greater than the 0.69 gray (69 rad) estimated originally from post-evacuation surveys of exposure rate. The difference was due to the presence of very short-lived activation and transuranic nuclides which, according to the nuclide composition, must have been present during exposure at Sifo Island.

Medical observations concerning thyroid abnormalities have been tabulated along with the new thyroid dose estimated for each person. From these results, the mean cancer risk rate in the exposed population of 251 people was 150 thyroid cancers per million person-gray-years at risk (1.5  $\pm$  2.3 thyroid cancers per million person-rad-years at risk). The mean time at risk for thyroid cancer was 19 years. The mean thyroid nodule risk rate was 830 nodules per million person-gray-years at risk (8.3  $\pm$  12 per million person-rad-years at risk). The mean time at risk for a thyroid nodule was 18 years.

#### I. INTRODUCTION

Persons who were present on March 1, 1954, at Rongelap Island, Rongelap Atoll; Sifo Island, Ailingnae Atoll; and Utirik Island, Utirik Atoll; in the Marshall Islands, have been examined by medical specialists to determine if any observable effects can be attributed to exposure to radioactive fallout. Their original estimates of external whole-body dose from the acute exposure were 1.75 gray (175 rad) at Rongelap and 0.14 gray (14 rad) at Utirik (Cr56). The first estimate of thyroid dose from internal emitters in Rongelap people was 100 to 150 rep\* (Cr56). Thus, the first estimate of total thyroid absorbed dose was 2.68 to 3.15 gray (268 to 315 rad) for Rongelap people in general and for internal plus external exposure.

Medical specialists have reported short-term effects exhibited over a period of many months and possible long-term effects exhibited over many years. In 1964, three teenage females who were exposed in 1954 underwent surgery for benign thyroid nodules. In 1964, 3- to 4-year-old child thyroid dose was reexamined by James on the basis of 1) urine bioassay results and 2) a range of values for thyroid burden of <sup>131</sup>I, thyroid mass, uptake retention functions, and ingestion or inhalation. For 3- to 4-year-old girls, the extreme range of thyroid dose from internal emitters was estimated at 2 to 33 gray (200-3300 rad). The most probable total thyroid dose was in the range of 7 to 14 gray (700-1400 rad). The James estimate of most probable total thyroid absorbed dose to the child was two to five times higher than the estimate reported by Cronkite for Rongelap people.

The value for the James estimate of total thyroid dose was extrapolated to other ages and to the Utirik people and reported along with medical effects by Conard (Co74). The number of radiation-induced thyroid lesions per million person-rad-years at risk was tabulated by Conard for the Rongelap and Utirik exposed populations (Co74). It was clear that the risks of radiation-induced benign and cancerous lesions for the two atolls were not comparable for any age grouping. The thyroid cancer risk for the Japanese population exposed at Nagasaki and Hiroshima, in units reported by the National Research Council's Committee on the Biological Effects of Ionizing Radiation, was 1.89 excess cases per million person-rad-years of tissue dose (CBEIR80). This parameter was 7.0 at Rongelap and 17.8 at Utirik for the 10-year and older age grouping in 1974 (Co74).

Variation in risk of radiation-induced thyroid cancer between atolls and the difference when compared to other irradiated groups had become an important scientific and health-related question with considerable political overtones. Early in 1977, Bond, Borg, Conard, Cronkite, Greenhouse, Naidu, and Meinhold, all members of Brookhaven National Laboratory (BNL), and Sondhaus, University of California, College of Medicine, initiated a reexamination of the technical issues. In 1978, formal program objectives and funding were supplied to BNL by the Department of Energy's Division of Biological and Environmental Research.

<sup>\*</sup>An obsolete unit of absorbed dose; 1 rep = 0.93 rad for soft tissue.

In June 1978, the Meteorology Division at Lawrence Livermore National Laboratory was subcontracted to provide a computer simulation of the dispersion, transport, and deposition of fallout from the 1955 atmospheric nuclear test, BRAVO. A subcontract to provide neutron activation analysis of archival soil samples was given to the Radiological Sciences Department, Battelle-Pacific Northwest Laboratory. Soil samples were provided by Seymour, Director of the University of Washington's Laboratory of Radiation Ecology.

During 1980, members of BNL researched the protracted exposure to fallout at Rongelap and Utirik Atolls. The interval of interest was from the time each population returned to their home atoll up to 50 years later. The nuclides considered were  $^{137}Cs$ ,  $^{60}Co$ ,  $^{90}Sr$ ,  $^{55}Fe$ ,  $^{65}Zn$ , and  $^{239}Pu$ . Thyroid absorbed dose from these sources was negligible relative to the thyroid dose committed during the first few days after the accidental exposure (Le84).

The subject of this report is the estimation of thyroid absorbed dose due to fallout exposure of the inhabitants of Rongelap, Utirik, and Sifo Islands on March 1, 1954. To determine thyroid dose, the amount of fallout activity taken into the body was estimated by reexamining the <sup>131</sup>I excreted from persons who were at Rongelap. The other components of fallout taken into the body had to be inferred from studies on fallout composition. Initially, fallout composition was assumed and nuclide activity concentrations in air, water, and food were established on the basis of meteorological and archival soil study results. Further study led to dose estimates based on actual BRAVO fallout composition rather than hypothetical composition. Finally, knowledge was gathered about the intake pathway and the time post-detonation at which intake was likely to have occurred, and this was factored into the thyroid absorbed dose estimates.

The report was prepared under the authorization of the Department of Energy's (DOE) Division of Biological and Environmental Research, which provided funding and review from 1978 until 1983. After organizational changes at DOE in 1983, funding and review were provided under the DOE Office of Military Application.

The purpose of the study was to clarify or document further the relationship between thyroid absorbed dose and incidence of thyroid nodules or thyroid cancer. The high incidence of benign and cancerous thyroid lesions was very evident (Co74). Our efforts were directed towards reevaluation of thyroid absorbed dose estimates upon which Conard's risk estimates were based.

The limitations for applying the risk estimated here to other exposed groups include the following: 1) thyroid dose estimates have a large standard error, 2) thyroid dose estimates apply to a unique situation involving ingestion of fallout plus external irradiation, and 3) the medical observations quoted are not infallible, that is, a reevaulation of medical results may result in reclassifications of thyroid lesions, or reveal other cancer sites, or additional thyroid lesions.

The sources of information were many and varied. Discussions with persons initially engaged in these studies, e.g., Stanton Cohn, Victor Bond, and Eugene Cronkite, led to review of documents which are cited in the references of this

report. A search for records at DOE headquarters led to the files currently held by Thomas McCraw who has acted as a repository for many Atomic Energy Commission documents. Some of these documents related directly to this study and were not easily located anywhere else. An abundance of environmental results have been published by the University of Washington's Laboratory of Radiation Ecology (also known as Applied Fisheries Laboratory). Medical information was published by BNL's Medical Department and by the Safety and Environmental Protection Division. Much of the early and detailed observations on the accidentally exposed Marshallese were recorded in documents published by the U.S. Naval Radiological Defense Laboratory and by the Naval Medical Research Institute.

The plan of this report is to document the details of the dose reassessment. Two methods, 1) the estimate of <sup>131</sup>I intake from urine results, and 2) the estimate of particle size and nuclide composition from Bikini ash results, could be related to each other and the known facts about arrival and duration of fallout, external exposure-rate measurements, and gross beta measurements. A schematic of the approach is given as Figure 1.

Once the nuclide composition and fallout arrival and duration times were assessed, the composition was normalized to external exposure-rate measurements. Exposure-rate histories and corresponding surface activity histories were then constructed for each island. Estimates of intake of radioiodines and radiotelluriums were based on the <sup>131</sup>I intake estimate which was in turn normalized to the Rongelap urine results. The time and mode of intake were based on observed diet and living patterns. The population mean and individual thyroid absorbed dose estimates were based on the age and location of the exposed people. Age-dependent values of thyroid absorbed dose per unit activity intake were taken from the scientific literature.

The final step was to obtain internal and external thyroid absorbed dose estimates for 251 exposed people. This was related to medical observations and summarized in the final section of the report. This relationship is presented in terms of thyroid cancer incidence per unit absorbed dose per million person years at risk.




Figure 1. Schematic of approach.

#### II. METHODS AND RESULTS

# A. 131 Intake at Rongelap Island Based on Urine Bioassay Results

Urine samples for 24-hour elimination were pooled and collected on the 17th day post-detonation from persons evacuated from Rongelap Island (Co72). The urine was sent to Harris at Los Alamos Scientific Laboratory and an estimate of thyroid-absorbed dose from internal emitters was reported by Cronkite (Cr56). The 64-person composite urine sample was 75% adult urine (18  $\ell$ , >16 years of age), 20% adolescent and child urine (4.8  $\ell$ , 5-16 years of age), and 4.8% child and infant urine (1.2  $\ell$ , <5 years of age) (Ja64). Harris indicated a mean activity of 0.48 kBq (1.31 x  $10^{-2}~\mu\text{Ci}$ ) of  $^{131}\text{I}$  in the Rongelap adult 24-hour urine taken on the 17th day post-detonation (Co72) and an adult mean peak thyroid content of 414 kBq (11.2  $\mu\text{Ci}$ ) (Ha54). This peak estimate was calculated on the assumption that 0.1% of stable iodine burden on the first day would be eliminated via urine between the 15th and 17th days (Co72).

Table 1 is a tabulation of the fraction of an initial <sup>131</sup>I activity intake by ingestion that would be eliminated by an adult on a given day post-intake. Two models were used to calculate these daily fractions, one developed by Johnson (Jo81) and the other by ICRP (ICRP79). Both models had feedback incorporated into the estimate of the fraction of initial intake. Both were solved using catenary compartment kinetics and both led to similar values for elimination of <sup>131</sup>I by a reference man. Values for fractions of an initial intake excreted by female individuals were higher than for males on days 10 and 25 but were the same on day 17. A comparison to an excretion function based on results for a normal adult male was made and values were tabulated for the intake of stable iodine (see Table 1). The stable fraction compares indirectly with the <sup>131</sup>I fraction through adjustment for radioactive decay.

On the basis of 0.48 kBq (1.31 x  $10^{-2}~\mu$ Ci) in adult urine on the 17th day post-intake, a 3440 kBq (93  $\mu$ Ci) intake was estimated for  $^{131}$ I. At Rongelap Island, ingestion at 0.5-day post-detonation was assumed.

The intake of 3440 kBq (93  $\mu$ Ci) was used as a normalization point. That is, once we had determined the relationship between <sup>131</sup>I and the other nuclides in fallout, we estimated the contribution to thyroid dose from all radioiodines, while keeping the <sup>131</sup>I intake at 3440 kBq (93  $\mu$ Ci). A similar method used by Cole and James to estimate thyroid absorbed dose (Co72,Ja64) differs from ours in that 1) we used the relationship between radioiodines and <sup>131</sup>I based on BRAVO fallout measurements, 2) we based the intake time (post-detonation) on diet and living pattern observations, and 3) we determined the mode of intake to be ingestion.

#### B. Radioiodine Air Concentrations Based on Meteorology

1. Calculation of Bravo Fallout Patterns. Downwind exposure-rate contours for the BRAVO detonation were estimated by several groups (Armed Forces Special Weapons Project, Rand Corporation, Naval Radiological Defense Laboratory) (Ha79). These contours, which were based on observations of BRAVO cloud dimensions and hodographs developed for 3 hours, 6 hours, and 9 hours post-detonation,

Table |

Fraction of Initial | 131 | Activity Ingested That

- Is Excreted on Given Day Post-Intake

Days Post- Intake	Reference Female <sup>a</sup>	Reference Male <sup>a</sup>	Reference Male <sup>b</sup>
1	-	<b>-</b>	4.4 x 10 <sup>-1</sup>
5	$1.4 \times 10^{-4}$	$1.4 \times 10^{-4}$	$4.4 \times 10^{-1}$ $1.4 \times 10^{-4}$
10	$1.9 \times 10^{-4}$	$1.8 \times 10^{-4}$	$1.9 \times 10^{-4}$
17	$1.4 \times 10^{-4}$	$1.4 \times 10^{-4}$	$1.4 \times 10^{-4}$
25	$9.2 \times 10^{-5}$	$8.0 \times 10^{-5}$	$9.0 \times 10^{-5}$

Fraction of Stable Iodine Ingested That Is Excreted on a Given Day Post-Intake for a Normal Adult Male

Days Post- Intake	Reference Male <sup>a</sup>	Reference Male <sup>b</sup>	A Normal Male <sup>c</sup>
1	~	4.6 x 10 <sup>-1</sup>	4 x 10 <sup>-1</sup>
5	$2.3 \times 10^{-4}$	$2.3 \times 10^{-4}$	4 x 10 <sup>-1</sup> 9 x 10 <sup>-4</sup>
10	$4.3 \times 10^{-4}$	$4.6 \times 10^{-4}$	7 x 10 <sup>-4</sup>
17	$6.4 \times 10^{-4}$	$6.4 \times 10^{-4}$	$7 \times 10^{-4}$
25	$6.9 \times 10^{-4}$	$7.5 \times 10^{-4}$	$7 \times 10^{-4}$

<sup>&</sup>lt;sup>a</sup>Johnson Model (Jo91).

do not all agree but are within a factor of 2 for any specific location at Rongelap and Utirik Atolls. A significant difference between the Armed Forces, Rand and Naval exposure-rate contours occurs 32 to 190 km (20 to 120 miles) north of Rongelap Atoll out to a distance of 480 km (300 miles) east of the detonation site. See Figure 2 for the relative location of the atolls and people.

Peterson estimated downwind exposures using a modified MATHEW-ADPIC computer code (Pe81). Additionally, Peterson developed instantaneous activity concentrations for \$129\text{Te}\$, \$131\text{I}\$, \$137\text{Cs}\$, and \$155\text{Eu}\$ for Ailingnae Atoll and the southeastern part of Rongelap Atoll near Rongelap Island. The computer codes were developed for the Atmospheric Release Advisory Capability of the Department of Energy. They were modified to include a larger number of upper-air

bICRP 30 Model (ICRP79).

CBerman (Be57), read from graph.




Figure 2. Relative location of the atolls and people.

wind levels which was thought by Peterson to be important. An additional modification included a turbulent wake correction to large granules falling from the stratosphere. Parameters for a tropical atmosphere were incorporated into granule fall velocity calculations. An assumption was made that the activity per granule increased as the cube of granule radius increased. The analytical approach has been described by Peterson (Pe81).

2. Comparison of Peterson's Whole-Body Dose Estimates. The cumulated whole-body dose was integrated from the onset of fallout to evacuation time. Peterson calculated the diffusion of fallout using computer codes and upper-air wind-level patterns. Peterson's results for whole-body dose were compared to estimates by Dunning (JCAE57) and Sondhaus (Cr56), and an estimate based on our analysis of Bikini ash. Sondhaus's work was detailed (So55); the whole-body dose was based on exposure-rate measurements and a range of assumed times for the onset and cessation of fallout. Sondhaus's best estimate of whole-body dose is given in Table 2, as are Peterson's estimate, the Dunning estimate, and the Bikini ash result (see column labeled 'This Report').

The values for whole-body dose estimated by Dunning and Sondhaus, and those estimated by the method indicated in Section II.D of this report are in

Table 2

Comparison of Cumulated Whole-Body Dose, Rad<sup>a</sup>

Location of People	1955 Sondhaus	1957 Dunning	1981 Peterson	1984 This Report
Rongelap	175	170	110	190
Ailingnae	69	75	24	110
Utirik	. 14	15	0.33	11
Rongerik	78	-	340	81

<sup>a</sup>Multiply by 0.01 to obtain gray.

reasonable agreement. These last two approaches were different from each other in that Sondhaus derived the estimate of whole-body dose from actual measurements of total exposure (film badges at Rongerik) and exposure rate, while the estimate using Bikini ash depended upon measurements of the composition of fall-out and exposure rate. The approach used by Peterson depended on upper-air wind level patterns and the fallout was estimated by him to drift back in a southerly fashion. This was not in agreement with assumptions regarding wind level patterns which were used in three previous and independent approaches (Ha79). The Peterson results for whole-body dose were radically different from other estimates for Rongerik and Utirik people and do not coincide with measured values for exposure and exposure rate (Sh57).

3. Duration of Fallout. Duration of fallout is defined as the time fallout begins up to the time of cessation (not to be confused with the time of evacuation, which was much later). Peterson's estimated duration of fallout (see Table 3) of about 19 hours at Rongelap appears to be too long relative to the reported wind velocity moving the cloud past Rongelap (Cr56) and relative to the first-hand accounts of fallout duration given by the Marshallese evacuated from Rongelap Island (Sh57). An upper limit of 16 hours' duration at Rongerik Atoll, estimated by Sondhaus, was based on the assumption of a constant rate-of-rise of exposure rate. The exposure-rate datum used to indicate cloud passage was the offscale reading of >100 mR h<sup>-1</sup> at 7 hours and 22 minutes post-detonation 270 km (170 miles) away from Bikini Atoll. Estimates of fallout duration time by Peterson, Sondhaus, and Dunning and those estimated by us are tabulated in Table 3 for comparison.

Sifo Island, Ailingnae Atoll, was the same distance from the detonation site as the Japanese vessel contaminated by Bikini ash (BRAVO fallout). Bikini ash was observed to fall for 5 hours (Ts55). Bikini ash granule size was visible to the eye (Su56), which at this location was consistent with reports that fallout was visible at Rongelap, Rongerik, and Ailingnae. Visual observations of

Table 3

Duration of Fallout, Hours

Location of People	Distance From the Detonation Site, km	Fallout Duration Estimated by Sondhaus 1955 (So55)	Fallout Duration Estimated by Dunning 1957 (JCAE57)	Fallout Duration Estimated by Peterson 1981 (Pe81)	Fallout Duration Estimated Here 1984 (This Report)
Ailingnae	150	12	5.5	10	5
Rongelap	210	12	5.5	19	7
Rongerik	270	12	-	17	9
Utirik	570	12	17	3	19

fallout arrival and cessation time were reported by many persons at each of these locations (Sh57, Ts55), except Utirik, and were in reasonable agreement with Dunning's values (see Table 3). On the basis of distance vs granule-size extrapolations and meteorological considerations, we also conclude that fallout would not have been visible at Utirik.

On Rongerik, a set of film badges was present and exposure results were obtained (So55). Survey instrument readings and the film badge results led Sondhaus to postulate total gamma exposures, from the time fallout began up to the time of evacuation, of 0.027, 0.022, and 0.018 C kg<sup>-1</sup> (106, 86, and 70 R). These values were based on three assumed fallout durations of 8, 12, and 16 hours, respectively. One film badge that remained outdoors at Rongerik gave a reading of 0.025 C kg<sup>-1</sup> (98 R). This total exposure from the time of fallout to evacuation corresponded to a fallout duration of 9.6 hours, which compares closely to the 9-hour value derived from fitting visual observations of fallout duration with distance from the detonation site (see Section II.D of this report). For whole-body dose estimates, Sondhaus appears to have assumed a 12-hour duration for all locations in order to conform to "constant fallout." The definition of "constant fallout" was not clear. Sondhaus also writes that "fallout probably would not be uniformly heavy throughout, the first portion being the most intense and the balance decreasing with time" (Cr56).

4. Rate-of-Rise of Exposure Rate. The rate at which exposure rate rises to the peak value has an effect on estimates of whole-body dose. A rate-of-rise in exposure rate at Rongerik Atoll was estimated from monitoring instrument readings taken for one-half hour (So55). Additional rate-of-rise information was determined from results supplied by Peterson (Pe81). Exposure-rate contours from graphs provided by Peterson were evaluated at different times at the Rongerik location. A best fit of the results yielded an exponential rise in exposure rate. A comparison of the two, measured rise versus predicted rise, indicated a wide discrepancy, the measured rise being much steeper. These results are tabulated in Table 4.

It is not clear which exposure-rate measurements Peterson accepted for normalizing his results. It is clear that he accepted at least one measurement at some location because he estimated whole-body dose. If both the Peterson and the Sondhaus whole-body dose results are to converge on the results for the Rongerik exposure-rate survey, which was made 9 days post-detonation (OC68), then Sondhaus's estimate of whole-body dose would have to be greater than Peterson's estimate, not less. This is because Peterson required a much slower rate-of-rise in exposure rate than did Sondhaus.

5. Comparison of Airborne Activity Concentrations. Air activity concentrations at Rongelap and Sifo Island were computed from the meteorological results provided by Peterson for <sup>131</sup>I and <sup>133</sup>I (Pe81). For comparison, results for air activity concentrations of <sup>131</sup>I and <sup>133</sup>I were estimated from the Bikini ash composition and are tabulated in Table 5. The cumulated activity and the airborne activity concentrations determined by either method do not agree. In summary, the Peterson-based approach towards estimating thyroid dose requires further refinement in order to achieve correspondence with all available information regarding external exposure, exposure rate and activity concentrations in air.

Table 4

Measured and Predicted Rate-of-Rise of
Exposure Rate at Rongerik Atoll

Time Post-Detonation, Hours	Measured Exposure Rate mR h <sup>-1</sup> a	Peterson's Predicted Exposure Rate mR h <sup>-la</sup>
6.87	0.18	220
6.91	0.70	240
6.95	2.7	270
7.04	3.6	330
7.12	10.5	400
7.20	30	480
7.29	60	580
7.37	100	700
% Change During		
Half Hour	55,000	320

<sup>a</sup>Multiple by 2.58 x  $10^{-7}$  to obtain C kg<sup>-1</sup> h<sup>-1</sup>.

# C. Radioiodine Surface Activity Based on Archival Soil Analyses for 129I

- 1. The Archival Soil Sample Collection. Surface soil samples were removed from Rongelap, Utirik, and other atolls in the Marshall Islands during the period 1954 to 1974. They were taken at depths up to two inches. Samples were stored at the University of Washington's Applied Fisheries Laboratory. Soil samples tested for <sup>129</sup>I were either midisland soils with humus, sandy soils from all parts of the island, black and white beach sands, grey powdery soils, randomly collected composites, or humus-seedy mixtures. Of the thousands of samples stored at the University, several hundred were identified for neutron activation analysis. Samples were packed and sent to Battelle Pacific Northwest Laboratory and analyzed by Brauer (Br80).
- 2. Analysis of Samples. Soil samples were analyzed for <sup>127</sup>I, <sup>129</sup>I, <sup>125</sup>Sb, <sup>137</sup>Cs, <sup>155</sup>Eu, and <sup>60</sup>Co. The methods for neutron activation analysis were described by Brauer (Br74) and Keisch (Ke65). Iodine was separated from soils according to the method of Studier (St62). Once separated, the iodine was irradiated with neutrons in a nuclear reactor, purified to reduce levels of interfering nuclides, and assayed using gamma spectroscopy (Br80). For quality control, comparison samples containing known amounts of <sup>125</sup>I, <sup>127</sup>I, and <sup>129</sup>I

Table 5
Air Activity Concentrations

	Peterson's Results, µCi cm <sup>-3a</sup>		Bikini Ash Results <u>µCi cm<sup>-3</sup></u>	
Time Post- BRAVO, h	131 <sub>I</sub>	133 <sub>I</sub>	131 <sub>I</sub>	133 <sub>I</sub>
Rongelap Island				
5	2x10 <sup>-10</sup>	7x10 <sup>-9</sup>	1x10 <sup>-7</sup>	3x10 <sup>-6</sup>
7	$7 \times 10^{-9}$	$2 \times 10^{-7}$	$3x10^{-8}$	7 <b>x</b> 10 <sup>-7</sup>
10	$4x10^{-7}$	$3x10^{-6}$	5x10 <sup>-10</sup>	9x10 <sup>-9</sup>
14	$2 \times 10^{-9}$	$4x10^{-8}$	-	-
17	$3x10^{-10}$	$7 \times 10^{-9}$	-	-
Cumulated Activity Concentration, Ci s m <sup>-3</sup>	4.0x10-3b	1.0x10 <sup>-1</sup>	1.4x10 <sup>-3</sup>	3.3x10 <sup>-2</sup>
Sifo Island				
3	4x10 <sup>-13</sup>	1x10 <sup>-11</sup>	8x10 <sup>-9</sup>	2x10 <sup>-7</sup>
5	$5 \times 10^{-10}$	1x10 <sup>-6</sup>	4x10 <sup>-10</sup>	1x10 <sup>-8</sup>
7	2x10 <sup>-8</sup>	5x10 <sup>-8</sup>	1x10 <sup>-11</sup>	3×10 <sup>-10</sup>
12	5×10 <sup>-9</sup>	1x10 <sup>-7</sup>	-	-
Cumulated Activity Concentration,				-
Ci s m <sup>-3</sup>	$6.0 \times 10^{-4b}$	1.8x10 <sup>-2</sup>	6.9x10 <sup>-5</sup>	$6.9 \times 10^{-3}$

<sup>&</sup>lt;sup>a</sup>Multiply 3.7 x  $10^{10}$  to obtain Bq m<sup>-3</sup>. <sup>b</sup>Multiply by 3.7 x  $10^{10}$  to obtain Bq s m<sup>-3</sup>.

were irradiated with each set of iodine samples isolated from Marshall Islands' soils (Br80).

The number of initial comparison atoms and the resulting comparison activity were used to determine a production ratio. The production ratio was applied to the soil sample activity and the number of atoms of activated nuclide

per gram of soil was estimated. Corrections to the soil activity were made on the basis of results for soil sample blanks, comparison sample blanks, and method yield.

A listing of the gamma-ray spectroscopy results and <sup>129</sup>I results for soil samples is shown in Table 6. The earliest surface soils dated back to 1955, about one and one-half years post-detonation of BRAVO. The <sup>60</sup>Co, <sup>137</sup>Cs, and <sup>155</sup>Eu activities per gram of soil appeared to have declined slowly over the years, while <sup>129</sup>I soil results declined at a much more rapid rate. Individual counting errors were normally less than 5%, although a few samples approached 20%.

3. Estimate of Initial Surface Activity. Positive 125Sb results (see Table 6) were too sparse for inferences to be drawn. For 129I, results were plentiful and, therefore, a least squares fitting was performed on results for nuclide soil activity per unit mass of dry soil vs days post-detonation using linear, exponential, logarithmic, and power function models. Sample results varied from their best-fit value by as much as a factor of 9 and by an average factor of 2.5 over the period 1955 to 1977.

The best-fitting function was determined from a comparison of the co-efficient of determination for each model. Functions used with <sup>129</sup>I results for Rongelap soil were plotted in Figure 3. Only the 1955 to 1957 results were plotted to illustrate the following points. For <sup>129</sup>I soil results, the best-fitting function was exponential. All four fitting functions were generally useful in predicting soil activity per gram at times after 600 days post-BRAVO for all nuclides. A significant divergence between functions occurs during the period several hours out to one year post-BRAVO. For example, at 0.5 day the difference between the exponential and power function estimate spans 5 orders of magnitude for <sup>129</sup>I.

Single exponential fitting gave the best coefficient of determination for  $^{129}\text{I}$ . The exponential fit of the  $^{129}\text{I}$  soil results at Rongelap led us to estimate a mean residence time in surface soil of about 5.4 years. The descriptive on these samples indicated that they were soils originally located at depths no greater than 5 cm (2 in.) beneath the surface.

4. Ratio of Nuclide Activity to Total Fallout Activity in Archival Soils. The ratio of 129 I activity to total fallout activity would help to determine whether the archival soil analysis for radioiodine corresponded to other measured or hypothetical ratios. The surface-soil activity of each nuclide measured by Brauer was estimated for 0.5 and 1.5 days post-detonation. These were the assumed times of cessation of fallout at Rongelap and Utirik, respectively. The value for the nuclide activity per unit mass of soil at the cessation of fallout was estimated from the best fit of archival soil results. For 129 I, the estimate was recorded in Table 7, column A.

At Rongelap, the total fallout activity per unit soil, based on four soil samples taken March 8, 1954 (OC68), was 3.0 x  $10^5 \pm 4.1$  x  $10^5$  Bq g<sup>-1</sup> (8.2  $\pm$  11  $\mu$ Ci g<sup>-1</sup>) at 0.5 day. The total fallout activity per unit mass of Utirik soil was 11% of the Rongelap result based on a ratio of exposure rate at the two

Table 6
Soil Sample Results for Rongelap and Utirik Islands

Sample		Rongelap, pCi g-la				
Collection Date	Days Post- Detonation	60 <sub>Co</sub>	125 <sub>Sb</sub>	129 <sub>I</sub>	137 <sub>Cs</sub>	155 <sub>Eu</sub>
10-22-55	600		_	1.1x10	1.4x10	_
10-22-55	600	$2.0 \times 10^{-1}$	_	$8.5 \times 10^{-3}$	$3.5 \times 10^{0}$	$2.7 \times 10^{-1}$
10-22-55	600	_	_	$9.4 \times 10^{-4}$	-	1.2x10 <sup>-3</sup>
12-5-55	644	2.1x10 <sup>-1</sup>	~	$5.8 \times 10^{-3}$	$2.4 \times 10^{0}$	2.0x10 <sup>-1</sup>
7-23-56	875	$2.3 \times 10^{-1}$	-	$7.6 \times 10^{-4}$	$2.2 \times 10^{1}$	$3.0 \times 10^{-1}$
7-23-56	875	-	-	$4.2x10^{-4}$	$7.0 \times 10^{0}$	_
7-17-57	1234	$3.7 \times 10^{-1}$	$1.0 \times 10^{-1}$	$1.5 \times 10^{-3}$	1.8x10 <sup>1</sup>	-
3-6-58	1466	$4.3x10^{0}$	_	$6.7 \times 10^{-4}$	$3.8 \times 10^{2}$	$1.0x10^{1}$
3-6-58	1466	$8.6 \times 10^{-1}$	-	$1.1 \times 10^{-4}$	2.5x10 <sup>1</sup>	$1.7 \times 10^{0}$
8-20-58	1633	1.1x10 <sup>1</sup>	$2.7 \times 10^{0}$	$3.5 \times 10^{-3}$	$5.0 \times 10^{1}$	$3.4 \times 10^{1}$
11-29-74	7578	$2.6 \times 10^{-1}$	-	$1.6 \times 10^{-5}$	$3.1 \times 10^{1}$	$6.2 \times 10^{-1}$
11-29-74	7578	$2.2 \times 10^{-1}$		$7.2 \times 10^{-5}$	3.5x10 <sup>1</sup>	$6.0 \times 10^{-1}$
12-2-74	7581	1.9x10 <sup>0</sup>	$7.0 \times 10^{-1}$	$2.9 \times 10^{-4}$	$6.3 \times 10^{1}$	7.5x10 <sup>0</sup>
4-3-76	8069	$5.1 \times 10^{-1}$	-	$6.5 \times 10^{-5}$	7.2x10 <sup>0</sup>	-
4-3-76	8069	-	_	$1.6 \times 10^{-5}$	5.1x10 <sup>0</sup>	-
9-27-76	8246	$9.8 \times 10^{-1}$	-	$8.0 \times 10^{-5}$	1.7x10 <sup>1</sup>	$2.3 \times 10^{0}$
5-10-77	8471	$4.4 \times 10^{-1}$	-	$4.6 \times 10^{-5}$	1.6x10 <sup>1</sup>	$4.1 \times 10^{-1}$
5-10-77	8471	$7.7 \times 10^{-1}$	-	4.7x10 <sup>-5</sup>	9.2x10 <sup>0</sup>	$8.0 \times 10^{-1}$
10-18-77	8632	$1.9 \times 10^{-1}$	-	$1.6 \times 10^{-5}$	$5.3x10^{0}$	2.1x10 <sup>-1</sup>
10-18-77	8632	$2.9 \times 10^{-1}$	-	$8.5 \times 10^{-6}$	3.7x10 <sup>0</sup>	-
10-18-77	8632	-	-	$2.0x10^{-5}$	$6.3x10^{0}$	-
10-19-77	8633	$7.7 \times 10^{-2}$	-	$2.5 \times 10^{-5}$	$2.3 \times 10^{0}$	_
10-19-77	8633	$1.1 \times 10^{-1}$	_	1.7x10 <sup>-5</sup>	$6.9 \times 10^{0}$	$2.2 \times 10^{-1}$
10-19-77	8633	$3.2 \times 10^{-1}$	-	$2.0 \times 10^{-5}$	$7.4 \times 10^{0}$	$2.6 \times 10^{-1}$

Table 6 (Cont'd)

Sample	-	Utirik, pCi g <sup>-la</sup>					
Collection Date	Days Post- Detonation	60 <sub>Co</sub>	125 <sub>Sb</sub>	129 <sub>I</sub>	137 <sub>Cs</sub>	155 <sub>Eu</sub>	
12-3-55	642	1.9x10 <sup>-1</sup>	-	1.6x10 <sup>-4</sup>	1.8x10 <sup>0</sup>	_	
12-3-55	642	-	_	$3.5 \times 10^{-5}$	-	-	
11-26-74	7575	$1.6 \times 10^{-1}$		$4.0 \times 10^{-3}$	$2.2 \times 10^{0}$	$2.5 \times 10^{-1}$	
11-26-74	7575	$2.0 \times 10^{-1}$	-	3.7x10 <sup>-5</sup>	1.4x10 <sup>0</sup>	-	
11-26-74	7575	$9.4 \times 10^{-2}$	_	$5.4 \times 10^{-4}$	$2.2 \times 10^{0}$	$2.4 \times 10^{-1}$	
9-21-76	8240	$1.8 \times 10^{-1}$	-	$2.3 \times 10^{-5}$	$2.8x10^{0}$	-	
9-21-76	8240	1.6x10 <sup>-1</sup>	-	1.6x10 <sup>-5</sup>	$7.8 \times 10^{-1}$	-	
5-8-77	8469	-	_	1.7x10 <sup>-5</sup>	$6.7 \times 10^{-1}$	_	
10-13-77	8627	$1.1 \times 10^{-1}$	_	9.6x10 <sup>-6</sup>	$1.2 \times 10^{0}$	-	
10-13-77	8627	1.3x10 <sup>-1</sup>		$2.0 \times 10^{-5}$	$1.6 \times 10^{0}$	_	
10-13-77	8627	-	_	5.7x10 <sup>-6</sup>	$9.0 \times 10^{-1}$	_	
10-14-77	8628	_	_	$1.1 \times 10^{-5}$	$7.0 \times 10^{-1}$	_	
10-14-77	8628	$8.6 \times 10^{-2}$	-	$2.3 \times 10^{-5}$	$3.2 \times 10^{0}$	-	
10-14-77	8628	$1.3 \times 10^{-1}$	-	$1.1 \times 10^{-5}$	1.6x10 <sup>0</sup>	-	

<sup>&</sup>lt;sup>a</sup>Multiply by 0.037 to obtain Bq  $g^{-1}$ .

islands after all of the fallout was on the ground. The fallout decay exponent was assumed by us to be -1.2 in order to extrapolate activity present on March 8, 1954, back to activity present on March 1, 1954. The exponent, -1.2, is the theoretical value for mixed fission products and is considered suitable for estimating the correspondence of  $^{129}\mathrm{I}$  soil results with other measurements. At Utirik, the total fallout activity per unit mass of soil was 7.8 x  $10^3$  Bq g $^{-1}$  (0.21  $\mu\mathrm{Ci}$  g $^{-1}$ ) at 1.5 days post-detonation.

The ratio of nuclide activity per unit mass of soil to the total beta activity per unit mass of soil was tabulated in Table 7, column B. This ratio applies at the times of cessation of fallout. The values in column B were compared to values estimated from measurements on actual BRAVO fallout and those estimated by calculation using hypothetical undisturbed fission product yield data. These estimates for BRAVO fallout activity ratios and those for hypothetical undisturbed fission products were determined as follows.

5. The Ratio of Nuclide Activity to Fission Product Activity for Thermonuclear Fission. Nuclide activity relative to total fission product activity was estimated from data on thermonuclear fission of <sup>238</sup>U given by Crocker (Cr65). Total activity values given by Crocker do not account for chemical and physical deletion or enhancement of fission products, production of activation products, or production of transuranics. Total activity per 10,000 fissions at 0.5 and




Figure 3. Curve fit of archival soil results.

1.5 days was taken from Table 3 of Crocker's report (Cr65). Individual nuclide activities were calculated by Crocker's methods and the original input data used by him (Cr63). The values for the hypothetical ratio of nuclide activity relative to total fission product activity are tabulated in Table 7, column E.

6. The Ratio of Nuclide Activity to Total Activity for Bikini Ash. Bikini ash was the name given by the Japanese for actual fallout from BRAVO (Is56). Estimates of Bikini ash activity per unit mass of soil were calculated from results for activity per unit area given in Table 13 of this report. Table 13 was devised by normalizing Bikini ash measurements to external exposure-rate measurements. Using the nuclide composition of Bikini ash, a fallout decay exponent specific for BRAVO fallout was developed (see Section IID.1.e) and was -1.4. Values for individual nuclide and total activity were developed for the surfaces of Rongelap, Utirik and Sifo Islands for different points in time. Bikini ash activity per unit mass of soil estimates were tabulated in Table 7, column C. The times are 1.5 days post detonation at Utirik and 0.5 days post detonation at Rongelap.

To estimate specific activity from areal activity, approximately  $65,000~{\rm g/m^2}$  of soil were assumed to be present in the top 5 cm (2 in.) of soil. This value comes from a conversion factor of  $6000~{\rm g/ft^2}$  proposed by the survey team which visited Rongelap on March 8, 1954 (OC68). A bulk soil-humus density of 1.3  ${\rm g/cm^3}$  in the top 5 cm (2 in.) of soil could be assumed to estimate a similar conversion factor.

Table 7
.
Archival Soil Results Compared to Thermonuclear Fission and Bikini Ash Results

Nuclide (# of Samples)	Archival Soil Value at 0.5 Day pCi g-la	Ratio of A to Measured Gross Bets Activity in Soil B	Bikini Ash Value at 0.5 Day pCi g-la C	Ratio of C to Total Bikini Ash Activity D	Hypothetical Ratio of Nuclide Activity to Total Activity for Thermonuclear Fission of <sup>238</sup> U E	Soil Result Compared to Thermonuclear Fission Result B/E	Soil Result Compared to Bikini Ash Result B/D	Bikini Ash Result Compared to Thermonuclear Fission Result D/E
		· · · · · · · · · · · · · · · · · · ·						
					Rongelap	•		
125 <sub>Sb</sub> (n=13)	1.5×10 <sup>0</sup>	1.8x10 <sup>-7</sup>	5.4x10 <sup>1</sup>	3.5x10 <sup>-6</sup>	4.6x10 <sup>-6</sup>	0.039	0.051	0.76
129 <sub>I</sub> (n=24)	2.1x10 <sup>-3b</sup>	2.6x10 <sup>-10b</sup>	7.0x10 <sup>-5</sup>	4.5x10 <sup>-12</sup>	3.5x10 <sup>-12</sup>	74.b	58.b	1.3
137 <sub>Cs</sub> (n=23)	6.2x10 <sup>1</sup>	7.6x10 <sup>-6</sup>	1.1x10 <sup>2</sup>	7.1x10 <sup>-6</sup>	5.5x10 <sup>-6</sup>	1.4	1.1	1.3
155 <sub>Eu</sub>	6.8x10 <sup>0</sup>	8.3×10 <sup>-7</sup>	1.1x10 <sup>1</sup>	7.1x10 <sup>-7</sup>	9.6x10 <sup>-7</sup>	0.87	1.2	0.74
(n=16)					Utirik <sup>C</sup>			
129 <sub>I</sub> (n=14)	1.4x10 <sup>-4b</sup>	6.7x10 <sup>-10b</sup>	7.7x10 <sup>-6</sup>	1.8×10 <sup>-11</sup>	1.3x10 <sup>-11</sup>	52.b	37.b	1.4
137 <sub>Cs</sub> (n=13)	2.0x10 <sup>0</sup>	9.5x10 <sup>-6</sup>	1.2x10 <sup>1</sup>	2.7x10 <sup>-5</sup>	2.1x10 <sup>-5</sup>	0.45	0.35	1.3
155 Eu (n=2)	2.5x10 <sup>-1</sup>	1.2x10 <sup>-6</sup>	1.2×10 <sup>0</sup>	2.7×10 <sup>-6</sup>	3.6x10 <sup>-6</sup>	0.33	0.44	0.75

\*Multiply by 0.037 to obtain Bq g<sup>-1</sup>. byalues have a standard deviation of ±900%. cValues at 1.5 days for Utirik results.

The ratio of nuclide activity to total activity was estimated from all of the activities listed in Table 13. The total activity in Bikini ash included the contribution of transuranics and activation products and was somewhat different in composition from hypothetical and undisturbed fission products.

On day 0.5 at Rongelap, a total activity per unit mass of soil of 5.5 x  $10^5$  Bq g<sup>-1</sup> (15  $\mu$ Ci g<sup>-1</sup>) was estimated from Bikini ash. A good portion of the activity was due to the decay of  $^{239}$ Np and  $^{237}$ U and other short-lived nuclides. The presence of short-lived activation and transuranic nuclides influenced the overall fallout decay exponent. A value for total activity per unit mass of soil of 1.6 x  $10^4$  Bq g<sup>-1</sup> (0.44  $\mu$ Ci g<sup>-1</sup>) at 1.5 days at Utirik was estimated. The ratio of nuclide activity to total activity based on Bikini ash is tabulated in Table 7, column D.

7. Comparison of Archival Soil Measurements to Thermonuclear Fission Data and Bikini Ash Estimates. The archival soil results were compared using the ratios of nuclide activity to total activity (Table 7, columns B/E, D/E, and B/D). For <sup>125</sup>Sb the ratios were not similar; however, soil sample-size was small. For <sup>155</sup>Eu and <sup>137</sup>Cs, results were in accord at both Rongelap and Utirik. The archival soil results for <sup>129</sup>I at Rongelap and Utirik were distinctly different from the hypothetical thermonuclear-fission results and Bikini Ash results.

In order to estimate the significance of the wide differences for  $^{129}I$  results, the standard deviations of the activity ratios were determined. The standard deviation of the archival soil best-fit value at 0.5 day (Table 7, column A) was approximated by linear regression methods (Be69). The archival soil result for  $^{129}I$  at Rongelap was 7.8 x  $10^{-5} \pm 6.7$  x  $10^{-4}$  Bq g<sup>-1</sup> (2.1 x  $10^{-3} \pm 1.8$  x  $10^{-2}$  pCi g<sup>-1</sup>) at the time of fallout cessation. The standard deviation of the four measurements of total activity per unit mass of soil on March 8, 1954, was 134% of the mean (OC68). The mean and standard deviation of the archival soil activity ratio (Table 7, column B) was estimated to be 2.6 x  $10^{-10} \pm 2.35$  x  $10^{-9}$ . Thus it is concluded that a significant difference between this ratio and the other two cannot be determined due to the large standard deviation. Columns B/E and B/D are also uncertain for  $^{129}I$ .

Errors in the thermonuclear fission product activity ratio for  $^{129}\text{I}$  (Table 7, column E) were due to errors in independent yield data and half-life measurements and were estimated by Crocker to be on the order of 10% (Cr65). The mean and standard deviation of this hypothetical ratio was estimated to be 3.5 x  $10^{-12} \pm 5.0 \times 10^{-13}$ .

A wide divergence between the measured activity ratio and the hypothetical activity ratio was possible. It may have been due to chemical and physical phenomena experienced by nuclides in the 129 mass chain at different times post-detonation. Enrichment by a maximum factor of 100 has been noted occasionally (Fr61).

The <sup>155</sup>Eu and <sup>137</sup>Cs archival soil activity ratios relative to the hypothetical ratio and the Bikini Ash ratio ranged between 0.87 and 1.4 for Rongelap soils and 0.33 and 0.45 for Utirik soils. These ratios were within acceptable limits of statistical uncertainty and are comparable. The Bikini Ash activity

ratios for  $^{129}$ I,  $^{155}$ Eu, and  $^{137}$ Cs were very close to the hypothetical ratios estimated for thermonuclear fission of  $^{238}$ U.

8. Estimation of Radioiodine Activity per Unit Area Based on Soil Activity for 1291. From the archival measurements, the iodine isotope activity was estimated per unit area of soil at the cessation of fallout at Rongelap (see Table 8). The enrichment of the iodine isotopes was assumed to be the same as for 1291.

The total radioiodine soil activity per unit area, based on <sup>129</sup> content of archival soils from Rongelap, exceeded the estimated total activity of all radionuclides per unit area by a factor of 10. The estimated total activity was based on four soil samples taken and measured for beta activity on March 8, 1954 (OC68). The radioiodine soil activity per unit area, based on archival soils from Utirik, exceeded the estimated total soil activity per unit area by a factor of 7. Because these archival soil based estimates were so much greater than measured activity, the assumption could not be made that iodine isotopes mimicked the behavior of <sup>129</sup>I, and thus the usefulness of archival soil measurements was limited.

The level of <sup>129</sup>I in archival soil may be real, an artifact of the neutron activation technique, or the residue from other weapons tests occurring near the time of soil collection. Comparison of Bikini ash results to hypothetical results for <sup>129</sup>I (Table 7, column D/E) leads one to believe that some enrichment of <sup>129</sup>I occurred but not to the extent indicated by our extrapolation of archival soil measurements (Table 7, column B/E). The level of activity of <sup>129</sup>I in Bikini ash was based on direct measurements of <sup>129</sup>Te and <sup>132</sup>I (Is56).

Table 8

Activity of Iodine Isotopes Based on Archival Soil Results

Iodine Isotope	Activity per Unit Area at Rongelap at 0.5 Day, µCi m <sup>-2a</sup>	Activity per Unit Area at Utirik at 1.5 Days, µCi m <sup>-2a</sup>
129 <sub>I</sub>	1.4x10 <sup>-4</sup>	9.0x10 <sup>-6</sup>
131 <sub>I</sub>	1.9x10 <sup>5</sup>	$9.2 \times 10^{3}$
132 <sub>I</sub>	5.8x10 <sup>5</sup>	2.5x10 <sup>4</sup>
133 <sub>I</sub>	2.0x10 <sup>6</sup>	4.9x10 <sup>4</sup>
134 <sub>I</sub>	$2.0 \times 10^{4}$	5.2x10 <sup>-6</sup>
135 <sub>I</sub>	2.5x106	$9.8 \times 10^{3}$
Total	5.3x10 <sup>6</sup>	9.3x10 <sup>4</sup>

<sup>a</sup>Multiply by 3.7 x  $10^4$  to obtain Bq m<sup>-2</sup>.

Enrichment of  $^{129}\text{I}$  in Bikini ash could have occurred independently without enriching  $^{129}\text{Te}$  or  $^{132}\text{I}$ , with the result that an  $^{129}\text{I}$  comparison between Bikini ash and archival soils was invalid. In conclusion, measurements on archival soils for  $^{155}\text{Eu}$  and  $^{137}\text{Cs}$  were in good agreement with Bikini ash and hypothetical results. The level of  $^{129}\text{I}$  in archival soils does not equate with the level of  $^{129}\text{I}$  estimated by other methods nor does it equate with a reasonable extrapolation of the levels of other iodine isotopes.

## D. Thyroid Absorbed-Dose Estimate Based on Bikini Ash

### 1. Surface Activity and Exposure-Rate Estimates

a. The Nuclide Composition. Radiochemical analysis results for the BRAVO fallout are summarized in Table 9. Bikini ash fell on the Japanese fishing vessel, the 5th Lucky Dragon, on the day of the test. Its gross beta activity was measured and normalized to day 26, and individual nuclide beta activity was identified and quantified by Japanese scientists (Ya56, Ts55). The percent of fallout beta activity, due to fission products present on day 26 after formation, is tabulated in Table 9. The hypothetical beta activity is based on a fallout composition unaltered due to chemical or physical mechanisms affecting certain fission product nuclides. This unaltered composition, which is referred to as unfractionated, was calculated from data given by Crocker. (Cr65).

The comparison between Bikini ash beta activity and unfractionated fission product beta activity required conversion of the Yamatera and Tsuzuki data sets (Ya56, Ts55) into percent fission product beta activity. That is, we exclude the beta activity of the activation products  $^{35}$ S,  $^{45}$ Ca and the transuranic nuclide  $^{237}$ U for comparison purposes. We assumed that  $^{237}$ U, which represented 20% of the beta activity on day 26 in the Tsuzuki data, represented 20% of the beta activity in the Yamatera data.

The column in Table 9 headed "U-238TN Unfractionated % Fission Product Beta Activity" represents the hypothetical percent of selected unfractionated fission products following thermonuclear neutron fission of <sup>238</sup>U. The data are applicable to day 26 post-detonation. The thermonuclear neutron energy spectrum and uranium target were chosen to represent the BRAVO device (OC68). The difference between percentages based on the Japanese measurements and those based on the hypothetical beta activity from thermonuclear fission represents differences between fractionated and unfractionated fallout.

As previously implied, the term fractionation indicated alterations of nuclide composition in fallout debris. The ratio of two nuclides in fallout was often used to describe fractionation quantitatively (Fr61). The denominator of the ratio was taken to be the activity of 95ZrNb (Fr61). To quantify fractionation between two nuclides, the beta activity ratios were compared by Freiling (Fr61). He uses the term "degree of fractionation" to represent the range of variability of the nuclide ratio. The term "extent of fractionation" represented the portion of the total nuclide produced in the fallout cloud which departed from the unfractionated ratio.

Table 9

Measured BRAVO Fallout Composition and Unfractionated Composition on Day 26

Nuclide(s)	Yamatera Data, % of Beta Activity	Yamatera % Fission Product Beta Activity	Tsuzuki Data, % of Beta Activity	Tsuzuki % Fission Product Beta Activity	U-238TN Unfractionated % Fission Product Beta Activity
00					
89 <sub>Sr</sub>	1.6	2.0	1.0	1.3	4.2
90SrY	0.02	0.025	0.040	0.050	0.062
91 <sub>Y</sub>	а	-	8.0	10.0	4.1
95ZrNb	9.8	12.0	8.0	10.0	9.6
103p,	5.0	6.3	ъ	С	8.5
106 <sub>RuRh</sub>	1.4	1.8	ъ	c	0.94
LZYTT-1ZYT-	1.3	1.6	ь	c	0.42
132 <sub>Te</sub>	1.0	1.3	ъ	С	0.83
131 <sub>I</sub>	4.5	5.6	ъ	c	6.1
132 <sub>I</sub>	1.0	1.3	ь	c	0.83
140BaLa	11.0	14.0	11.0	14.0	23.0
1+100	. 9.7	12.0	7.0	8.8	10.0
L44Copr	2.8	3.5	4.0	5.0	2.9
173pr	а	-	16.0	20.0	12.0
147 <sub>Nd</sub>	a	-	9.0	11.0	5.3
45 <sub>Ca</sub>	a	-	0.20	-	-
23/ <sub>11</sub>	а	-	20.0	-	-
239 <sub>Pu</sub> (α)	a	-	0.00040	-	-
35 <sub>S</sub>	a	-	0.050	-	-

a51% of total beta activity.

A review of the data in Table 9 indicated to us that the activity ratios for \$132\_{Te}\$, \$132\_{I}\$, \$131\_{I}\$, \$141\_{Ce}\$, \$106\_{RuRh}\$, \$144\_{CePr}\$ (their activity relative to measured \$95\_{ZrNb}\$ beta activity) did not differ by a factor greater than about 1.5 from the unfractionated ratios. Ratios for \$140\_{BaLa}\$, \$147\_{Nd}\$, \$91\_{Y}\$, \$90\_{SrY}\$, \$103\_{Ru}\$, and \$143\_{Pr}\$ were different by a factor of about 2 for \$89\_{Sr}\$ and \$129\_{Te}^{-129}\_{Te}\$ by a factor of about 3 relative to the unfractionated ratios. The nuclides \$91\_{Y}\$, \$106\_{RuRh}\$, \$129\_{Te}^{-129}\_{Te}\$, \$132\_{Te}\$, \$132\_{I}\$, \$144\_{CePr}\$, \$143\_{Pr}\$, and \$147\_{Nd}\$ were in greater abundance relative to unfractionated debris.

bl5% of total beta activity.

c<sub>19%</sub> of total fission product beta activity.

Freiling (Fr61) indicated that the degree of fractionation from a surface burst could be significant. The extent of the fractionation throughout the debris was another variable he observed to be significant. Freiling emphasized the high degree of fractionation between nuclides classified as volatile and refractory for coral atoll surface bursts. Generalizations were made, to be used with much caution. Freiling indicated that, in general, fractionation would decrease as device yield decreased and would increase with depth, that is, air bursts would be less fractionated than surface bursts which would be less fractionated than surface bursts which would be less fractionated than subsurface bursts. From Freiling's studies, we cautiously expect that the high yield surface burst creating the BRAVO fallout caused a moderate-to-high degree of fractionation which occurred moderately to extensively throughout the debris.

For the coral surface burst, Freiling observed that the ratio of 95 Tr to 89 Sr activity could be chosen as a representative measure of the overall degree of fractionation between refractory and volatile elements. This ratio had a value of 5 for a deep water surface burst of megaton range and a value of 100 for a coral surface burst (Fr61). The unfractionated value for this ratio, for day 26 post-detonation and for thermonuclear neutron fission of 238U, was calculated to be 1.6 from data given by Crocker (Cr65). From the average of Yamatera and Tsuzuki data, we calculated the ratio of 95 Tr activity to 89 Sr activity measured on day 26 to be 4.8. This measured value for the degree of fractionation was characteristic of a deep water surface burst of the megaton range, moderately but not highly fractionated. This moderate fractionation probably occurred moderately to extensively throughout the fallout cloud because of the large yield and surface location of the device (Fr61).

The effect of fractionation on decay rate is very complex, and simple observation of overall radioactive decay does not yield significant information. Even so, the decay rates from widely distributed samples obtained out to 480 km (300 miles) from the BRAVO detonation site were similar. The decay rates from activity on different-size fallout granules collected at the same site were similar (0C68). These facts alone do not indicate that the same fractionation was common to all granule sizes. In fact, small granules traveled with the cloud for longer periods of time and possibly adsorbed more longer-lived nuclides than did the very large granules. In the analysis, we assume that the fractionation observed for Bikini ash granules was similar for granules at Rongelap, Sifo, and Utirik Islands. With the possible exception of Utirik Island, this assumption was considered valid owing to the proximity of Rongelap and Sifo Islands to the 5th Lucky Dragon.

b. The Decay of Fallout. The gamma and beta decay of the BRAVO radioactivity after the first 10 days post-detonation was measured by several researchers (e.g., Miller, Servis, Tomkins, Wilsey, and Stetson, see OC68). Decay data from measurements made between 0 and 10 days were not found in the literature. Fallout samples, taken weeks after the BRAVO event, were from Bikini Atoll, Rongelap Atoll, the 5th Lucky Dragon, and the surface of US Navy ships in the area. The measured decay exponent after two weeks was used by many researchers to extrapolate exposure rate back to times prior to sample collection and in one case was used to estimate activity decline every hour postdetonation (Miller, OC68). These extrapolations by Miller for the decay of fall-

out activity from several hours to a few weeks post-BRAVO apparently excluded the decay characteristics of non-fission-fragment nuclides. This would affect surface activity estimates which we derived from Bikini ash results since these estimates relied in part on extrapolated decay rates. The estimated thyroid dose from internal sources would be affected by decay characteristics because it relied in part on these derived surface activity estimates.

In order to derive ground activity estimates at times close to BRAVO detonation and to derive external and internal thyroid dose, the gamma- or beta-decay-rate decline over short periods of time was assumed to have followed the relationship

$$x_2 = x_1 \frac{t_2}{t_1}^m , \qquad (1)$$

where

 $x_1$  = gamma- or beta-decay rate at time  $t_1$ , and  $x_2$  = gamma- or beta-decay rate at time  $t_2$ .

m = decay exponent.

In the early post-BRAVO period and for time intervals of a few hours, Miller's estimate of decay exponents may have departed significantly from the standard value used for planning fallout activity decline (m = -1.2). His values for m at different times post-detonation of BRAVO are listed in Table 10. At short time intervals there was a departure from m = -1.2. However, the overall decay exponent calculated from Miller's declining activity results, for the interval one hour to sixty days post-detonation, was -1.2. This was in agreement with the standard value used for decay of unfractionated fission products. Thus, it

seemed to us that the impact on activity decline due to non-fission-fragment nu-

clides may not have been folded into Miller's extrapolation.

Further study was done to establish actual BRAVO activity and exposure-rate decline. Surveys performed by the radsafe team of the USS PHILIP, the ship dispatched to evacuate people from Rongelap Island, have recorded an exposure-rate level for Rongelap village of 3.8 x  $10^{-4}$  C kg<sup>-1</sup> h<sup>-1</sup> (1473 mR h<sup>-1</sup>) average and 4.9 x  $10^{-4}$  C kg<sup>-1</sup> h<sup>-1</sup> (1900 mR h<sup>-1</sup>) maximum at 2.2 days postdetonation (COMTASK GROUP 7.3 Disp 020848Z of March 1954, 0C68). A similar but less precise statement of the exposure rate at the time of evacuation was given by Sharp (Sh57). In order to reconstruct the BRAVO exposure-rate decline prior to evacuation and not use the standard decay exponent, we derived additional information about the arrival time and nuclide composition of BRAVO fallout from Bikini ash measurements.

c. The Buildup of BRAVO Fallout on the Ground. The studies by Suito, Takiyama, and Uyeda (Su56) indicated that Bikini ash consisted of irregularly shaped white granules. Bikini ash, taken from the deck of the 5th Lucky Dragon, was deposited while the ship was located about 150 km (90 miles) from the detonation site (Ts55). Suito defined the mean volume diameter to be the diameter corresponding to the mean volume. From the size and shape distributions, Suito determined the mean volume diameter of Bikini ash granules to be 320  $\pm$  70  $\mu m$  (1.3  $\times$  10<sup>-2</sup>  $\pm$  2.8  $\times$  10<sup>-3</sup> in.). The mean mass of a granule was 0.039 mg (8.7  $\times$  10<sup>-9</sup> lb). The specific gravity was 2.4, less than the specific gravity of

Table 10

BRAVO Gamma or Beta Exponent
Indicated by Miller (OC68) for Fission Products

Time Post-Detonation,  t <sub>1</sub> to t <sub>2</sub> (h)	Decay Exponent,
1 to 2	-1.4
2 to 3	-1.2
3 to 6	92
6 to 9	81
9 to 12	78
12 to 24	82
24 to 48	-1.0
48 to 96	-1.2

CaCO<sub>3</sub>, 2.7-2.9. The granules were aggregates of smaller unit particles with shapes that varied from spindles to cubes to spheres. The size of these unit particles making up the granules varied from 0.1 to 3.0  $\mu$ m (4 x 10<sup>-6</sup> to 1.2 x 10<sup>-5</sup> in.). It was suggested by Suito that Bikini ash was formed by evaporation of the coral reef to its constituent atoms and then by recrystallization of Ca with H<sub>2</sub>O and CO<sub>2</sub> in the air (Su56).

The granule size distribution of Bikini ash was used to estimate the time over which the bulk of the activity fell on the fishing vessel. Most of the activity was carried by larger-volume granules, which fell at early times post-detonation (La65). The Bikini ash activity versus granule size distribution, % of total activity versus granule size, was plotted in Figure 4. To construct this histogram, we assumed the activity of a granule to be proportional to the 3.5 power of its size. Lavrenchik summarized the results of many studies and concluded that the activity of a granule was proportainal to the 3rd or 4th power of granule size (La56). He generalized that the activity and volume of the granule were proportional. The number of granules in each size class was reported by Suito for Bikini Ash (Su56). The size at median activity was 370 µm.

Our information regarding granule fall time as a function of granule size was derived from deposition models which were reviewed by Norment (No66). Four models of fallout settling were presented. These models accounted for granule size and initial height of the granule. Granule fall times from various heights were derived by Norment who used the model results of Davies, Hedman, Hastings, or Ksanda. Although the complexity of each model varied, each accounted for the aerodynamic properties of irregularly shaped fallout granules. The granule fall time result versus granule size was recast by us using a power




Figure 4. Activity vs granule size for Bikini ash.

function. This simple power function model gave a best fit to the results recorded by Norment.

Tsuzuki reported the observed fallout arrival time, cessation time, and granule size distribution for Bikini Ash (Ts55). These data were used to model a power function relationship which related granule size to granule fall time specifically for BRAVO fallout as follows:

$$T = 79.5 D^{-0.524}$$
, (2)

where

T = granule fall time in hours post-BRAVO,

D = granule size, micrometers.

It was assumed by us that the largest granules in the Bikini ash fell upon arrival and the smallest fell upon cessation of fallout. We used Eq. (2) to determine granule size distribution at Rongelap, Utirik, and Sifo Islands. To deter-

mine the rate at which activity built up on the surface at these locations, we used the relationship between activity and granule size previously described.


Equation (2) is a simple model to describe fall time versus granule size. The bulk of the activity of BRAVO was at the base of the cloud at 17 to 29 km (10 to 20 miles) aboveground, ten minutes after the burst (OC68). Granules of a given size were spread throughout the stem, the base of the cloud, and up to the cloud top at 40 km (25 miles). In fact, the entire distribution of granule sizes would reach the surface at any point in time, not just one size at one time. Our simple model (Eq. (2)), which we assumed for our purposes of estimating the rate-of-rise of exposure rate, the rate of accumulation of activity at the surface, and the accumulated external exposure during the period of rising exposure rates, was in agreement with measurements on rate-of-rise of exposure rate for weapons tests made during the Hardtack Series in 1957 (USPHS59) and with the rate-of-rise of exposure rate measured for one half-hour at Rongerik Atoll on March 1, 1954 (So55).


These estimates of granule fall time, granule size, and activity versus granule size were combined in a straightforward manner to determine the cumulative percent of activity deposited on the surface of the 5th Lucky Dragon versus time after the BRAVO explosion. The cumulative percent is plotted in Figure 5. The fallout was first observed by the fishermen on the Lucky Dragon at 3 hours post-detonation. Examination of Figure 5 indicates that the bulk of activity had fallen on the fishing vessel by 4 hours post-detonation. Granules could no longer be seen falling by the crew of the 5th Lucky Dragon at 8 hours post-detonation (Ts55).

The Rongelap people who were interviewed at the time of evacuation indicated to Sharp that the granules were noticed first at 5 hours postdetonation (Sh57). These people were about 210 km (130 miles) from Namu Island, Bikini Atoll, the origin or center of BRAVO fallout. Duration of the fallout was observed to be about 7 hours at Rongelap Island (Sh57). Using Eq. (2), we estimated granule size for Rongelap Island on the basis of observed fallout arrival and cessation times. The Rongelap granule size distribution was assumed to have the same shape as Bikini ash. Assuming that the activity of a granule was proportional to the 3.5 power of the granule size, we estimated the percent of total activity versus granule size at Rongelap (see Figure 6). For fallout at Rongelap Island, the size corresponding to median activity was about 150  $\mu$ m (6 x 10<sup>-3</sup> in.). The cumulative percent of total activity deposited on the surface of Rongelap Island versus time post-detonation (see Figure 7) was estimated by us using the same method described here for Bikini ash.

Fallout was not visible at Utirik Island. The first analysis of arrival time of BRAVO fallout, based on an assumed mean wind speed, was estimated by Sondhaus et al. to be 22 hours post-detonation (Cr56). Fallout cessation was estimated to be 34 hours post-detonation.

We estimated new values for fallout arrival and cessation times at Utirik Island on the basis of observations made by persons on the 5th Lucky Dragon, on Rongelap Island, and the military outpost on Rongerik Atoll. Fallout was first seen at 150 km (90 miles) at 3 hours post-detonation by the Japanese





1x10<sup>-3</sup> 9x10<sup>-2</sup>

Figure 7. Cumulative % of activity deposited on Rongelap Island vs ti

post-BRAVO detonation.

Island vs time

26 -

fishermen and lasted for 5 hours (Ts55). It was then seen at Rongelap Island at 210 km (130 miles) at 5 hours post-detonation and it lasted for 7 hours (Sh57). Fallout reported by military personnel stationed at Eniwetak Island, 270 km (170 miles) from ground zero, was first observed at about 7 hours post-detonation (Sh57), and it lasted into the night and perhaps into the next day (Sh57). From a linear regression fit of the values for distance versus time of arrival or distance versus time of duration, we extrapolated to arrive at estimates of fallout arrival and cessation times of 17 hours and 36 hours post-detonation, respectively, at Utirik Island. These derived values for fallout arrival and cessation times departed somewhat from the original estimates of Sondhaus.

On the basis of Eq. (2) and the new estimates of fallout arrival and cessation time, we determined a granule size distribution for the Utirik Island location. Based on Lavrenchik's summary (La56) we assumed that activity of a granule was proportional to the 3.5 power of the size, and used Eq. (2) to produce an activity versus granule size distribution (see Figure 8). The relative number of granules in each size class was based on the Bikini ash distribution (Su56). The granule size corresponding to the median activity at Utirik Island was about 14.5  $\mu$ m (6 x 10<sup>-4</sup> in.). The granule size distribution estimated by us was in agreement with the fact that fallout was not visible to the eye at Utirik. The cumulative percent of total activity deposited on the surface of Utirik Island (see Figure 9) was also estimated.

An adjustment for radioactive decay, for the period of time when fallout began to the time it reached the surface, was not accounted for by us when Figures 5, 7, and 9 were drawn. The activity referred to in these figures




Figure 8. Activity vs granule size for Utirik Island fallout.




Figure 9. Cumulative % of activity deposited on Utirik Island vs time post-BRAVO detonation.

was that which would have existed at the onset of fallout at each location. Correction for decay leads us to estimate a slightly steeper rise to the curve for cumulative percent activity versus time post-BRAVO detonation.

Eighteen Rongelap people went to Sifo Island, Ailingnae Atoll, to fish and to make copra (Sh57). They left Rongelap Island prior to or at about the time of the BRAVO detonation (Sh57). These people were located about 150 km (90 miles) from the detonation site at the time of fallout arrival, and thus, would have received fallout similar in granule size to that shown in Figure 4 for Bikini ash. Their location was further south than the 5th Lucky Dragon, however, and much less debris per unit area ultimately fell on Sifo Island. The fallout encountered by these 18 people was estimated to be off the centerline of maximum activity of the BRAVO cloud by about 30 km (20 miles).

d. A Simple Model for Exposure-Rate History at Rongelap, Sifo, and Utirik Islands. We combined the exposure-rate survey by the radsafe team of the USS PHILIP (OC68), the early fallout decay exponents indicated by Miller (OC68), and the time of arrival of fallout at Rongelap to estimate the exposure-rate history prior to evacuation (see Table 11). This exposure-rate history would not include the contribution from non-fission-fragment nuclides since it was an extrapolation which we based on the fission product decay exponent given by Miller (OC68). The total integrated exposure at 1 m above Rongelap Island, from the time of onset of fallout until evacuation, was  $4.6 \times 10^{-2}$  C kg<sup>-1</sup> (180 R). (This compares to  $7.2 \times 10^{-2}$  C kg<sup>-1</sup> (280 R) based on Bikini ash results; details of this estimate are given in upcoming sections.) We estimated the mean exposure rate to be  $3.1 \times 10^{-3}$  C kg<sup>-1</sup> h<sup>-1</sup> (12 R h<sup>-1</sup>) at 5 hours post-detonation. We assumed for this estimate of peak exposure rate that all the fallout was on the ground at the onset, that is, an instantaneous rise in exposure rate from zero to its maximum value.

The radsafe team of the USS PHILIP surveyed Sifo Island and the radsafe team of the USS RENSHAW surveyed Utirik Island during evacuation efforts (OC68). The exposure-rate histories for both islands were estimated from these survey results and are given in Table 11. As before, the exposure rates listed in Table 11 were based on Miller's decay estimates and we do not account here for buildup and peaking of radioactivity. Sondhaus reported that surveys at evacuation were performed with only one survey meter (AN/PDR-39), and that this instrument had not been calibrated recently and its operating condition was not known to be satisfactory at the time of use (Cr56). Sondhaus, therefore, based his estimates of external exposure on surveys made with calibrated instruments 7, 8, and 9 days after BRAVO detonation. Estimates of exposure in Table 11 which we made with evacuation survey results are, however, in agreement with estimates of cumulated exposure made by Sondhaus. Thus, we conclude the survey results by the radsafe teams were accurate.

A more refined estimate of external exposure-rate history and cumulated external whole-body absorbed dose performed by us was based on Bikini ash results as follows.

Table 11

BRAVO Fallout Exposure Rate Decline Based on Miller's (OC68) Decay Estimates

Rongelap Isla	nd, Rongelap A	toll	Utirik Island, Utirik Atoll					
fime Post-Detonation, hours	Exposure Rate R h-la	Cumulated Exposure, Rb	Time Post-Detonation, hours	Exposure Rate, R h-la	Cumulated Exposure, Rb			
5	12	-	17	0.46	-			
7	9.0	21	19	0.42	0.88			
9	7.3	37	21	0.39	1.7			
17	4.4	84	24	0.35	2.8			
20	3.8	96	27	0.31	3.8			
25	3.2	110	30	0.28	4.7			
30	2.7	130	35	0.24	6.0			
35	2.3	140	40	0.21	7.1			
40	2.0	150	45	0.19	8.1			
45	1.8	160	55	0.15	9.8			
54	1.50	180	75	0.10d	12			
			78	0.095	12			

#### Sifo Island, Ailingnae Atoll

Time Post-Detonation, hours	Exposure Rate, R h-1s	Cumulated Exposure, Rb	
3	6.4	-	
5	4.0	10	
7	3.0	17	<sup>a</sup> In air at about one meter above surface, multiply
9	2.4	23	by 2.58 x $10^{-4}$ to obtain C kg <sup>-1</sup> h <sup>-1</sup> .
15	1.6	35	bNumerical integration, multiply by 2.58 x 10-4
20	1.3	42	to obtain C kg <sup>-1</sup> .
25	1.1	48	CVillage average: maximum was 1.9 R h-1
30	0.88	53	USS PHILIP report (OC68).
35	0.76	57	dvillage average; maximum was 0.13 R h-1
40	0.66	61	USS RENSHAW report (OC68).
45	0.59	64	evillage average; maximum was 0.48 R h-1
50	0.53	67	USS PHILIP report (OC68).
57	0.45	70	
62	0.41	72	

## e. Activity and Exposure Rate History Based on Bikini Ash

i. Areal Activity and Exposure Rate from Nuclides Observed on Day 26. We used the Yamatera and Tsuzuki results to estimate BRAVO fallout activity on the ground and exposure rate prior to evacuation. We accounted for the fractionation of fission products, the presence of transuranic and activation products observed in Bikini ash, and a buildup followed by a decline of exposure rate. The Japanese results, summarized in Table 9, were used to generate the percent of fallout beta activity represented by each nuclide in Bikini ash (Table 12, column 2). The values in this column were based on the mean value of the Yamatera and Tsuzuki result if two values of a nuclide's beta activity in Bikini ash were reported. If not, only the one value was used. We calculated the day-26 exposure rates, at 1 m above the surface of a planar source of a unit area of Bikini ash activity (Table 12, column 3), for each nuclide. We based the estimate on data of Beck (Be80) or Kocher (Ko80) and results recorded in Table 12, column 2. Beck recorded factors to convert activity to exposure-rate for a number of particulate gamma-emitting fission products and for a number of particulate activation products and residual nuclear materials on the ground, as a result of weapons tests (Be80). By summing each nuclide's exposure rate relative to total Bikini ash activity per unit area, we estimated an exposure-rate conversion factor for Bikini ash to be  $1.12 \times 10^{-17}$  C kg<sup>-1</sup> s<sup>-1</sup> Bq<sup>-1</sup> m<sup>2</sup> (5.8 x  $10^{-3}~\mu R~h^{-1}~mCi^{-1}~km^2$ ). By inverting this factor and multiplying by the fraction of each nuclide's beta activity in Bikini ash (see Table 12, column 2), we estimated the beta activity of each nuclide per unit area, which was relative to a unit fallout exposure rate from Bikini ash.

Held (He65) reported a mean exposure-rate at Rongelap Island of about 2.9 x  $10^{-9}$  C kg<sup>-1</sup> s<sup>-1</sup> (40 mR h<sup>-1</sup>) at 26 days post-detonation. He also reported a storm with heavy rain two weeks post-detonation (He65). This was followed by a reduction in exposure rate greater than he would have expected from decay of BRAVO fallout. Glasstone (G162) reported a 40% reduction after 25 days for the BRAVO exposure rate which he attributed to weathering in certain areas of the Marshall Islands.

We estimated the reduction in exposure rate due to weathering at Rongelap Island on the basis of the survey taken by the USS PHILIP radsafe team. We assumed the survey at this early time post-detonation to be a measurement of unweathered fallout and assumed a decay exponent m=-1.4 from day 2.2 to day 26. This value for m was the mean value calculated for the decay of the nuclide mixture present at Rongelap 2.2 to 26 days post-detonation, which we based on the gamma decay of 142 nuclides tabulated in Table 13. Specifically, we accounted for the contribution to exposure rate from 1) the transuranic nuclides  $^{237}$ U and  $^{239}$ Np, 2) the neutron-induced nuclides,  $^{35}$ S and  $^{45}$ Ca, 3) the day-26 fission products which had fractionated according to Japanese results (Ya56, Ts55), and 4) the fission product and transuranic product precursors initially present on day 2.2. The day-26 value of the exposure rate which we extrapolated from the measurement made by the radsafe team on day 2.2 was 18% greater than that reported by Held. Thus, we estimated that, had the rainstorm not occurred, the mean unweathered exposure rate on Rongelap on day-26 would have been  $3.4 \times 10^{-9}$  C kg<sup>-1</sup> s<sup>-1</sup> (47 mR h<sup>-1</sup>).

Table 12 BRAVO Fallout Beta Activity Related to BRAVO Fallout Exposure Rate

		Day 26 Post-Detonation	
Nuclide	% of Bikini Ash Beta Activity	(mCi km <sup>-2</sup> ) Nuclide <sup>a</sup> (mCi km <sup>-2</sup> ) Bikini Ash	(mCi km <sup>-2</sup> ) Nuclide <sup>l</sup> (μR h <sup>-1</sup> ) Bikini Asl
89 <sub>Sr</sub>	1.3	3.3×10 <sup>-8</sup>	2.2x10 <sup>0</sup>
90 <sub>5</sub> ,	.013	$0.0 \times 10^{0}$	$2.2 \times 10^{-2}$
90 <sub>Y</sub>	.013	$3.5 \times 10^{-11}$	2.2x10 <sup>-2</sup>
91v	8.0	$5.0 \times 10^{-6}$	1.4x10 <sup>1</sup>
95 <sub>7</sub> -	6.2	$8.6 \times 10^{-4}$	$1.1 \times 10^{1}$
95 <sub>Nh</sub>	2.7	$3.9 \times 10^{-4}$	$4.7 \times 10^{0}$
103 <sub>P</sub> .,	5.0	4.5x10 <sup>-4</sup>	8.6x10 <sup>0</sup>
106 <sub>R</sub> .,	0.70	0.0x10 <sup>0</sup>	1.2x10 <sup>0</sup>
106ph	0.70	$2.7 \times 10^{-5}$	1.2x10 <sup>0</sup>
129 <sub>TA</sub>	0.35	$3.6 \times 10^{-6}$	$6.0 \times 10^{-1}$
129mm_	0.95	5.3x10 <sup>-6</sup>	1.6x10 <sup>0</sup>
132 <sub>Te</sub>	1.0	$3.8 \times 10^{-5}$	$1.7 \times 10^{0}$
1317	4.5	$3.3 \times 10^{-4}$	7.8x10 <sup>0</sup>
132 <sub>I</sub>	1.0	$4.2 \times 10^{-4}$	$1.7 \times 10^{0}$
140 <sub>Ba</sub>	- 5.0	$1.4 \times 10^{-4}$	8.6x10 <sup>0</sup>
140 <sub>La</sub>	6.0	$2.3 \times 10^{-3}$	1.0x10 <sup>1</sup>
141 <sub>Ce</sub>	8.4	$1.0 \times 10^{-4}$	$1.4 \times 10^{1}$
144Ce	1.7	$4.7 \times 10^{-6}$	$2.9 \times 10^{0}$
144Pr	1.7	$9.0 \times 10^{-6}$	$2.9 \times 10^{0}$
143 <sub>Pr</sub>	<b>16.</b>	2.7x1031	2.8x10 <sup>1</sup>
147 <sub>Nd</sub>	9.0	-2.3x10	
45 <sub>Ca</sub>	<b>20.20</b> - 4	1.6x10 <sup>-12</sup>	3.5x10 <sup>-1</sup>
237 <sub>U</sub>	<b>*20</b> •	4.6x10 <sup>-4</sup>	$= 3.5 \times 10^{1}$
239 <sub>Pu</sub> (α)	₫.0004	5.4x10-10	$6.9 \times 10^{-4}$
35 <sub>S</sub>	0.050	0.0x10 <sup>0</sup>	$28.6 \times 10^{-2}$

Divide by 1.94 a 10 Tto obtain

ii. Aseal Activity at Fallout Cessation. Using the above estimate of the mean unweathered exposure rate on day 26, we estimated the mean unweathered activity per unit area to be 1.0 x  $10^4$  Eq.  $(2.4 \times 10^2 \text{ mCi km}^{-2})$ . We made this estimate by multiplying 47 mR h  $^{-1}$  by 1900 and then multiplying this product by the activity per unit area per unit Bikini ash exposure rate (see Table 12, column 4).

Although the magnitudes of the uncertainties in the mean unweathered activity per unit area were not well defined, we thought that the estimates for Rongelap Island had a standard deviation based partly on the original Bikini Ash activity measurements (e.g., 95 Zr S.D. = ±20% (Is56)) and partly on the variation in exposure-rate measurements (e.g., radsafe team survey S.D. = ±20% (OC68)). A measurement of activity per unit area based on a single soil sample would be highly uncertain, because of random fallout deposition and because of physical mechanisms which move deposited fallout. This variation was dampened considerably by our use of exposure-rate survey results to estimate mean surface activity rather than use of a few gross beta measurements on soil. Our estimate of the standard deviation for the few soil samples collected by the radsafe team was ±140% of the mean value, based on the surface activity measurements reported by O'Conner (OC68) for surface samples taken shortly after detonation from one island in the Northern Marshall Islands. If soil sample results were used in the final estimate of dose, this large standard deviation would propagate through the calculations. Thus, we chose a method which offered greater certainty in the result.

Our estimate of each nuclide's mean unweathered activity per unit area of Rongelap Island was extrapolated back to 0.5 day post-detonation. Results are listed in Table 13. The 0.5-day post-detonation time was chosen as the time at which the fallout at Rongelap Island had effectively ceased (Sh57). We used first-order linear kinetics for serially related nuclide species (Bal0) and decay schemes from the Table of the Isotopes (Le78) in order to calculate the 0.5-day activity from the day-26 activity.

iii. Areal Activity of Nuclides Without Descendants in Bikini Ash. Many short-lived nuclides did not have daughter radionuclides present on day 26. We based the activity of these short-lived nuclides on the activity of a reference nuclide. Equation (3) was used by us to relate the unknown activity of the short-lived nuclide with no daughters present on day 26 to the known activity of a nuclide which had fractionated in the same fashion as the unknown. Thus, if no isobar was present on day 26, an isotope or an isotope of an isobar of the unknown was chosen to represent the fractionation behavior and be the reference nuclide for the estimate of activity per unit area. The equation used to relate activity of a short-lived nuclide to a reference nuclide was

$$A = \frac{B \lambda_a A_n}{\lambda_b B_n} , \qquad (3)$$

where

A = activity of nuclide A per unit area at time t post-detonation,

B = activity of nuclide B per unit area at time t post-detonation,

 $\lambda_a$  = decay constant of nuclide A,

 $\lambda_b$  = decay constant of nuclide B,

 $A_n$  = number of A atoms per unit fission at time t,  $B_n$  = number of B atoms per unit fission at time t.

The quantity  $A_n$  or  $B_n$  was calculated using 1) first-order linear kinetics equations, 2) fission yields for 14-MeV fission of  $^{238}$ U obtained from the evaluated nuclear data files of the National Nuclear Data Center

Table 13

Estimated Unweathered Activity on Surface and Exposure Rate at One Meter, Rongelap Island

Nuclide	Reference Nuclide	H+0.5 Day Activity per Unit Area, Ci km <sup>-2</sup> a	H+0.5 Day Exposure Rate, R h <sup>-1</sup> b	H+26 Day Activity per Unit Area, Ci km <sup>-2</sup> a	H+26 Day Exposure Rate, R h <sup>-1b</sup>
35 <sub>S</sub>	35 <sub>S</sub>	5.0×10 <sup>0</sup>	_	4.0x10 <sup>0</sup>	
45 Ca	45 Ca	1.8×100	2.5x10 <sup>-12</sup>	1.7x101	2.3x10 <sup>-12</sup>
75 <sub>Ge</sub>	95 <sub>Zr</sub>	4.9x100	2.3x10 <sup>-6</sup>	-	2.3810
77Ge	95 <b>Zr</b>	9.0×100	1.9x10 <sup>-4</sup>	_	-
77 <sub>As</sub>	95 <b>Zr</b>	1.5×10 <sup>1</sup>	1.9x10-6	_	_
78 <sub>As</sub>	95 <b>Zr</b>	5.7×10 <sup>1</sup>	1.2x10-3	_	_
77 <b>n</b> Se	95 <sub>Zr</sub>	4.7x10 <sup>-2</sup>	6.7x10 <sup>-8</sup>	_	_
81Se	95 <sub>Zr</sub>	$1.9 \times 10^{-1}$	2.6x10-6	_	_
81m <sub>Se</sub>	95 <sub>Zr</sub>	1.3x10 <sup>-1</sup>	2.6x10 <sup>-8</sup>	_	_
82 <sub>Br</sub>	95 <b>Zr</b>	2.8x10 <sup>-2</sup>	1.3×10 <sup>-6</sup>	_	• -
83 <sub>Br</sub>	95Zr	2.0010 ~	2.5×10 <sup>-4</sup>	_	-
84 <sub>Br</sub>	95 <sub>Zr</sub>	1.8x10 <sup>3</sup>	1.3x10 <sup>-6</sup>	-	-
83mKr	95Zr	4.6x10 <sup>-2</sup>	1.3x10 °	-	-
85mgr	95Zr	5.0x104	3.0x10 <sup>-2</sup>	-	-
87 <sub>Kr</sub>	95Zr	$7.9 \times 10^{3}$	2.7x10 <sup>-2</sup>	-	-
o/Kr	95Zr	$4.1 \times 10^{2}$	5.3x10 <sup>-3</sup>	-	-
88 <sub>Kr</sub>	95 <b>Zr</b>	8.9x10 <sup>3</sup>	2.7x10 <sup>-1</sup>	-	-
86 <sub>Rb</sub>	952r	5.7x10 <sup>-3</sup>	9.2x10 <sup>-9</sup>		-
88 <sub>Rb</sub>	91 <sub>Y</sub>	1.7×10 <sup>4</sup>	1.8x10 <sup>-1</sup>	-	-
89 <sub>Rb</sub>	89Sr	3.9×10 <sup>-9</sup>	1.4x10 <sup>-13</sup>		
895r	89Sr	1.5×10 <sup>2</sup>	3.8x10 <sup>-7</sup>	1.0x10 <sup>2</sup>	2.4x10 <sup>-7</sup>
90 <sub>Sr</sub>	90sr	1.0x10 <sup>0</sup>	-	1.0×10 <sup>0</sup>	-
91sr	91 v	5.7x10 <sup>4</sup>	7.1x10 <sup>-1</sup>	-	-
925-	91v	2.0x10 <sup>4</sup>	4.6x10 <sup>-1</sup>	-	-
89nav	89 <sub>Sr</sub>	$1.4 \times 10^{-3}$	2.4×10 <sup>-8</sup>	=	_
90 <sub>Y</sub> •	90 <sub>Y</sub>	1.4x!0 <sup>-1</sup>	$3.7 \times 10^{-11}$	1.0x10 <sup>0</sup>	2.5x10 <sup>-10</sup>
91y	91 Y	6.6x10 <sup>2</sup>	3.7x10 <sup>-5</sup>	6.6x10 <sup>2</sup>	3.7x10 <sup>-5</sup>
91 <del>m.y</del>	91 <sub>Y</sub>	3.4x10 <sup>4</sup>	$3.4 \times 10^{-1}$	-	· •
92 <b>y</b>	91 y	8.4x10 <sup>4</sup>	3.8x10 <sup>-1</sup>	_	-
93 <sub>Y</sub>	91 Y	7.0x104	1.1x10 <sup>-1</sup>	-	-
952r	95 <sub>Zr</sub>	6.8x10 <sup>2</sup>	9.6x10 <sup>-3</sup>	5.2x10 <sup>2</sup>	$7.2 \times 10^{-3}$
972r	95 <sub>Zr</sub>	4.0x10 <sup>4</sup>	1.3x10 <sup>-1</sup>	-	, <del>-</del>
95 <sub>Nb</sub>	95 <sub>Nb</sub>	3.1x10 <sup>-1</sup>	4.0x10 <sup>-6</sup>	2.1x10 <sup>2</sup>	$2.7 \times 10^{-3}$
95 <b>ธองก</b> อ	95Zr	6.4x10 <sup>1</sup>	1.4x10-4		-
2.7 m(N.D)	95Zr	4.4x10 <sup>4</sup>	5.4x10 <sup>-1</sup>	_	-
97 <sub>Nb</sub>	95ZT	4.4X1U~	5.3x10 <sup>-1</sup>	_	-
97 шүль	95zr	$3.9 \times 10^4$	4.5x10 <sup>-2</sup>	_	-
99 <sub>Mo</sub>	95Zr	1.5x10 <sup>4</sup>	4.3XIU ~		-
99wTc	95 <b>Zr</b>	1.0x10 <sup>4</sup>	2.2x10 <sup>-2</sup>	4.0x10 <sup>2</sup>	3.8×10 <sup>-3</sup>
103Ru	103 <sub>Ru</sub>	6.4x10 <sup>2</sup>	$5.9 \times 10^{-3}$	4.UX1U-	J.0810

Table 13 (cont'd)

Nuclid <b>e</b>	Reference Nuclide	H+O.5 Day Activity per Unit Area, Ci km <sup>-2</sup> a	H+0.5 Day Exposure Rate, R h-lb	H+26 Day Activity per Unit Area, Ci km <sup>-2</sup> a	H+26 Day Exposure Rate, R h <sup>-1b</sup>
105 <sub>Ru</sub>	95 <sub>Zr</sub>	2.8×10 <sup>4</sup>	4.1×10 <sup>-1</sup>	_	-
106 g.,	106 p.,	5.9x10 <sup>1</sup>	-	5.7x10 <sup>1</sup>	-
103 <del>ա</del> թե	103 <sub>2</sub> .,	6.3×10 <sup>2</sup>	1.2x10 <sup>-4</sup>		_
105թե	952~	1.7×10 <sup>4</sup>	2.5×10 <sup>-2</sup>	_	-
105 <sub>Rh</sub>	95 <sub>2</sub> r	7.9x10 <sup>3</sup>	3.5x10 <sup>-3</sup>	-	_
106ph	106 <sub>Rh</sub>	5.9x10 <sup>1</sup>	2.2x10-4	5.7x10 <sup>1</sup>	2.1x10 <sup>-4</sup>
109 <sub>Pd</sub>	952-	1.3×10 <sup>4</sup>	1.7x10 <sup>-4</sup>		-
lllpd	95 <sub>2r</sub>	2.7×10 <sup>3</sup>	1.2×10 <sup>-3</sup>	<del>-</del>	_
lllmpa	95 <sub>2+</sub>	$3.5 \times 10^{3}$	2.2x10 <sup>-2</sup>	<del>-</del>	_
112pa	957-	2.0x10 <sup>4</sup>	3.1x10 <sup>-4</sup>	_	-
109maa	957-	1.3x10 <sup>4</sup>	$9.3 \times 10^{-3}$	_	-
11140	957-	3.7×10 <sup>2</sup>	1.7x10 <sup>-4</sup>	_	
llimac	957 <del>~</del>	2.8x10 <sup>3</sup>	1.9×10 <sup>-5</sup>	<del>-</del>	_
1124~	957-	2.1x10 <sup>3</sup>	2.5x10 <sup>-2</sup>	_	-
1134~	957-	1.1x10 <sup>3</sup>	5.6x10 <sup>-3</sup>	_	_
1154~	957-	2.0×10 <sup>-6</sup>	2.0x10 <sup>-11</sup>	. <del>-</del>	_
LLDCA	952-	8.3x10 <sup>2</sup>	3.7×10 <sup>-3</sup>	_	_
115mca	957-	2.4×10 <sup>1</sup>	9.3x10 <sup>-6</sup>	_	_
117 <sub>Cd</sub>	95 <sub>7+</sub>	3.3x10 <sup>2</sup>	6.1x10 <sup>-3</sup>	_	-
117m	957 <del>-</del>	6.3x10 <sup>2</sup>	2.1x10 <sup>-2</sup>	_	_
118 <sub>Cd</sub>	95 <mark>2r</mark>	3.0x100	-	_	_
ll5w <sub>In</sub>	95 <sub>2r</sub>	4.6x10 <sup>2</sup>	$2.7 \times 10^{-3}$	_	<u>-</u>
li7 <sub>In</sub>	95 <b>z</b> r	1.4x10 <sup>3</sup>	1.8x10 <sup>-2</sup>	_	
ll7mIn	952r	2.1x10 <sup>3</sup>	3.0x10 <sup>-3</sup>	_	_
118 <sub>In</sub>	952r	3.0x10 <sup>0</sup>	1.3x10 <sup>-5</sup>	_	_
ll9msn	952r	7.9x10 <sup>-2</sup>	6.4x10 <sup>-9</sup>	<b></b>	-
121 <sub>Sn</sub>	952r	4.4x10 <sup>3</sup>	-	_	-
l21msn	952r	2.2×10 <sup>-2</sup>	1.4x10 <sup>-9</sup>	_	<b>-</b> '
123 <sub>Sn</sub>	95 <sub>2r</sub>	$4.3 \times 10^{-1}$	5.2×10 <sup>-8</sup>	_	_
123 <b>m</b> Sn	952r	3.1x10 <sup>-1</sup>	7.3x10 <sup>-7</sup>	_	_
125 <sub>Sn</sub>	95 <sub>2r</sub>	5.6x10 <sup>-1</sup>	3.1×10 <sup>-6</sup>	_	_
127 <sub>Sn</sub>	1321	3.8x10 <sup>2</sup>	1.3x10 <sup>-2</sup>	_	-
128 <sub>Sn</sub>	132 <sub>1</sub>	1.5x10 <sup>2</sup>	1.9x10 <sup>-3</sup>	_	-
125 <sub>Sb</sub>	95 <sub>Zr</sub>	3.5×10 <sup>0</sup>	2.8x10 <sup>-5</sup>	_	-
126 <sub>Sb</sub>	95 <sub>Zr</sub>	5.3x10 <sup>2</sup>	2.5x10 <sup>-2</sup>	_	_
127 <sub>Sb</sub>	1321	5.1x10 <sup>2</sup>	6.6x10 <sup>-2</sup>	_	-
128-	132 <sub>1</sub>	3.1XIO.	1.1x10 <sup>-1</sup>	_	-
128 <sub>Sb</sub> 128msb	1321	1.9x10 <sup>3</sup> 1.9x10 <sup>2</sup>	6.8x10 <sup>-3</sup>		

Table 13 (Cont'd)

Nuclide	Reference Nuclide	H+0.5 Day Activity per Unit Area, Ci km <sup>-2</sup> a	H+O.5 Day Exposure Rate, R h <sup>-1</sup> b	H+26 Day Activity per Unit Area, Ci km <sup>-2a</sup>	H+26 Day Exposure Rate, R h <sup>-11</sup>
129 <sub>Sb</sub>	132 <sub>I</sub>	3.2×10 <sup>4</sup>	7.9x10 <sup>-1</sup>	_	-
130ch	132 I	3.1x10 <sup>0</sup>	1.7x10 <sup>-4</sup>	_	-
131sh	132 <sub>T</sub>	5.2x10 <sup>-4</sup>	1.8x10 <sup>-8</sup>	_ ^	-
125 <del>m</del>	95 <sub>2.5</sub>	1.4x10 <sup>-3</sup>	2.0x10 <sup>-9</sup>	-	-
127 <sub>Te</sub>	132 т	2.4x10 <sup>3</sup>	2.4x10 <sup>-4</sup>	_	-
127mm	132 т	3.7×100	1.7x10 <sup>-6</sup>	_	_
129 <sub>Te</sub>	129Ta	1.4x10 <sup>4</sup>	1.5×10 <sup>-2</sup>	2.8x10 <sup>1</sup>	3.5x10 <sup>-5</sup>
129ma	129 m r.a	1.1×10 <sup>2</sup>	6.1x10 <sup>-5</sup>	7.6×10 <sup>1</sup>	6.7x10 <sup>-5</sup>
1317-	132 <sub>T</sub>	6.8×102	5.2x10 <sup>-3</sup>	_	•
131 mrs	132 <sub>T</sub>	3.1x10 <sup>3</sup>	7.9×10 <sup>-2</sup>	_	-
1327	132 <sub>Te</sub>	1.8x10 <sup>4</sup>	6.8x10 <sup>-2</sup>	7.9×10 <sup>1</sup>	$3.1 \times 10^{-4}$
133 <sub>T</sub>	132 <sub>T</sub>	2.7x101	$4.6 \times 10^{-4}$	-	
133 <del>ay</del> e	132 <u>1</u>	1.3×10 <sup>2</sup>	5.4x10 <sup>-3</sup>	_	· <del>-</del>
134 <sub>Te</sub>	132 <u>T</u>	1.4x10 <sup>1</sup>	2.2x10 <sup>-4</sup>	-	-
129 <sub>I</sub>	132 <sub>I</sub>	4.5x10 <sup>-6</sup>	5.6x10 <sup>-12</sup>	_	_
130 I	1321	2.6x100	1.1x10 <sup>-4</sup>	-	_
131 <sub>I</sub>	131 <sub>I</sub>	3.1x10 <sup>3</sup>	2.2x10 <sup>-2</sup>	3.5x10 <sup>2</sup>	$2.6 \times 10^{-3}$
1327	132 I	1.9x10 <sup>4</sup>	7.9x10 <sup>-1</sup>	8.0x10 <sup>1</sup>	3.4×10 <sup>-3</sup>
133 <sub>I</sub>	132 I	6.5×10 <sup>4</sup>	7.4x10 <sup>-1</sup>	-	-
133mg	132 <sub>I</sub>	1.1x101	3.1x10 <sup>-4</sup>	_	_
134 <sub>T</sub>	1321	6.5×10 <sup>2</sup>	3.1×10 <sup>-2</sup>	· <u>-</u>	_
135 I	132 I	7.8x10 <sup>4</sup>	2.1x100	_	-
131 my a	132 T	1.8x100	1.7×10-6	_	_
133 <sub>Xe</sub>	132 <sub>I</sub>	2.1x10 <sup>3</sup>	3.2x10 <sup>-3</sup>	<u>-</u>	-
133wy	132 T	3.2x10 <sup>2</sup>	4.5x10 <sup>-4</sup>	-	_
135 <sub>Xe</sub>	132 I	8.9x10 <sup>4</sup>	4.6x10 <sup>-1</sup>	-	-
135 <b>m</b> Xe	132 I	1.2x10 <sup>4</sup>	1.0x10 <sup>-1</sup>	-	_
135 <sub>Cs</sub>	132 I	1.4x10 <sup>-3</sup>	-	_	_
136 <sub>Cs</sub>	132 <sub>I</sub>	1.5×10 <sup>1</sup>	$6.0 \times 10^{-4}$	-	_
137 <sub>Cs</sub>	132 I	7.0x100	0.0x10	•••	-
138 <sub>Cs</sub>	132 <sub>I</sub>	8.7×10 <sup>-1</sup>	3.4x10 <sup>-5</sup>	-	-
137mm.	132 <sub>I</sub>	6.5×100	7.4×10 <sup>-5</sup>	_	_
139 <sub>Ba</sub>	132 т	$3.3 \times 10^{3}$	2.1x10 <sup>-3</sup>	-	-
140 <sub>Ba</sub>	140Ba	1.7x10 <sup>3</sup>	4.5×10 <sup>-3</sup>	4.0x10 <sup>2</sup>	1.1x10 <sup>-3</sup>
140La	140 <sub>La</sub>	3.1x10 <sup>2</sup>	1.2x10 <sup>-2</sup>	4.7×10 <sup>2</sup>	1.9x10 <sup>-2</sup>
141 <sub>La</sub>	141 Ce	3.0x10 <sup>4</sup>	2.1×10 <sup>-2</sup>	711810	

Table 13 (cont'd)

Nuclide	Reference Nuclide	H+0.5 Day Activity per Unit Area, Ci km <sup>-2a</sup>	H+0.5 Day Exposure Rate, R h <sup>-1</sup> b	H+26 Day Activity per Unit Area, Ci km <sup>-2a</sup>	H+26 Day Exposure Rate, R h <sup>-1b</sup>
142 <sub>La</sub>	141 Ce	2.6x10 <sup>3</sup>	1.1×10 <sup>-1</sup>	_	
1410-	141 ca	9.9x10 <sup>2</sup>	1.2x10 <sup>-3</sup>	6.6×10 <sup>2</sup>	7.9x10 <sup>-4</sup>
143ca	141 c-	1.9x104	9.2×10 <sup>-2</sup>	0.0x10	7.9810
1440-	144 Ce	1.4x10 <sup>2</sup>	4.0x10 <sup>-5</sup>	1.4x102	4.0x10 <sup>-5</sup>
143p.	143 <sub>Pr</sub>	9.2x10 <sup>2</sup>	1.5×10-10	1.3x103	2.2x10 <sup>-10</sup>
144Pr	144Pr	1.4202	7.4×10 <sup>-5</sup>	1.4x10 <sup>2</sup>	7.4×10 <sup>-5</sup>
144mpr	141 Ce	1.7*100	7.8x10 <sup>-7</sup>	1.4x10-	7.4×10
145pr	141 Ce	2.6x10 <sup>4</sup>	6.1x10 <sup>-3</sup> sr		-
146pr	141 Ce	2.0210		·	-
144Nd	141 Ce	2.6x10-3	5.2x10 <sup>-8</sup> .	-	_
144Nd	144 Ce	4.7x10 <sup>-17</sup>	3		
147 <sub>Nd</sub>	147Nd	3.5x10 <sup>3</sup>	8.9×10 <sup>-3</sup>	7.1x10 <sup>2</sup>	1.8x10 <sup>-3</sup>
149Nd	141 Ce	1.4×103	9.8x10-3	-	• -
147 <sub>Pm</sub>		5.7£10 <sup>-1</sup>	47×10-11	<del>-</del>	-
149pm -	741c	4.7x103	1.0x10	<del>-</del>	-
150 Pm	141 Ce	3.8x10 <sup>3</sup>	1.12	-	-
151 Pm	141 Ce	~ 3x10 <sup>3</sup>	2.5×10 <sup>-2</sup>	<u> </u>	-
151 Smg	141 Ce	5.1x10 <sup>-2</sup>	9.4x10-11	* ** <u>*</u>	-
153cm	141 Ce	1.3x10 <sup>3</sup>	$1.2 \times 10^{-3}$	-	-
156 <sub>Sm</sub>	141 Ce	9.6x102	1.9x10 <sup>-3</sup>	<del>-</del>	-
155 <sub>Eu</sub>	141 Ce	7.3x10 <sup>-1</sup>	6.8x10 <sup>-7</sup>	<u>=</u>	-
156 <sub>E1</sub> ,	-141 ca	3.5±101	8.0x10 <sup>-4</sup>		-
157Eu	141 Ce	6.5x102	$3.0 \times 10^{-3}$		
158 <sub>E</sub> .,	141 <sub>Ce</sub>	2.1x10 <sup>-2</sup>	$5.2 \times 10^{-7}$	<b>-</b> **	-
159 <sub>Gd</sub>	141 Ca	1.9×103	1.4x10 <sup>-3</sup>	<u> </u>	-
161 Th	141 <sub>Ce</sub>	9.82260	1.3×10 <sup>-6</sup>	•	<u>-</u>
237!	237 <sub>U</sub> .	2.6204	5.4×10 <sup>-2</sup>	1:3103	$3.8 \times 10^{-3}$
23911	្ទ 🚾 239ប្	120×10-2	8.1x10 <sup>-9</sup>		
237 <sub>Nn</sub>	237 <sub>II</sub>	Γ"t÷M"Ž⊸‰	4.0=10-12		_
239 <sub>Nn</sub>	239 <sub>Pa</sub>	1.0x105	3.0x40		_
239 <sub>Pu</sub>	239 <sub>Pu</sub>	4-3×10 <sup>-3</sup>	£5.7×10-10	1.2-14-2	4.3x10 <sup>-9</sup>
Fu	4 <b>- FU</b>	* 4-JXIV		J. ZASU	A.DXIO .

aMultiply by 3.7 x 104 to obtain Bq m<sup>-2</sup>.

bMultiply by 7.17 x 10<sup>-8</sup> to obtain C kg<sup>-1</sup> s<sup>-1</sup>.

(NNDC82), and 3) branching fractions and decay schemes from the seventh edition of the Table of Isotopes (Le78). Since each nuclide which we accounted for was the nth member of an isobaric chain, the number of atoms at time it would increase or decrease relative to the number present at time of detonation because of decay and in-growth phenomena of precursor isobars. Decay and in-growth phenomena were accounted for using the callowing equation which was originally described by Bateman (Balo) and later recast in a more general form by Skrable (Sk75). -

$$A_{n} = \sum_{i=1}^{i=n} \begin{bmatrix} j=n-1 \\ \pi \\ j=i \end{bmatrix}^{j=n} \begin{pmatrix} j=n-1 \\ \pi \\ j=i \end{pmatrix}^{j=n} \begin{pmatrix} \lambda_{j} \\ \lambda_{j} \end{pmatrix}^{j=n} \begin{pmatrix} \lambda_{j} \\ \mu=n \\ \mu=i \end{pmatrix}^{j=n} \begin{pmatrix} \lambda_{j} \\ \mu=n \\ \mu=n \end{pmatrix}^{j=n} \begin{pmatrix} \lambda_{j} \\ \mu=n \end{pmatrix}^{j=n} \begin{pmatrix} \lambda_{j} \\ \mu=n \\ \mu=n \end{pmatrix}^{j=n$$

where

An = the number of atoms of the nth member of an isobaric chain at time t post-detonation per unit fission,

isobaric chain per unit fission,  $\lambda_i = \text{decay constant of the } j^{\text{th}}$  isobar, fj, j+1 branching fraction of the jth isobar leading to the

creation of the j<sup>th</sup> + 1 isobar, t = time post-BRAVO detonation.

The use of Eqs. (3) and (4) allowed us to calculate all fission products present at the time of exposure (see Table 13). We also included in Table 13, the important precursor transuranics and activation products which were based on the Tsuzuki measurements on day 26 (Ts55) and the use of parentdaughter transformation equations given by Bateman (Bal0).

Non-Fission-Fragment Nuclides Not Accounted for. The nuclides which may have been present at some level but which remain unaccounted for are 7Be, 24Na, 56m; 55me, 59me, 57Co, 58Co, 66Co, 64Cu, 67Cu, 240Np, 241Am, and 242Cm. The decay of two thort-lived activation products, 24Na and 56Mn, might have accounted for some of the exposure rate metaured at 2.2 days at Rongelap Island. Borg tabulated the photon energy spectrum from a BRAVO fallout sample collected at Rongelap Island. (BoJ6). The fallout sample was reported to be applied at 4 days post-determined that the spectrum has a minor analyzed at 4 days post-detonation. We determined that the spectrum has a minor peak energy ground 850 keV. The intensity of the peak was about 5 to 7% of the total photon intensity. The nuelide Mn has a characteristic photon at 847 keV but so do Manther nuclides which may have been present (RSIC73). Mather indicated the these short-lived activation products may account for as such as 20 to 50% at the photon intensity during the first day the detonations however, most 24Ns and 25m activity would be observed close to the soint of creation (Ma56). Lathe case of BRAVO this was near Namu Island, Bikini Atoll. Therefore, we doubt that 24Na and 56Mm contributed much photon exposure at

We approximated the exposure rate contribution from all notaccounted-for nuclides at distances for from the detonation site on the basis of

fallout studies at the Nevada Test Site (Hi81). An approximation of the exposure due to all not-accounted-for nuclides listed above would be less than 1% of the total from day 0.5 to day 2.2 post-detonation. This may not be a good comparative assessment since no study of a device like BRAVO was reported at the Nevada Test Site. The fourth shot in the Castle Series, UNION, was a 9.5-MT device with a number of characteristics similar to those of BRAVO, including its fission-to-fusion ratio. The gross gamma decay was measured from 0.2 day post-detonation, unlike BRAVO for which gross gamma decay was not reported until after 5.5 days had passed. From 0.2 day to 0.3 day the decay exponent was -1.5. From 0.2 day to 2.2 days it was -1.3. From 2.2 days to 26 days it was -1.4. These values of gamma-decay exponents were comparable to those we estimated from Bikini ash extrapolations. Significant amounts of not-accounted-for nuclides in the activity produced by UNION might have caused us to estimate a wide difference in decay exponents. Thus, we conclude that not-accounted-for nuclides contributed very little to the dose received by persons at Rongelap, Utirik, or Sifo Islands.

v. Input Data to Kinetics Equations. A check on input data for activity per unit fission versus time was made by us. The theoretical activity of unfractionated iodine isotopes following 10,000 thermonuclear fissions of 238U as given by Crocker (Cr65) was compared to the activity at any time following fission of 238U with 14-MeV neutrons. Our comparison calculation was based on decay schemes from the Table of the Isotopes (Le78), independent yield data for fission products from the National Nuclear Data Center (NNDC82), and Eq. (4). The Crocker yields were based on a slightly different neutron energy spectrum than that used in the calculation made here. The kinetics equations, verified yield data, and our decay scheme approach led to results remarkably similar to those of Crocker. Our estimated maximum difference was approximately 50% for 134I activity at two hours post-detonation. All iodine isotope activities were within 20% of the Crocker estimate at about 10 hours post-detonation.

vi. Exposure Rate on Day 0.5 and Surface Roughness Effects. We estimated the mean exposure rate from all the nuclides given in Table 13 to be 7.9 x  $10^{-7}$  C kg<sup>-1</sup> s<sup>-1</sup> (1.1 x  $10^1$  R h<sup>-1</sup>) on day 0.5 post-detonation. We include in this estimate the contribution from noble gas nuclides. Exclusion of the noble gas activity yields 7.0 x  $10^{-7}$  C kg<sup>-1</sup> s<sup>-1</sup> (9.7 R h<sup>-1</sup>) for the exposure rate at day 0.5. The exposure-rate history at Rongelap Island based on the particulate activity in Bikini Ash, has been plotted in Figure 10.

Photons emitted by fallout on the surface may have been intercepted by overlying layers of soil or by surface structures. Because of surface roughness effects, the radsafe survey team may have reported an exposure rate which is an underestimate of one which is produced by a plane source. This would have caused us to underestimate surface activity at Rongelap because Bikini ash activity was normalized to the Rongelap exposure-rate survey made by the radsafe team. The effect of fallout particles penetrating into Rongelap's coral surface was approximated by comparing Beck's values for mR h<sup>-1</sup>  $\mu$ Ci<sup>-1</sup> m<sup>2</sup> for activity on a smooth flat plane, to a plane where activity was distributed depthwise with a relaxation length of 0.16 g cm<sup>-2</sup> (Be80). By relaxation length we mean the depth at which the activity in overlying layers of soil is reduced

by a factor e. We estimate that this translates into a 15% underestimate of the activity present if one assumes that the exposure rate was due to a smooth flat plane of activity rather than one distributed depthwise.

Since we normalized activity intake to urine activity excreted, the effect of this underestimate of activity per unit area was inconsequential on thyroid dose estimates. It would, of course, impact on the relative amounts entering the body through the ingestion versus inhalation versus skin absorption pathways but not the total amount taken in. Since in our assessment the ingestion pathway dominated, the impact on thyroid-absorbed dose would be negligible.

vii. Integrated Exposure and Whole-Body Absorbed Dose. The total integrated exposure from the onset of fallout to evacuation was  $7.2 \times 10^{-2}$  C kg<sup>-1</sup> (280 R) 1 m above the surface of Rongelap Island. In order to make this estimate, we accounted for the buildup of fallout on the ground as previously described and accounted for the photons emitted from all nuclides listed in Table 13. A plot of the integrated exposure versus time was given as Figure 11. From the decay exponents derived from Bikini ash decay and the exposure-rate survey results obtained by the radsafe teams of the USS RENSHAW and the USS PHILIP, exposure rates versus time post-detonation were plotted (Figure 10) and integrated (Figure 11) for Sifo and Utirik Islands. The total integrated exposure at 1 m above the surface of Sifo Island was 4.4 x  $10^{-2}$  C kg<sup>-1</sup> (170 R) and at Utirik Island 4.1 x  $10^{-3}$  C kg<sup>-1</sup> (16 R). These exposures were for the period of time from the onset of fallout to evacuation, March 1-3, 1954.

Although our air exposure estimates at early times postdetonation differ from those of Cronkite et al. (Cr56), they are in agreement with Cronkite's whole-body and external thyroid absorbed-dose estimates. The Marshallese reported no significant deviation from routine living patterns (see interviews recorded by Sharp, Sh57). In a previous document by Greenhouse and Miltenberger (Gr77), it was shown that external exposure inhomogeneities due to various living patterns (such as fishing in the lagoon, standing on the beach, etc.) could be accounted for by multiplying the mean exposure rate for the island at 1 m above the surface by a factor of 0.73 to obtain whole-body absorbeddose rate. They included in this multiplicative factor a correction for the electron density difference between air and tissue. We used another multiplicative factor of 0.95 to convert exposure to whole-body dose. We used this additional factor to account for attenuation and buildup of the photon flux as it traversed the body. The energy spectra we assumed was the one given by Borg (Bo56) for BRAVO fallout at 4 days. Thus, we estimate the external whole-body dose at Rongelap to have been 1.9 gray (190 rad). This compares to 1.75 gray (175 rad) which was estimated by Cronkite et al.

## 2. Radioactivity in Food, Water Supplies, and Air

a. Activity in Cistern Water. The main water supplies at Rongelap, eight cisterns, were reported to each contain 0.23 m of water during the later part of March and early April 1954 (Sh57). Water was drawn from six of these cisterns at Rongelap for gross beta analysis on March 2, 1954 (see report of the radsafe team USS PHILIP, OC68), and one other cistern was reported empty. Each




Figure 10. Exposure-rate histories for Rongelap, Sifo, and Utirik Islands based on Bikini ash characteristics.




Figure 11. Integrated exposure vs time.

cistern opening measured about  $0.65~\text{m}^2$  and was fed by means of galvanized metal sheeting used for catching rainwater (Figure 12). A little rain was reported on the afternoon of March 1, 1954 (Sh57). We assumed that the additional cistern catchment area did not contribute water or activity to the cistern.

Results of the analysis for gross beta-activity concentration in cistern water ranged from 1.8 x  $10^5$  to 2.0 x  $10^6$  Bq  $l^{-1}$  (0.005 to 0.054  $\mu$ Ci  $ml^{-1}$ ) with a mean of 5.0 x  $10^5$  Bq  $l^{-1}$  (0.027  $\mu$ Ci  $ml^{-1}$ ) at 50 hours post-detonation (0C68). The fallout from Castle series coral surface bursts including BRAVO was reported as being barely soluble in water (Ka66). BRAVO fallout, which was collected with mixtures of rain and sea spray, lost only 20 to 50% of the iodine activity to the liquid phase (Ka66). The serviceman at Rongerik Atoll examined the terrestrial fallout under a microscope and reported that the sand-like granules were not soluble in water on the microscope slide (Sh57). Therefore, most BRAVO activity and a good portion of the radioiodine activity probably remained with the fallout particles at the bottom of a cistern.

We extrapolated the 50-hour post-detonation beta-activity concentrations back to 0.5 day post-detonation using decay characteristics for Bikini ash components. The range for gross beta-activity concentrations was 1.0 x  $10^6$  to 1.2 x  $10^7$  Bq  $\ell^{-1}$  (0.027 to 0.31  $\mu$ Ci ml<sup>-1</sup>) and the mean was 2.9 x  $10^6$  Bq  $\ell^{-1}$  (0.078  $\mu$ Ci ml<sup>-1</sup>). At 0.5 day, a total of 3.7 x  $10^{10}$  Bq m<sup>-2</sup> (1 Ci m<sup>-2</sup>) of Bikini ash gross beta activity was estimated by us as the sum of the activity of all nuclides listed in Table 13. Given the area of a cistern opening, we calculated that the average cistern contained 8.3 m<sup>3</sup> of water if all the Bikini ash activity was in the liquid phase. This water volume would be necessary to dilute the activity to the level reported by the radsafe team. We estimate that this was about 55 times greater than the observed water volume of the cisterns as previously indicated by Sharp (Sh57). Assuming only 20% of the iodine activity in



Figure 12. A cistern at Rongelap Island.

the liquid phase (the lowest estimate reported, Ka66), no activity in the liquid phase from all other nuclides, and the appropriate activity of each iodine isotope in Bikini ash at 50 hours post-detonation, leads us to the same estimate of cistern water content as reported by Sharp and others, about 0.15 m<sup>3</sup> (Sh57).

On the basis of 1) Bikini ash radioiodine activity per unit area estimates given in Table 13, 2) a 20% release of iodine activity from fallout granules to cistern water, and 3) an average cistern water volume of 0.15 m<sup>3</sup>, we estimated the radioiodine activity concentrations for cisterns located at Rongelap Island. A range of cistern water activity at Rongelap Island was estimated to be between 0.2 and 2 times the average values given in Table 14. We based this estimate on the range reported for gross beta-activity measurements (OC68). The instantaneous activity concentrations given in Table 14 were adjusted for the rate of buildup of activity during fallout deposition.

The activity concentration in Sifo Island cistern water was assumed by us to be 12% the values given at Rongelap. This was based on a ratio of mean exposure rate at both islands at seven hours post-detonation and the ratio of the fractions of total granule activity on the surface of fallout granules.

Kawahara reported that the water removed the iodine near the surface of the fallout granule (Ka66). We assumed that small granules had a greater fraction of total activity near the surface than did large granules, because of the surface-area to volume ratio. We estimated a different portion of iodine activity released from granules sized differently from those at Rongelap by assuming spherical-shaped granules and a mean granule radius for each island.

The cisterns and wells at Utirik Island were observed to be covered as reported by the evacuation team aboard the USS RENSHAW (OC68). Interestingly, the range of cistern water activity at Utirik Island was 1.2 x  $10^5$  to 5.5 x  $10^5$  Bq  $\ell^{-1}$  (0.003 to 0.02  $\mu$ Ci ml<sup>-1</sup>), as computed for 0930 on March 3, 1954, from two different cistern water samples taken on March 9 (OC68). The mean Utirik cistern water activity was about one third the mean cistern water activity reported for Rongelap Island at the same time. The roof over each cistern apparently was not effective in preventing contamination.

We assumed that activity in the liquid phase in two cisterns would be directly proportional to the ratio of exposure rates near each cistern as well as to the ratio of the fraction of total activity on the surface of the mean granule size in each cistern. This approach leads us to expect roughly equal radioiodine activity in the liquid phase in cisterns at Rongelap and Utirik Islands at the same point in time. This was largely due to a greater proportion of activity on the surface of fallout granules in the Utirik cistern. Thus, on the basis of expected activity vs measured activity, the cistern coverings at Utirik did protect the drinking water to some degree, perhaps reducing its activity by as much as a factor of 3. This reduction was based on the observed average activity ratio between Utirik and Rongelap cistern water.

b. Activity Ingested with Drinking Water. Prior to evacuation of Rongelap, many weeks of drought were reported by Sharp (Sh57). In the weeks pre

Table 14

Average Estimate of Radioiodine Activity in Cistern Water and Time After the BRAVO Detonation

			Rongela	p Island, µC	i cm-3a			
Hours Po BRAVO	st- 135 <sub>I</sub>	<sup>134</sup> 1	133 <sub>I</sub>	133m <sub>I</sub>	132 <sub>I</sub>	<sup>131</sup> I	130 <sub>I</sub>	<sup>129</sup> 1
5.5	4.0x10 <sup>-2</sup>	2.5×10 <sup>-2</sup>	1.8x10 <sup>-2</sup>	2.6x10 <sup>-4</sup>	3.8×10 <sup>-3</sup>	6.8x10 <sup>-4</sup>	9.6×10 <sup>-7</sup>	3.8x10 <sup>-13</sup>
7.0	$1.3 \times 10^{-1}$	$2.4 \times 10^{-2}$	$6.7 \times 10^{-2}$	$4.1 \times 10^{-4}$	1.6x10 <sup>-2</sup>	2.7x10 <sup>-3</sup>	3.6x10 <sup>-6</sup>	2.7x10 <sup>-12</sup>
9.0	$1.0 \times 10^{-1}$	5.5x10 <sup>-3</sup>	$6.4 \times 10^{-2}$	$1.2 \times 10^{-4}$	$1.6 \times 10^{-2}$	$2.7 \times 10^{-3}$	3.3x10 <sup>-6</sup>	$3.2 \times 10^{-13}$
12	$6.8 \times 10^{-2}$	5.7x10 <sup>-4</sup>	5.7x10 <sup>-2</sup>	9.6x10 <sup>-6</sup>	1.7x10 <sup>-2</sup>	2.7x10 <sup>-3</sup>	$2.3 \times 10^{-6}$	3.9x10 <sup>-13</sup>
17.5	$3.8 \times 10^{-2}$	$7.0 \times 10^{-6}$	$4.8 \times 10^{-2}$	1.5x10 <sup>-7</sup>	1.6x10 <sup>-2</sup>	2.7x10 <sup>-3</sup>	1.9x10 <sup>-6</sup>	4.2x10 <sup>-1</sup>
20	2.9x10 <sup>-2</sup>	9.5x10 <sup>-7</sup>	$4.5 \times 10^{-2}$	2.2x10 <sup>-8</sup>	1.5x10 <sup>-2</sup>	2.7x10 <sup>-3</sup>	1.7x10 <sup>-6</sup>	4.4x10 <sup>-13</sup>
25	1.6x10 <sup>-2</sup>	1.7x10 <sup>-8</sup>	$3.8 \times 10^{-2}$	$5.4 \times 10^{-10}$	$1.4 \times 10^{-2}$	2.7x10 <sup>-3</sup>	1.2x10 <sup>-6</sup>	$4.7 \times 10^{-1}$
30	$1.0 \times 10^{-2}$	7.8x10-10	$3.1 \times 10^{-2}$	1.2x10 <sup>-11</sup>	$1.4 \times 10^{-2}$	$2.7 \times 10^{-3}$	8.1x10 <sup>-7</sup>	4.7x10 <sup>-1</sup>
35	$6.0 \times 10^{-3}$	-	2.6x10 <sup>-2</sup>	-	$1.3 \times 10^{-2}$	2.6x10 <sup>-3</sup>	6.9x10 <sup>-7</sup>	4.7x10 <sup>-13</sup>
40	3.5x10 <sup>-3</sup>	6.5x10 <sup>-13</sup>	$2.2 \times 10^{-2}$	5.9x10 <sup>-15</sup>	1.2x10 <sup>-2</sup>	2.6x10 <sup>-3</sup>	5.7x10 <sup>-7</sup>	4.7x10 <sup>-1</sup>
45	1.9x10 <sup>-3</sup>	-	$1.9 \times 10^{-2}$	-	1.2x10 <sup>-2</sup>	2.6x10 <sup>-3</sup>	3.8x10 <sup>-7</sup>	4.7x10 <sup>-13</sup>
50	$1.1 \times 10^{-3}$	$4.9 \times 10^{-16}$	1.6x10 <sup>-2</sup>	6.6x10 <sup>-18</sup>	1.1x10 <sup>-2</sup>	$2.6 \times 10^{-3}$	2.2x10 <sup>-7</sup>	4.7x10 <sup>-1</sup>
54	7.4x10 <sup>-4</sup>	-	1.5x10 <sup>-2</sup>	-	$1.1 \times 10^{-2}$	$2.6 \times 10^{-3}$	$2.0 \times 10^{-7}$	4.7x10 <sup>-13</sup>
			Sifo	Island, <sub>H</sub> Ci	ст-За			
3.5	1.2×10 <sup>-2</sup>	1.5x10 <sup>-2</sup>	4.1x10 <sup>-3</sup>	3.5×10 <sup>-4</sup>	8.6×10 <sup>-4</sup>	1.5x10 <sup>-7</sup>	2.4x10 <sup>-7</sup>	8.3x10 <sup>-14</sup>
5.5	1.9x10 <sup>-2</sup>	1.2x10 <sup>-2</sup>	$8.6 \times 10^{-3}$	1.2x10 <sup>-4</sup>	1.8x10 <sup>-3</sup>	$3.3 \times 10^{-4}$	4.6x10 <sup>-7</sup>	1.8x10 <sup>-13</sup>
7.0	$1.6 \times 10^{-2}$	$3.0 \times 10^{-3}$	$8.3 \times 10^{-3}$	5.1x10 <sup>-5</sup>	2.0x10 <sup>-3</sup>	$3.4 \times 10^{-4}$	4.5x10 <sup>-7</sup>	3.4x10 <sup>-1</sup>
9.0	1.2x10 <sup>-2</sup>	$6.8 \times 10^{-4}$	$8.0 \times 10^{-3}$	1.5x10 <sup>-5</sup>	2.0x10 <sup>-3</sup>	$3.4 \times 10^{-4}$	4.1x10 <sup>-7</sup>	4.0x10 <sup>-1</sup>
12	$8.4 \times 10^{-3}$	7.1x10 <sup>-5</sup>	$7.1 \times 10^{-3}$	$1.2 \times 10^{-3}$	2.1x10 <sup>-3</sup>	$3.4 \times 10^{-4}$	2.9x10 <sup>-7</sup>	4.9x10 <sup>-1</sup>
17.5	4.5x10 <sup>-3</sup>	8.4x10 <sup>-7</sup>	$5.8 \times 10^{-3}$	1.8x10 <sup>-8</sup>	1.9x10 <sup>-3</sup>	$3.4 \times 10^{-4}$	2.3x10 <sup>-7</sup>	5.0x10 <sup>-1</sup>
20	$3.6 \times 10^{-3}$	1.2x10 <sup>-7</sup>	$5.6 \times 10^{-3}$	2.7x10 <sup>-9</sup>	$1.9 \times 10^{-3}$	$3.4 \times 10^{-4}$	2.1x10 <sup>-7</sup>	5.4x10 <sup>-1</sup>
25	2.0x10 <sup>-3</sup>	2.1x10 <sup>-9</sup>	$4.7 \times 10^{-3}$	6.5x10 <sup>-11</sup>	$1.7 \times 10^{-3}$	$3.4 \times 10^{-4}$	1.5x10 <sup>-7</sup>	5.8x10 <sup>-1</sup>
30	1.2x10 <sup>-3</sup>	9.7x10 <sup>-11</sup>	$3.9 \times 10^{-3}$	1.5x10 <sup>-12</sup>	$1.7 \times 10^{-3}$	3.4x10-4	1.0x10 <sup>-7</sup>	5.8×10 <sup>-1</sup>
35	$7.5 \times 10^{-4}$	-	$3.2 \times 10^{-3}$	-	1.6x10 <sup>-3</sup>	3.2x10 <sup>-4</sup>	8.6x10 <sup>-7</sup>	5.8x10 <sup>-1</sup>
40	$4.3 \times 10^{-4}$	8.1x10 <sup>-14</sup>	$2.7 \times 10^{-3}$	7.3x10-16	$1.5 \times 10^{-3}$	$3.2 \times 10^{-4}$	7.1x10 <sup>-8</sup>	5.8×10 <sup>-1</sup>
45	2.4x10 <sup>-4</sup>	-	$2.4 \times 10^{-3}$	-	1.5x10 <sup>-3</sup>	3.2x10 <sup>-4</sup>	4.7x10 <sup>-8</sup>	5.8x10 <sup>-1</sup>
50	1.4x10 <sup>-4</sup>	6.1x10 <sup>-17</sup>	$2.0 \times 10^{-3}$	8.2x10 <sup>-19</sup>	$1.4 \times 10^{-3}$	$3.2 \times 10^{-4}$	2.7x10 <sup>-8</sup>	5.8x10 <sup>-1</sup>
54	$9.2 \times 10^{-5}$	-	1.9x10 <sup>-3</sup>	-	1.4x10 <sup>-3</sup>	3.2x10 <sup>-4</sup>	2.5x10 <sup>-8</sup>	5.8x10 <sup>-1</sup>
62	3.8x10 <sup>-5</sup>	2.9x10 <sup>-21</sup>	$1.4 \times 10^{-3}$	-	1.3x10 <sup>-3</sup>	$3.2 \times 10^{-4}$	2.0x10 <sup>-8</sup>	$5.8 \times 10^{-1}$
		,	<u> Utirik</u>	Island, pCi	сщ-За			
17.5	1.3×10 <sup>-3</sup>	2.3x10 <sup>-7</sup>	1.6x10 <sup>-3</sup>	5.0x10 <sup>-4</sup>	5.3x10 <sup>-4</sup>	9.0x10 <sup>-5</sup>	6.3x10 <sup>-8</sup>	1.4x10 <sup>-13</sup>
20	5.8x10-3	1.9x10 <sup>-7</sup>	9.0x10 <sup>-3</sup>	4.4x10 <sup>-9</sup>	2.8x10 <sup>-3</sup>	5.4x10 <sup>-4</sup>	3.4x10 <sup>-7</sup>	9.4x10 <sup>-1</sup>
25	5.3×10 <sup>-3</sup>	5.7×10 <sup>-9</sup>	1.3×10 <sup>-2</sup>	4.7x10 <sup>-9</sup>	5.0x10 <sup>-3</sup>	9.0x10 <sup>-4</sup>	4.0x10 <sup>-7</sup>	1.6x10 <sup>-1</sup>
30	3.3×10 <sup>-3</sup>	2.6x10-10	1.0x10 <sup>-2</sup>	4.0x10-12	5.0x10 <sup>-3</sup>	9.0x10 <sup>-4</sup>	2.7x10 <sup>-7</sup>	1.6x10 <sup>-1</sup>
35	2.0x10 <sup>-3</sup>	-	8.7×10 <sup>-3</sup>	-	4.3x10 <sup>-3</sup>	8.7x10 <sup>-4</sup>	2.3x10 <sup>-7</sup>	1.6x10 <sup>-1</sup>
40	1.2x10-3	2.2x10 <sup>-13</sup>	$7.3 \times 10^{-3}$	2.0x10 <sup>-15</sup>	4.0x10-3	8.7x10 <sup>-4</sup>	1.9x10 <sup>-7</sup>	1.6x10 <sup>-1</sup>
45	$6.3 \times 10^{-4}$	_	$6.3 \times 10^{-3}$	_	4.0x10 <sup>-3</sup>	8.7x10 <sup>-4</sup>	1.3x10 <sup>-7</sup>	1.6x10 <sup>-1</sup>
50	$3.7 \times 10^{-4}$	1.6x10 <sup>-16</sup>	5.3x10 <sup>-3</sup>	2.2x10 <sup>-18</sup>	$3.7 \times 10^{-3}$	8.7x10 <sup>-4</sup>	7.3x10 <sup>-8</sup>	1.6x10 <sup>-1</sup>
54	$2.5 \times 10^{-4}$	-	$5.0 \times 10^{-3}$		3.7x10 <sup>-3</sup>	8.7x10 <sup>-4</sup>	6.7×10 <sup>-8</sup>	1.6x10 <sup>-1</sup>
75	2.3x10 <sup>-5</sup>	_	2.4x10 <sup>-3</sup>		2.5x10-3	8.7x10 <sup>-4</sup>	1.8x10 <sup>-8</sup>	1.6x10 <sup>-1</sup>

<sup>a</sup>Multiply by 3.7 x  $10^{7}$  to obtain Bq  $\chi^{-1}$ .

ceding the BRAVO contamination, water from cisterns was rationed to "one pint cup per person each day" (Sh57), or (assuming US liquid measure) 470 cm³ of water per person per day. This water was used to make tea and coffee and was directly ingested (Sh57). Naidu, in the late 1970s, observed an average intake of about 1000 cm³ of coconut water per day for adults, 800 cm³ for adolescents, and 500 cm³ for 1- to 3-year-old children (Na80). In addition, the Marshallese consumed coconut tree sap, about 700 cm³ per day for adults, 600 cm³ for adolescents, and 400 cm³ for 1- to 3-year-old children (Na80). Not including the water intake from ingested food and by oxidation of food, a 70-kg adult would ingest 2000 cm³ per day of fluids and a 10-year-old child 1400 cm³ per day in order to balance normal water losses in a temperate climate (ICRP74). Therefore, it is likely that each person drank most of his or her daily cistern water ration of 470 cm³ in order to maintain water balance. People reported that they drank this water despite the off taste and color produced by fallout contamination (Sh57).

We assumed that 150 cm<sup>3</sup> of water was taken with each meal. At Rongelap Island, this was assumed to occur at 5.5 (lunch), 12 (dinner), 24 (breakfast), 30 (lunch), 38 (dinner), and 50 (breakfast) hours post-detonation. We have found no report to indicate that rationing was necessary at Sifo or Utirik Island. Based on water balance, it was assumed that one pint per person per day was the cistern water intake at these islands as well. We assumed that the 150-cm<sup>3</sup> intake of water with meals occurred at Sifo Island at the same meal times assumed for Rongelap Island and at 57 hours (lunch) post-detonation as well. At Utirik, we assumed that the 150-cm<sup>3</sup> mealtime cistern water intake occurred at 24, 31, 38, 50, 57, 64, and 76 hours post-detonation. Evacuation at Utirik was completed at 78 hours post-detonation (OC68). These assumed cistern water intakes led to estimates of ingested radioiodine activity which are tabulated in Table 15.

The values in Table 15 represent a conservative estimate of radioiodine activity intake from this pathway since we assumed that all activity in the liquid phase was due only to iodine isotopes. Typically, 50 to 80% of the radioiodine would settle out of cistern water along with a good portion of the total fallout activity. Given the range of measured beta activity in each cistern on Rongelap on March 31, 1954, we estimate an upper limit to drinking water intake at twice the values in Table 15. The upper limit estimate is about 4% of the expected intake if one compares to the urine derived intake estimate. We did not consider further refinement of the cistern water pathway leading to radioiodine intake, since the result would be not an increase in the iodine intake, but rather a decrease. Thus, we would not achieve the boundary condition that iodine in urine at day-17 be accounted for.

c. Activity in Food. Preparation and consumption of food in the open was, and still is, a common practice among the Marshallese people; therefore, fallout was ingested directly with food. Persons interviewed at Rongelap indicate that food had a strange taste (like cement) just prior to the 1954 evacuation (Sh57). Fallout had the appearance of table salt and flour, taro powder or chalk dust, and blackened the sky as if night were approaching (Sh57). One family group reported to Sharp that the only food not dusted by fallout was coconut meat and milk (Sh57). Most families reported eating in the usual outdoors style

Table 15

Average Estimate of Activity Intake from Cistern Water

	Rongelap Island		Sifo Is	land	Utirik Island		
	Вq	μCi	Bq	μCi	Вq	μCi	
135 <sub>I</sub> 134 <sub>I</sub> 133 <sub>I</sub> 133m <sub>I</sub> 132 <sub>I</sub> 131 <sub>I</sub>	7.8×10 <sup>5</sup>	21	1.7×10,5	4.7	6.7x10 <sup>4</sup>	1.8	
134 <sub>I</sub>	1.4×10 <sup>5</sup>	3.8	$6.7 \times 10^{4}$	1.8	-	-	
133 <sub>I</sub>	$1.0 \times 10^{6}$	28	1.6x10 <sup>5</sup>	4.2	2.6x10 <sup>5</sup>	7.0	
133m <sup>I</sup>	$1.5 \times 10^{3}$	0.040	$6.7 \times 10^{2}$	0.018	-	-	
132 <sub>I</sub>	4.1x10 <sup>5</sup>	11	$5.9 \times 10^4$	1.6	$1.4 \times 10^{5}$	3.9	
1311	7.8x10 <sup>4</sup>	2.1	$1.1 \times 10^{4}$	0.29	3.4x10 <sup>4</sup>	0.93	

and prepared foods such as cooked pumpkin, starch tubes, rice, and bread products over open campfires (see Figure 13). In addition, fish was normally dried on open air racks prior to intake.

d. Activity Ingested with Meals. Most of the activity fell at Rongelap Island during preparation of the midday and evening meals. Fallout was visible even on peoples' skin, and caused itching, sneezing, and coughing (Sh57). The living pattern of the Marshallese led to direct ingestion of BRAVO fallout in amounts which can be estimated on the basis of meal intake and if the lill activity measured in urine is used as a normalization point. The living patterns at Utirik and Sifo were similar to those at Rongelap (Na80). No alteration in daily routine was thought to occur and no attempt at removing visible fallout from food was reported by persons evacuated from Rongelap or Sifo Islands (Sh57).

Fallout was distributed on the surface of Rongelap Island at 0.5 day post-detonation at a level of about 3.7 x  $10^{10}$  Bq m<sup>-2</sup> (1 Ci m<sup>-2</sup>) (see Table 13). This was in agreement with soil sample results obtained on March 8, 1954 (OC68). On the basis of a conversion factor given by the persons doing the soil analysis (OC68), the measured soil specific activity was converted to activity per unit area at 0.5 day post-detonation for comparison purposes. Their value for Rongelap Island based on four samples, was 2.0 x  $10^{10}$  ± 2.7 x  $10^{10}$  Bq m<sup>-2</sup> (0.53 ± 0.72 Ci m<sup>-2</sup>).

Random soil sampling was done at Utirik Island, Sifo Island, Eniwetak Island, and other islands at Rongelap, Ailingnae, Utirik, and Rongerik Atolls (OC68). At the end of fallout deposition at Utirik Island, which we estimated to be 1.5 days post detonation, the surface activity based on one soil sample was 1.0 x  $10^{10}$  Bq m<sup>-2</sup> (0.27 Ci m<sup>-2</sup>). This very large result does not agree with estimates we derive from exposure-rate measurements. At this activity per unit area, the exposure rate 1.5 days post-detonation should have been 8.3 x  $10^{-4}$  C kg<sup>-1</sup> h<sup>-1</sup> (3.2 R h<sup>-1</sup>), however, the island average was estimated



Figure 13. Food prepared and consumed outdoors.



Figure 13. (Continued.)

from the survey to be 7.2 x  $10^{-5}$  C kg<sup>-1</sup> h<sup>-1</sup> (0.28 R h<sup>-1</sup>) (0C68). We recognize that soil analysis results exhibit orders of magnitude variations even when soil is taken from nearly the same spot (0C68). We assumed the exposure-rate surveys were correct for Utirik and we ignored this one soil activity result which would lead us to estimate very high thyroid doses. At Sifo Island, the fallout cloud passed by at 0.33 day post-detonation. The activity per unit area at Sifo, measured with one soil sample, was 1.2 x  $10^9$  Bq m<sup>-2</sup> (0.032 Ci m<sup>-2</sup>). At Eniwetak Island, the BRAVO cloud was estimated to have passed by at 0.67 day post-detonation and the measured surface activity at that time, based on two samples, was 1.2 x  $10^{10}$  ± 7.8 x  $10^9$  Bq m<sup>-2</sup> (0.32 ± 0.21 Ci m<sup>-2</sup>).

In Table 16 we tabulated activity per unit area and time post-detonation for Rongelap Island for nuclides contributing significantly to thyroid dose. We based this tabulation on Bikini ash nuclide composition and we normalized the activity per unit area to the exposure-rate surveys made by the survey teams. In this table, the instantaneous surface activities during fall-out deposition reflect the buildup discussed earlier. We estimated the activity per unit area of selected nuclides at Utirik and Sifo Islands by using the ratio of the exposure rates at Rongelap and Utirik. The exposure-rate ratio for Rongelap and Sifo Islands was 3.0 to 1.0 and for Rongelap and Utirik Islands, 9.5 to 1.0 after the cessation of fallout.

Although BRAVO debris was not highly soluble in water, calcium carbonate and hydrated calcium oxide (the matrix in which BRAVO fallout was entrained) were both highly soluble in acid (Co72). Therefore, ingestion of BRAVO debris resulted in release of radioiodines and other nuclides trapped in the granules because of the acid environment of the stomach. The mass and volume of BRAVO fallout granules were insignificant relative to the normal amount of food eaten per meal, which was about 400 g for adults (Ev66). The mass of BRAVO fallout per square meter at Rongelap Island was 4.4 g and the volume of this mass was 1.9 cm<sup>3</sup>, about four tenths the volume of a teaspoon. These estimates at Utirik Island were 0.46 g m<sup>-2</sup> and 0.20 cm<sup>3</sup> m<sup>-2</sup>. For Sifo Island it was 1.5 g m<sup>-2</sup> and 0.48 cm<sup>3</sup> m<sup>-2</sup>. These mass and volume per unit area estimates were for the time at which all fallout was on the ground. They were based on the specific activity and specific gravity of Bikini ash measured on April 23, 1954 (Ki56). The values for Utirik and Sifo Islands were estimated by ratio of their exposure rate to that at Rongelap Island after fallout cessation at the same time.

The outside area used to prepare food for the midday or evening meals at Rongelap may have been within several square meters for a family (see Figure 13). Boiling and frying were done over an open fire fueled by coconut shells. Green breadfruit, fish, and nuts were roasted over a coconut-shell- or husk-fueled fire, when the husk had turned to coals. Ground ovens, used for baking breadfruit, were normally protected with banana leaf coverings against dirt and dust (Na80). These outdoor preparation and cooking modes allowed significant amounts of BRAVO debris to be mixed with food.

The amount of fallout dust ingested per meal would depend upon the amount that fell into utensils and plates during preparation and during consumption. Resuspension and subsequent deposition on food and preparation of food on

Table 16
Surface Activity and Times After BRAVO

	n 8.					1	longelap I	land, uCi	<u>-2a</u>						
Nuclide	3.5	et Detonat 5.5	7.0	9.0	12	17.5	20	25	30	35	40	45	50	54	75
135 <sub>I</sub>	-	4.5×10 <sup>4</sup>	1.5x10 <sup>5</sup>	1.1x10 <sup>5</sup>	7.8x104	4.4x10 <sup>4</sup>	3.3×10 <sup>4</sup>	1.8x104	1.1x104	6.9x10 <sup>3</sup>	4.0x103	2.2x10 <sup>3</sup>	1.3x103	3.6x10 <sup>2</sup>	7.9x10l
134 <u>1</u>	- '	2.9x104	2.8x10 <sup>4</sup>	6.3x10 <sup>3</sup>	6.5x10 <sup>2</sup>	8.0x100	1.1x10 <sup>0</sup>	2.0x10 <sup>-2</sup>	8.9x10 <sup>-4</sup>	_	-	-	-	-	-
133 <sub>I</sub>	-	2.1x10 <sup>4</sup>	7.7x10 <sup>4</sup>	7.3x10 <sup>4</sup>	6.5x104	5.5x104	5.2x104	4.4x104	3.6x10 <sup>4</sup>	3.0x104	2.5x10 <sup>4</sup>	2.2x104	1.8x104	1.7×104	8.3x10 <sup>3</sup>
132 <u>T</u>	_	$4.4 \times 10^{3}$	1.8x104	1.8x104	1.9x104	1.8x104	1.7×104	1.6x104	1.5x104	1.5x104	1.4x104	$1.4 \times 10^{4}$	1.3x104	1.2x104	1.0x10 <sup>4</sup>
131 <sub>I</sub>	-	7.8x10 <sup>2</sup>	3.1x10 <sup>3</sup>	3.1x10 <sup>3</sup>	3.1x10 <sup>3</sup>	3.0x10 <sup>3</sup>	3.0x10 <sup>3</sup>	3.0x10 <sup>3</sup>	$3.0 \times 10^{3}$	$3.0 \times 10^{3}$	3.0x10 <sup>3</sup>				
132Te	-	4.8x10 <sup>3</sup>	1.9x104	1.8x104	1.8x104	1.7x104	1.7x104	1.6x104	1.5x104	1.5x104	1.4x104	1.4x104	1.3x10 <sup>4</sup>	1.2x104	1.0x104
131 <b>=</b> Te	-	9.1x10 <sup>2</sup>	$3.5 \times 10^{3}$	3.3x10 <sup>3</sup>	3.1x10 <sup>3</sup>	2.7x10 <sup>3</sup>	2.6x10 <sup>3</sup>	2.3x10 <sup>3</sup>	2.0x10 <sup>3</sup>	1.8x10 <sup>3</sup>	1.6x10 <sup>3</sup>	1.4x10 <sup>3</sup>	1.3x10 <sup>3</sup>	1.2x10 <sup>3</sup>	7.2x10 <sup>2</sup>
							Sifo Isla	ınd, µCi m	2.						
135 <u>1</u> 134 <u>1</u>	3.8x10 <sup>4</sup> 4.9x10 <sup>4</sup>	6.0x10 <sup>4</sup> 3.9x10 <sup>4</sup>	5.0x10 <sup>4</sup> 9.3x10 <sup>3</sup>	3.6x10 <sup>4</sup> 2.1x10 <sup>3</sup>	2.6x10 <sup>4</sup> 2.2x10 <sup>2</sup>	1.5x10 <sup>4</sup> 2.6x10 <sup>0</sup>	1.1x10 <sup>4</sup> 3.6x10 <sup>-1</sup>	6.0x10 <sup>3</sup> 6.6x10 <sup>-3</sup>	3.6x10 <sup>3</sup> 2.9x10 <sup>-4</sup>	2.3x10 <sup>3</sup>	1.3x10 <sup>3</sup>	7.3x10 <sup>2</sup>	4.3x10 <sup>2</sup>	1.2×10 <sup>2</sup>	2.6x101
133 <sub>I</sub>	1.3x10 <sup>4</sup>	2.8x10 <sup>4</sup>	2.5x10 <sup>4</sup>	2.4x10 <sup>4</sup>	2.2x10 <sup>4</sup>	1.8x10 <sup>4</sup>	1.7x10 <sup>4</sup>	1.5x10 <sup>4</sup>	1.2x10 <sup>4</sup>	9.9x103	8.3x10 <sup>3</sup>	7.3x10 <sup>3</sup>	6.0x10 <sup>3</sup>	5.6x10 <sup>3</sup>	2.7x10 <sup>3</sup>
132 <sub>I</sub>	2.8x10 <sup>3</sup>	5.9x10 <sup>3</sup>	6.0x10 <sup>3</sup>	6.0x10 <sup>3</sup>	6.3x10 <sup>3</sup>	6.0x10 <sup>3</sup>	5.6x10 <sup>3</sup>	5.3x10 <sup>3</sup>	5.0x10 <sup>3</sup>	5.0x10 <sup>3</sup>	4.6x10 <sup>3</sup>	4.6x10 <sup>3</sup>	4.3x10 <sup>3</sup>	4.0x10 <sup>3</sup>	3.3x10 <sup>3</sup>
1311	4.5x10 <sup>2</sup>	1.0×103	1.0x10 <sup>3</sup>	1.0x10 <sup>3</sup>	1.0x10 <sup>3</sup>	1.0x103	1.0x103	1.0x103	1.0x103	9.9x10 <sup>2</sup>					
132 <u>T</u> e	2.9x103	6.4×10 <sup>3</sup>	6.3×10 <sup>3</sup>	6.0x10 <sup>3</sup>	6.0x103	5.6x10 <sup>3</sup>	5.6x10 <sup>3</sup>	5.3x10 <sup>3</sup>	5.0x10 <sup>3</sup>	5.0x10 <sup>3</sup>	4.6x10 <sup>3</sup>	4.6x10 <sup>3</sup>	4.3x10 <sup>3</sup>	4.0x103	3.3×10 <sup>3</sup>
131 <b>=</b> Te	5.7x10 <sup>2</sup>	1.2x10 <sup>3</sup>	1.2x10 <sup>3</sup>	1.1x10 <sup>3</sup>	1.0x10 <sup>3</sup>	8.9x10 <sup>2</sup>	8.6x10 <sup>2</sup>	7.6×10 <sup>2</sup>	6.6x10 <sup>2</sup>	6.0x10 <sup>2</sup>	5.3x10 <sup>2</sup>	4.6x10 <sup>2</sup>	4.3x10 <sup>2</sup>	4.0x102	2.4x10 <sup>2</sup>
							Utirik Isl	and, μCi π	-2a						
135 <sub>1</sub>	_	-	_	_	_	4.7x10 <sup>2</sup>	2.1x103	1.9x103	1.2x10 <sup>3</sup>	7.3x10 <sup>2</sup>	4.2×10 <sup>2</sup>	2.3x102	1.4x10 <sup>2</sup>	3.8x101	8.3x100
134 I	_	-	-	_	-	8.5×10 <sup>-2</sup>	7.0×10 <sup>-2</sup>	2.1x10 <sup>-3</sup>	9.4x10 <sup>-5</sup>	-	-		_		-
133 <u>T</u>	-	-	_	-	_	5.7x10 <sup>2</sup>	3.2×10 <sup>3</sup>	4.6x10 <sup>3</sup>	3.8x10 <sup>3</sup>	3.2x10 <sup>3</sup>	2.6x103	2.3x10 <sup>3</sup>	1.9x10 <sup>3</sup>	1.8x10 <sup>3</sup>	8.7x10 <sup>2</sup>
132 <u>1</u>	-	_	-	-	-	1.9x10 <sup>2</sup>	1.1x103	1.7x103	1.6x103	1.6x10 <sup>3</sup>	1.5x103	1.5x103	1.4x103	1.3x10 <sup>3</sup>	1.1x103
1311	-	-	-	-	-	3.3x10 <sup>1</sup>	2.0x10 <sup>2</sup>	$3.3 \times 10^{2}$	$3.3 \times 10^{2}$	$3.2 \times 10^{2}$	3.2x10 <sup>2</sup>	3.2x10 <sup>2</sup>	3.2x102	3.2x10 <sup>2</sup>	3.2x10 <sup>2</sup>
132 <sub>Te</sub>	-	-	-	-	-	1.8x10 <sup>2</sup>	1.1x10 <sup>3</sup>	1.7x10 <sup>3</sup>	1.6x10 <sup>3</sup>	1.6x10 <sup>3</sup>	1.5x10 <sup>3</sup>	1.5x10 <sup>3</sup>	$1.4 \times 10^{3}$	1.3x10 <sup>3</sup>	1.1x103
131 <b>≡</b> Te	-	~	-	-	-	2.8x101	1.6x10 <sup>2</sup>	2.4x10 <sup>2</sup>	2.1x10 <sup>2</sup>	1.9x10 <sup>2</sup>	1.7x10 <sup>2</sup>	1.5x10 <sup>2</sup>	$1.4 \times 10^{2}$	1.3x10 <sup>2</sup>	7.6x101

<sup>4</sup>Multiply by 3.7 x  $10^4$  to obtain Bq m<sup>-2</sup>.

dusty surfaces would be secondary pathways. During the midday meal at Rongelap Island, BRAVO dust probably fell directly onto plates and on the surfaces of fish which were drying in the open. The area of one plate exposed to BRAVO fallout plus the area of a small fish is approximately 0.04 m<sup>2</sup>. If a 30-minute lunch interval beginning at 5 hours post-detonation was assumed to be the plate and fish exposure interval to dust, then about 40 mg would fall on this eating area at Rongelap Island. During the preparation of the evening meal, about 0.1 m<sup>2</sup> of surface area was assumed as the family food preparation area exposed to dust during fallout deposition. On the average, each family was estimated to consist of about 4.5 people (Sh57). Therefore an additional 100 mg of BRAVO debris per family member was estimated to be consumed with the evening meal at 12 hours post-detonation.

As indicated by our reassessment of the urine result, a 3.4 x  $10^6$  Bq (93  $\mu$ Ci) intake of  $^{131}$ I was estimated on the basis of measured  $^{131}$ I in urine on day 17. This was assumed to be a total per adult ingestion intake of about 1.1 x  $10^6$  Bq (30  $\mu$ Ci) at 5.5 hours post-detonation and 2.2 x  $10^6$  Bq (60  $\mu$ Ci) at 12 hours post-detonation. Therefore, intake with midday and evening meals provided us with a reasonable pathway in terms of the mass of fallout ingested since 140 mg corresponded to 3.3 x  $10^6$  Bq (90  $\mu$ Ci) of  $^{131}$ I.

In Table 17 we have presented the estimated activity intake (with meals) of selected nuclides at Rongelap Island. An adult male was assumed to take in 3.4 x  $10^6$  Bq (93 µCi) of  $^{131}$ I in order to normalize with urine data. Other nuclides were estimated by normalizing the  $^{131}$ I intake to Bikini ash composition which, in turn, was normalized to exposure-rate measurements. Activity intake with meals was modified to agree with meal intakes appropriate for body weight for the different age members of the exposed populations. This modification was based on an exponential relationship between total element intake and body weight which we derived from data tabulated in the ICRP Publication 23, Reference Man (ICRP74).

Activity would have been ingested directly with meals at Utirik Island during breakfast, lunch, and dinner on March 2, 1954, due to fallout on plates, on food preparation areas, and on the food itself. As mentioned previously, Sharp reported that fallout particles were not visible to the eye at Utirik Island (OC68). Fallout activity was measured in cisterns even though cisterns were reported as covered, which indicated to us that BRAVO dust may have contaminated the surface of covered food. Essentially, our estimates indicate that the majority of the BRAVO activity fell during the time breakfast was prepared and eaten. Assuming the same food eating and preparation areas as at Rongelap, and the same family size, then about 30 mg of BRAVO dust was ingested with the breakfast meal at 24 hours post-detonation.

Resuspension followed by redeposition was considered secondary to direct deposition prior to and during breakfast. Our estimates of particle deposition velocity and reports of resuspension factors (ICRP80) indicate that the entire fallout would have to be resuspended into the air many times over in order to make resuspension an important pathway for internal thyroid dose. Dust falling from the cloud and ingested with lunch and evening meals at Utirik was

Table 17

Average Estimate of Activity Intake with Meals

			Rongelap I	sland, µCi	. <u>a</u>	•		
Age	Body Weight, kg	<sup>135</sup> I	<sup>134</sup> 1	133 <sub>I</sub>	132 <sub>I</sub>	<sup>131</sup> I	132 <sub>Te</sub>	131m <sub>Te</sub>
Adult Male	70	3400	1200	2100	550	93	550	80
Adult Female	58	3000	1000	1800	480	81	480	70
Fourteen-Year-Old	50	2800	980	1700	450	76	450	66
Twelve-Year-Old	40	2500	890	1600	410	69	410	59
Nine-Year-Old	30	2300	800	1400	370	62	370	54
Six-Year-Old	20	2100	720	1300	330	56	330	48
One-Year-Old	10	1900	660	1200	300	51	300	44
			Utirik Is	land, µCi				
Adult Male	70	140	0.00028	280	100	20	100	15
Adult Female *	58	120	0.00024	240	87	17	87	13
Fourteen-Year-Old	50	115	0.00023	230	82	16	82	12
Twelve-Year-Old	40	100	0.00021	210	74	15	74	11
Nine-Year-Old	30	94	0.00019	190	67	13	67	10
Six-Year-Old	20	84	0.00017	170	60	12	60	9
One-Year-Old	10	77	0.00015	150	55	11	55	, 8
			Sifo Isla	and, µCi				
Adult Male	70	1200	780	560	120	20	130	24
Adult Female	58	1000	670	490	100	17	115	21
Fourteen-Year-Old	50	980	640	460	98	16	110	20
Twe lve-Year-Old	40	890	580	410	89	15	97	18
Nine-Year-Old	30	800	520	380	80	13	87	16
Six-Year-Old	20	720	470	340	72	12	78	14
One-Year-Old	10	660	430	310	66	11	72	13

<sup>&</sup>lt;sup>a</sup>Multiply by 3.7  $\times$  10<sup>4</sup> to obtain Bq.

not considered, since fallout activity in the air would have ceased substantially by those times.

At Sifo Island, most of the fallout fell in one midmorning hour between breakfast and lunch times. Assuming the same food preparation area as at Rongelap Island, but no deposition on plates while eating, values for intake were estimated. We assumed that 60 mg of BRAVO dust was ingested at 5.5 hours post-detonation. These dust particles would have been large, 320 micrometers average size, and visible on food preparation surfaces.

e. Activity Concentrations in Air. Mean air concentration estimates of activity of selected nuclides were based on fallout deposition rates. The percent of activity deposited per minute at various times at Rongelap Island was estimated by us from Eq. (2). Fall velocity corresponding to granule size was taken from Figure 8 of Holland's report (Ho63). We used an estimate of fall velocity because we did not know the height of the column of fallout over each island.

Air activity concentrations at various times were assumed by us to be 1) directly proportional to the fraction of total activity deposited per minute, 2) directly proportional to the total activity on the ground at the end of fallout (decay corrected back to various points in time), and 3) inversely proportional to fall velocity of granules. We applied these same assumptions to surface activity results for Sifo and Utirik Islands as well. Our values for air concentration at all three islands and times post-BRAVO detonation are tabulated in Table 18. The cumulated air activity concentrations for Rongelap Island which we derived from Bikini ash were about one third the cumulated air activity concentration results of Peterson (Pe81).

The air activity concentrations for Utirik Island relative to those at Rongelap Island might be expected to be less because of the exposurerate differences that were observed and because of greater dispersion of the fallout cloud. The fall velocity of a granule corresponding to the activity median size was greater by a factor of 95 at Rongelap Island than at Utirik Island, while the exposure rate after deposition differed by only a factor of 9.5. If one hypothesizes that the deposition intervals at both islands were the same, and the air activity concentrations were equal, then 95 times less exposure rate at Utirik Island would be anticipated, not 9.5. The fallout cloud duration at Utirik was 2 to 3 times longer than at Rongelap based on granule size considerations. However, it was not long enough to account for the measured exposurerate results. Therefore, the air concentration at Utirik Island must have been greater than at Rongelap (see <sup>131</sup>I, Table 18). Given that fallout was not visible and exposure-rate measurements were accurate, longer fallout duration and higher air concentrations at Utirik relative to Rongelap were likely. The total fallout activity on the surface of Rongelap Island was still ten times greater than at Utirik Island, largely as a result of the greater rate at which granules fell to the surface of Rongelap.

f. Activity Intake By Inhalation. Airborne activity intakes were dependent upon breathing rate of individuals during fallout cloud passage. We assumed breathing rate to be proportional to body mass as derived from reference

Table 18

Air Activity Concentration of Selected Nuclides

		Ronge	lap Island,	µСі cm <sup>-3</sup> а			
Hours Post BRAVO	135 <sub>I</sub>	134 <sub>I</sub>	133 <sub>I</sub>	132 <sub>I</sub>	131 <sub>I</sub>	132 <sub>Te</sub>	131m <sub>Te</sub>
5.06	5.4x10-6	3.8x10 <sup>-6</sup>	2.5x10 <sup>-6</sup>	5.4x10 <sup>-7</sup>	1.0x10 <sup>-7</sup>	6.0x10 <sup>-7</sup>	1.2x10 <sup>-7</sup>
5.27	9.0x10 <sup>-6</sup>	5.8x10 <sup>-6</sup>	$4.3 \times 10^{-6}$	$8.9 \times 10^{-7}$	1.7x10 <sup>-7</sup>	1.1x10 <sup>-6</sup>	$2.0 \times 10^{-7}$
5.51	1.3x10 <sup>-5</sup>	7.0x10 <sup>-6</sup>	6.0x10 <sup>-6</sup>	1.4x10 <sup>-6</sup>	2.5×10 <sup>-7</sup>	1.5x10 <sup>-6</sup>	2.9x10 <sup>-7</sup>
5.78	2.1×10 <sup>-5</sup>	9.6x10 <sup>-6</sup>	$9.6 \times 10^{-6}$	2.2x10 <sup>-6</sup>	$4.0 \times 10^{-7}$	2.4x10 <sup>-6</sup>	$4.7 \times 10^{-7}$
6.10	9.8x10 <sup>-6</sup>	$3.4 \times 10^{-6}$	5.0x10 <sup>-6</sup>	1.1x10 <sup>-6</sup>	2.1x10 <sup>-7</sup>	1.2x10 <sup>-6</sup>	2.3x10 <sup>-7</sup>
6.48	7.5×10 <sup>-6</sup>	2.4x10 <sup>-6</sup>	3.9x10 <sup>-6</sup> 7.1x10 <sup>-7</sup>	9.2×10 <sup>-7</sup>	1.6×10 <sup>-7</sup>	9.7x10 <sup>-7</sup>	1.9x10 <sup>-7</sup>
6.94	1.5x10 <sup>-6</sup> 3.1x10 <sup>-7</sup>	2.7x10 <sup>-7</sup>	7.1x10 7 1.7x10 <sup>-7</sup>	1.7x10 <sup>-7</sup> 4.2x10 <sup>-8</sup>	3.0x10 <sup>-8</sup> 7.4x10 <sup>-9</sup>	1.8x10 <sup>-7</sup> 4.4x10 <sup>-8</sup>	$3.4 \times 10^{-8}$
7.51 8.23	1.3x10 <sup>-7</sup>	5.3x10 <sup>-8</sup> 1.2x10 <sup>-8</sup>	7.5x10 <sup>-8</sup>	2.0x10 <sup>-8</sup>	7.4x10 9 3.4x10 9	4.4x10 0 2.0x10 -8	8.2x10 <sup>-9</sup> 3.8x10 <sup>-9</sup>
9.21	3.4×10 <sup>-8</sup>	1.8x10 <sup>-9</sup>	2.3×10 <sup>-8</sup>	6.1x10 <sup>-9</sup>	1.1x10 <sup>-9</sup>	6.1x10 <sup>-9</sup>	1.7x10 <sup>-9</sup>
10.6	6.6x10 <sup>-9</sup>	1.4x10-10	4.7x10 <sup>-9</sup>	1.3x10 <sup>-9</sup>	$2.3 \times 10^{-10}$	1.3x10 <sup>-9</sup>	2.4x10 <sup>-1</sup>
		Sif	o Island, μ	Ci cm-3a			
3.07	6.4x10 <sup>-7</sup>	1.2x10 <sup>-6</sup>	2.3x10 <sup>-7</sup>	4.2x10 <sup>-8</sup>	8.3x10 <sup>-9</sup>	5.5x10-8	1.1x10-8
3.20	$9.5 \times 10^{-7}$	1.7x10 <sup>-6</sup>	$3.5 \times 10^{-7}$	6.5x10 <sup>-8</sup>	1.3x10 <sup>-8</sup>	8.5x10 <sup>-8</sup>	1.7x10 <sup>-8</sup>
3.36	1.4x10 <sup>-6</sup>	2.4x10 <sup>-6</sup>	$5.4 \times 10^{-7}$	1.0x10 <sup>-7</sup>	2.0x10 <sup>-8</sup>	$1.3 \times 10^{-7}$	2.6x10 <sup>-8</sup>
3.54	1.1x10 <sup>-6</sup>	3.1x10 <sup>-6</sup>	8.3x10 <sup>-6</sup>	1.5x10 <sup>-7</sup>	2.9x10 <sup>-8</sup>	1.9x10 <sup>-7</sup>	3.8x10 <sup>-8</sup>
3.75	1.0x10 <sup>-6</sup> 7.5x10 <sup>-7</sup>	1.4x10 <sup>-6</sup> 8.5x10 <sup>-7</sup>	4.0x10 <sup>-7</sup> 3.0x10 <sup>-7</sup>	7.8x10 <sup>-8</sup> 5.9x10 <sup>-8</sup>	1.5x10 <sup>-8</sup> 1.1x10 <sup>-8</sup>	9.9x10 <sup>-8</sup> 7.1x10 <sup>-8</sup>	1.9x10 <sup>-8</sup>
4.01 4.33	1.3x10 /	1.3x10 <sup>-7</sup>	5.4x10 <sup>-8</sup>	1.1x10 <sup>-8</sup>	2.0x10 <sup>-9</sup>	1.3x10 <sup>-8</sup>	2.5x10 <sup>-9</sup>
4.73	3.0×10 <sup>-8</sup>	2.4x10 <sup>-8</sup>	1.3x10 <sup>-8</sup>	2.7x10 <sup>-9</sup>	4.8x10 <sup>-10</sup>	3.1x10 <sup>-9</sup>	6.0x10 <sup>-1</sup>
5.26	1.9×10 <sup>-8</sup>	1.1x10 <sup>-8</sup>	8.2×10 <sup>-9</sup>	1.8x10 <sup>-9</sup>	3.1x10 <sup>-10</sup>	2.0x10 <sup>-9</sup>	3.8x10 <sup>-1</sup>
6.02	2.8×10 <sup>-9</sup>	1.0x10 <sup>-9</sup>	1.3x10 <sup>-9</sup>	3.0x10 <sup>-10</sup>	5.1x10 <sup>-11</sup>	3.2×10 <sup>-10</sup>	6.3x10 <sup>-1</sup>
7.44	2.4×10-10	3.5x10-11	1.2x10-10	3.0x10-10	5.0x10 <sup>-12</sup>	3.1x10 <sup>-11</sup>	5.9x10 <sup>-1</sup>
		Utir	ik Island,	μCi cm <sup>-3a</sup>			
17.3	5.4x10-6	1.7x10-10	7.0x10-6	2.1x10 <sup>-6</sup>	4.1x10 <sup>-7</sup>	2.2x10 <sup>-6</sup>	3.4x10 <sup>-7</sup>
18.0	6.6x10 <sup>-6</sup>	1.2×10 <sup>-10</sup>	$9.0 \times 10^{-6}$	2.8x10 <sup>-6</sup>	$5.4 \times 10^{-7}$	2.9x10 <sup>-6</sup>	4.4x10 <sup>-7</sup>
18.8	1.1x10 <sup>-5</sup>	9.9x10 <sup>-11</sup>	1.6x10 <sup>-5</sup>	5.1x10 <sup>-6</sup>	$9.8 \times 10^{-7}$	5.1x10 <sup>-6</sup>	7.7x10 <sup>-7</sup>
19.7	1.6x10 <sup>-5</sup>	8.7x10 <sup>-11</sup>	2.3x10 <sup>-5</sup>	7.5×10 <sup>-6</sup>	1.4x10 <sup>-6</sup>	7.5×10 <sup>-6</sup>	1.1x10 <sup>-6</sup>
20.7	6.8x10 <sup>-6</sup> 2.2x10 <sup>-6</sup>	2.4x10 <sup>-11</sup>	1.1x10 <sup>-5</sup> 9.5x10 <sup>-6</sup>	3.8x10 <sup>-6</sup>	$7.4 \times 10^{-7}$	3.8x10 <sup>-6</sup>	5.6x10
21.9 23.3	2.2x10 <sup>-0</sup> 9.7x10 <sup>-7</sup>	-	9.5x10 <sup>-6</sup>	3.3x10 <sup>-6</sup> 6.5x10 <sup>-7</sup>	$6.4 \times 10^{-7}$ $1.3 \times 10^{-7}$	3.3x10 <sup>-6</sup> 6.5x10 <sup>-7</sup>	4.8x10 <sup>-7</sup> 9.3x10 <sup>-8</sup>
24.9	1.9x10 <sup>-7</sup>	_	4.3x10 <sup>-7</sup>	1.6x10 <sup>-7</sup>	3.2x10 <sup>-8</sup>	1.6x10 <sup>-7</sup>	2.2x10
27.3	6.0x10 <sup>-8</sup>	- -	1.6x10 <sup>-7</sup>	6.4x10 <sup>-8</sup>	1.3x10 <sup>-8</sup>	$6.4 \times 10^{-8}$	8.8x10
30.0	1.9x10 <sup>-8</sup>	$8.0 \times 10^{-17}$	6.1x10 <sup>-8</sup>	2.6x10 <sup>-8</sup>	5.3×10 <sup>-9</sup>	2.6x10 <sup>-8</sup>	3.4x10 <sup>-9</sup>
33.8	2.8x10 <sup>-9</sup>	-	1.2x10 <sup>-8</sup>	5.6x10 <sup>-9</sup>	1.2x10 <sup>-9</sup>	5.6x10 <sup>-9</sup>	7.0x10 <sup>-1</sup>

 $a_{\mbox{\scriptsize Multiply}}$  by 3.7 x  $10^{10}$  to obtain Bq  $m^{-3}.$ 

data for persons weighing less than 58 kg (ICRP74). Adult reference values for breathing rate (ICRP74) were assumed for Marshallese adults regardless of adult body mass. At Rongelap Island, BRAVO debris passed during the afternoon, a period of light physical activity for the population. At Utirik Island, the debris passed during the night, a period of resting. At Sifo Island, a period of light physical activity was assumed in order to estimate breathing rate during the morning people were exposed to the fallout cloud. Values for airborne activity intake were compiled and are given in Table 19.

On the basis of urine results for <sup>131</sup>I, we concluded that inhalation could not account for the estimated activity intake for <sup>131</sup>I. In fact, lethal external exposure rates would have to accompany significant radioiodine intakes if inhalation of initial cloud fallout were the dominant intake pathway leading to the urine activity excreted on day 17. The other alternative, resuspension of fallout, would require the air concentrations produced by the cloud itself to be resuspended 200 times over.

- g. Total Activity Intake. Total activity intake and corresponding age were tabulated in Table 20 which we compiled on the basis of Tables 15, 17, and 19. We assumed that newborn babies inhaled activity at Rongelap and Utirik Islands; no newborns were reported at Sifo Island (Co74). We assumed that newborns from Rongelap and Utirik ingested 850 ml of breast milk per day (ICRP74) for 3 days post-detonation. A fraction of 10<sup>-5</sup> per ml of adult female breast milk was assumed to be the fraction of mother's intake of iodine which was transferred to the newborn (Ma81). Iodine decay between the time of intake for the mother and the time of intake for the newborn was neglected since we assumed breast milk to be part of the early excretion pathway out of the mother's body. Radioiodine excreted from the long-term clearance compartments was considered insignificant relative to total radioiodine cleared in the short term (Ma81).
- h. Derivation of  $^{131}$ I Intake Based on Bikini Ash and  $^{89}$ Sr and  $^{140}$ Ba in Urine on Day 45 Post-Detonation. Cronkite (Cr56) reported  $^{89}$ Sr and  $^{140}$ Ba urine activity excretion on day 45 post-detonation for six adults from Rongelap Island. The mean urine activity excreted on day 45 was 8.9 Bq (2.4 x  $^{10^{-4}}$   $\mu\text{Ci}$ ) of  $^{89}$ Sr and 2.2 Bq (6.0 x  $^{10^{-5}}$   $^{140}$ Ba. Whole-body retention functions given by ICRP (ICRP72) for injection of strontium and barium are

$$R_{Sr}(t) = 0.60e^{-0.25t} + 0.299(t + 0.20)^{-0.18}(0.555e^{-6.5x10^{-5}t} + 0.445e^{-2.6x10^{-4}t}), \quad (5)$$

$$R_{Ba}(t) = 0.38e^{-0.75t} + 0.191(t + 0.007)^{-0.237}(0.564e^{-1.09 \times 10^{-4}t} + 0.436e^{-4.36 \times 10^{-4}t})$$
,(6)

where t is in days and R(t) is the injected fraction remaining on day t. The fecal-to-urine ratios for excretion of injected Sr and Ba were 0.25 and 9.0, respectively (ICRP72). Correcting for 45 days of decay, the estimated activities injected into the systemic region of the body were 2.3 x  $10^4$  Bq (0.61  $\mu$ Ci) and 6.1 x  $10^5$  Bq (16.4  $\mu$ Ci) for  $8^9$ Sr and  $1^{40}$ Ba, respectively. If fallout was directly ingested as a single intake of dust at 0.5 day post-detonation, then the intake of  $1^{40}$ Ba,  $8^9$ Sr, or  $1^{31}$ I would be in the same ratios as the activity per unit area for these nuclides given in Table 13. Thus, we roughly estimated the

Table 19
Average Estimate of Inhaled Activity

Rongelap Island, uCia										
Age	Body Weight, kg	Breathing Rate cm <sup>3</sup> min-1	135 <sub>I</sub>	134 <sub>I</sub>	133 <sub>I</sub>	132 <sub>I</sub>	131	132 <sub>Te</sub>	131m <sub>Te</sub>	
Adult Male	70	20,000	24	10	11	2.6	0.48	2.9	0.55	
Adult Female	58	19,000	22	9.9	11	2.5	0.45	2.7	0.52	
Fourteen-Year-Old	50	19,000	22	9.9	11	2.5	0.45	2.7	0.52	
Twelve-Year-Old	40	15,280	18	8.0	8.7	2.0	0.36	2.2	0.42	
Nine-Year-Old	30	11,530	14	6.0	6.6	1.5	0.27	1.7	0.32	
Six-Year-Old	20	7,790	9.2	4.1	4.5	1.0	0.19	1.1	0.21	
One-Year-Old	10	4,050	4.8	2.1	2.3	0.53	0.096	0.58	0.11	
Newborn	3.5	1,620	1.9	0.85	0.93	0.21	0.039	0.23	0.045	
			Sifo	Island, uCi	<u>a</u>					
Adult Male	70	20,000	2.2	2.3	2.3	0.12	0.023	0.15	0.029	
Adult Female -	58	19,000	2.1	2.2	2.2	0.11	0.022	0.14	0.028	
Fourteen-Year-Old	50	19,000	2.1	2.2	2.2	0.11	0.022	0.14	0.028	
Twelve-Year-Old	40	15,280	1.7	1.8	1.7	0.090	0.017	0.11	0.023	
Nine-Year-Old	30	11,530	1.3	1.3	1.3	0.068	0.013	0.085	0.017	
Six-Year-Old	20	7,790	0.85	0.90	0.89	0.046	0.0089	0.058	0.012	
One-Year-Old	10	4,050	0.44	0.47	0.46	0.024	0.0046	0.030	0.006	
			Utiri	K Island, µC	<u>i#</u>					
Adult Male	70	7,500	1.9	0.00020	33	11	2.1	11	1.7	
Adult Female	58	6,500	1.7	0.00017	29	9.6	1.8	9.6	1.4	
Fourteen-Year-Old	50	6,500	1.7	0.00017	29	9.6	1.8	9.6	1.4	
Twelve-Year-Old	40	5,650	1.5	0.00014	25	8.4	1.6	8.3	1.2	
Nine-Year-Old	30	4,250	1.1	0.00011	19	6.3	1.2	6.3	0.94	
Six-Year-Old	20	2,850	0.74	0.000074	13	4.2	0.80	4.2	0.63	
One-Year-Old	10	1,450	0.37	0.000038	6.4	2.2	0.41	2.1	0.32	
Newborn	3.5	540	0.14	0.000014	2.4	0.80	0.15	0.79	0.12	

<sup>&</sup>lt;sup>a</sup>Multiply by 3.7 x  $10^4$  to obtain Bq.

Table 20 Total Radioiodine and Radiotellurium Activity Intake and Corresponding Age

		Rong	elap Islan	d, uCia			
Age	135	134 <sub>I</sub>	133 <sub>I</sub>		<sup>131</sup> 1	<sup>132</sup> Te	131 <sub>m</sub> Te
Adult Male Adult Female Fourteen-Year-Old Twelve-Year-Old Nine-Year-Old Six-Year-Old One-Year-Old Newborn	3.5x103 3.0x103 2.8x103 2.5x103 2.3x103 2.1x103 1.9x103 7.9x101	1.2x10 <sup>3</sup> 1.0x10 <sup>3</sup> 9.9x10 <sup>2</sup> 9.0x10 <sup>2</sup> 8.1x10 <sup>2</sup> 7.3x10 <sup>2</sup> 6.7x10 <sup>2</sup> 2.6x10 <sup>1</sup>	1.8x10 <sup>3</sup> 1.7x10 <sup>3</sup>	4.9x10 <sup>2</sup> 4.6x10 <sup>2</sup> 4.2x10 <sup>2</sup> 3.8x10 <sup>2</sup>	8.4x10 <sup>I</sup> 7.9x10 <sup>I</sup> 7.1x10 <sup>I</sup> 6.4x10 <sup>I</sup>	5.5x10 <sup>2</sup> 4.8x10 <sup>2</sup> 4.5x10 <sup>2</sup>	8.1x10 7.1x10 6.7x10 5.9x10 5.4x10 4.8x10 4.4x10
		Sifo	Island, µC	ia		1.28101	1.8×10 <sup>0</sup>
Adult Male Adult Female Fourteen-Year-Old Twelve-Year-Old Nine-Year-Old Six-Year-Old One-Year-Old	1.2x103 1.0x103 9.9x102 9.0x102 8.1x102 7.3x102 6.7x102	7.8x10 <sup>2</sup> 6.7x10 <sup>2</sup> 6.4x10 <sup>2</sup> 5.8x10 <sup>2</sup> 5.2x10 <sup>2</sup> 4.7x10 <sup>2</sup>	5.7x10 <sup>2</sup> 5.0x10 <sup>2</sup> 4.7x10 <sup>2</sup> 4.2x10 <sup>2</sup> 3.9x10 <sup>2</sup> 3.5x10 <sup>2</sup> 3.1x10 <sup>2</sup>	1.2x10 <sup>2</sup> 1.0x10 <sup>2</sup> 9.9x10 <sup>2</sup> 9.0x10 <sup>1</sup> 8.1x10 <sup>1</sup> 7.3x10 <sup>1</sup> 6.7x10 <sup>1</sup>	2.0x101 1.7x101 1.6x101 1.5x101 1.3x101 1.2x101	1.3x10 <sup>2</sup> 1.2x10 <sup>2</sup> 1.1x10 <sup>2</sup> 9.7x10 <sup>1</sup> 8.7x10 <sup>1</sup> 7.8x10 <sup>1</sup>	2.4x101 2.1x101 2.0x101 1.8x101 1.6x101
		<u>Utirik</u>	Island, µC	ia			1.3x101
Adult Male Adult Female Fourteen-Year-Old Twelve-Year-Old Jine-Year-Old ix-Year-Old ne-Year-Old ewborn	1.4x102 1.2x102 1.2x102 1.0x102 9.7x101 8.7x101 7.9x101 3.1x100	- - - -	3.2x102 2.8x102 2.7x102 2.4x102 2.2x102 1.9x102 1.6x102 9.4x100	1.1x102 1.0x102 9.5x101 8.6x101 7.7x101 6.7x101	2.3x101 2.0x101 1.9x101 1.8x101 1.5x101 1.4x101 1.3x101 6.5x101	1.1x10 <sup>2</sup> 9.7x10 <sup>1</sup> 9.2x10 <sup>1</sup> 8.2x10 <sup>1</sup> 7.3x10 <sup>1</sup> 6.4x10 <sup>1</sup> 5.7x10 <sup>1</sup> 3.2x10 <sup>0</sup>	1.7x101 1.4x101 1.3x101 1.2x101 1.1x101 1.0x101 8.3x100 1.2x10-1

<sup>a</sup>Multiply by 3.7  $\times$  10<sup>4</sup> to obtain Bq.

intake of  $^{131}$ I using  $^{140}$ Ba and  $^{89}$ Sr estimates of injected activities. The fractions ingested and absorbed into body fluids were taken to be 1.0 for iodine, 0.2 for strontium and 0.06 for barium (ICRP68). We assumed instantaneous transfer from ingestion with meals up to the point of injection into systemic body fluids. The corresponding estimated intakes were 1.2 x  $^{105}$  Bq (3.1  $\mu$ Ci) for  $^{89}$ Sr and 1.0 x  $^{107}$  Bq (270  $\mu$ Ci) for  $^{140}$ Ba. If iodine, barium, and strontium were taken as dust, then we estimate  $^{131}$ I intake as 2.4 x  $^{106}$  Bq (64.1  $\mu$ Ci) or 1.8 x  $^{107}$  Bq (490  $\mu$ Ci) based on strontium or barium intakes, respectively.

i. Absorption Through Skin. According to Glasstone (G162), fallout will enter the body through the digestive tract, through the lungs, or through wounds or abrasions. No direct absorption through skin is reported in CAE57, JCCRRER56, G162, Cr56, or Du56. Beta burns appeared on the skin of Rongelap people many weeks after exposure; thus at the time of contamination we believe skin was intact. Harrison (Ha63) measured the extent to which gaseous  $^{131}I_2$  and aqueous solutions of  $K^{131}I$  and  $^{131}I_2$  were absorbed through human skin. For aqueous  $K^{131}I$ , the mean absorption rate was 7.8 x  $10^{-4}$  h<sup>-1</sup> and for  $^{131}I_2$  it was less. Use of stable I carrier with the gas was found to irritate and blister skin which may have led to the increased absorption reported for gaseous  $131_{12}$  (Ha63). We assumed 0.17  $m^2$  of skin surface was exposed, a skin surface activity of 110 MBq m<sup>-2</sup> (3.1 x 10<sup>3</sup>  $\mu$ Ci m<sup>-2</sup>), and 49 hours of exposure at Rongelap Island. These assumptions led to an upper estimated intake of 0.7 MBq (19  $\mu$ Ci)  $^{131}$ I based on an absorption rate of 7.8 x 10  $^{-4}$  h  $^{-1}$ . This was an upper estimate since the skin surface was likely to be less contaminated than the ground surface because of swimming and bathing. Assuming that the urine bioassay results of Harris (Ha54) were accurate, we estimate the intake through skin to be as much as 20% of the total intake for 131 I. It was not likely that skin was as contaminated as the ground and, therefore, we do not consider this to be an important pathway.

#### 3. Absorbed Dose for Individuals

a. Absorbed Dose per Unit Activity Intake. Radioiodine and radiotellurium thyroid absorbed-dose commitment per unit activity intake and corresponding age were compiled in Table 21 from dose equivalent per unit intake results generated by Johnson (Jo81, Jo82). We performed an exponential interpolation of pre-adult values in order to generate all the results given here. Thyroid absorbed-dose commitment was generated because all the nuclides of interest to us had half-lives much shorter than 50 years, the integration interval used by Johnson to generate committed dose equivalents. The values for the tellurium isotopes were generated from reference man data in Limits for Intakes of Radionuclides by Workers (ICRP79). The tellurium isotope values listed in Table 21 for the pre-adult ages were generated by ratios of the Johnson values for the appropriate iodine daughters. The thyroid absorbed dose for a person of any age per unit activity intake for tellurium was assumed to be directly proportional to the product of the adult value and the ratio of the iodine value. For example, <sup>132</sup>Te rad per µCi for a six-year-old (see Table 21) would be the product of 0.22 (taken from the <sup>132</sup>Te column of Table 21) and the ratio of 0.048 to 0.013 (taken from the <sup>132</sup>Te column of Table 21).

Table 21

Radioiodine and Radiotellurium Thyroid Absorbed-Dose Commitment per Unit

Activity Intake and Corresponding Age

-		rad	µCi <sup>-la</sup>					
Age	135 <sub>I</sub>	134 <sub>I</sub>	133 <sub>I</sub>	1 <b>32</b> 1	131 <sub>I</sub>	132 <sub>Te</sub>	131m <sub>Te</sub>	
Adult Male	0.056	0.0025	0.26	0.013	1.4	0.22	0.16	
Adult Female	0.067	0.0035	0.31	0.015	1.7	0.25	0.19	
Fourteen-Year-Old	0.10	0.0041	0.46	0.022	2.5	0.38	0.29	
Twelve-Year-Old	0.12	0.0053	0.56	0.027	2.9	0.46	0.33	
Nine-Year-Old	0.16	0.0077	0.75	0.036	3.8	0.61	0.43	
Six-Year-Old	0.21	0.011	1.0	0.048	4.8	0.81	0.55	
One-Year-Old	0.49	0.026	2.3	0.11	11	1.9	1.3	
Newborn	0.62	0.032	3.0	0.14	15.	2.4	1.7	
In Utero, 3rd tri.b	0.042	0.0021	0.21	0.0089	1.0	0.15	0.11	
In Utero, 2nd tri.b	0.12	0.0050	0.54	0.022	2.5	0.37	0.29	
In Utero, 1st tri.b	0.00	0.00	0.00	0.00	0.00	0.00	0.00	

<sup>a</sup>Multiply by 2.7 x  $10^{-7}$  to obtain Gy Bq<sup>-1</sup>. <sup>b</sup>Per unit activity intake of the mother.

The most probable ingestion dose evaluation by James (Ja64) for a 3.5-year-old Rongelap girl was given as 14.45 gray (1445 rad). James chose this age because three teenage females were the first to develop thyroid nodules, 10 years after the acute exposure. James assumed the total thyroid absorbed dose from ingestion of all iodine isotopes in fallout was 2.6 times the thyroid dose due t 131 I. This factor of 2.6 is dependent upon the age of the fallout and the age of the individual and differs considerably from our estimates. Since James based the total thyroid dose on 131 I measurements in urine and this factor of 2.6, there is a significant difference in thyroid dose derived by our method and that derived by James. Adjusting the James ingestion dose estimate by multiplying by the ratio of 8.6 (our factor for a 3.5-year-old person) to 2.6 increases the total thyroid absorbed dose estimate of James to 47.8 gray (4780 rad). The comparable result for a 3.5-year-old, using our method and Johnson's (Jo81) dose conversion factor, was 37 gray (3700 rad).

b. Thyroid Absorbed Dose. We compiled the product of age-specific intake (see Table 20) and age-specific thyroid absorbed dose per unit intake (see Table 21) for several specific ages (Table 22). The thyroid absorbed dose from all iodine and tellurium nuclides was 7.7 times the dose due to <sup>131</sup>I at Rongelap Island for an adult male. It was 10 times the dose due to <sup>131</sup>I at Sifo Island and 4.7 times the dose due to <sup>131</sup>I at Utirik Island.

Table 22

Estimated Radioiodine and Radiotellurium Thyroid Absorbed Dose and Corresponding Age

		Ro	ongelap Isl	land, rad <sup>a</sup>				
Age	135 <sub>I</sub>	<sup>134</sup> 1	133 <sub>I</sub>	132 <sub>I</sub>	131 <sub>I</sub>	132 <sub>Te</sub>	131m <sub>Te</sub>	Total
Adult Male	1.9x10 <sup>2</sup>	3.0x10 <sup>0</sup>	5.5x10 <sup>2</sup>	7.3x10 <sup>0</sup>	1.3x10 <sup>2</sup>	1.2x10 <sup>2</sup>	1.3x10 <sup>1</sup>	1.0x10 <sup>3</sup>
Adult Female	2.0x10 <sup>2</sup>	3.5x10 <sup>0</sup>	$5.7 \times 10^{2}$	7.4x10 <sup>0</sup>	1.4x10 <sup>2</sup>	1.2x10 <sup>2</sup>	1.3x10 <sup>1</sup>	1.1x10 <sup>3</sup>
Fourteen-Year-Old	2.8x10 <sup>2</sup>	$4.0 \times 10^{0}$	$7.5 \times 10^{2}$	1.0x10 <sup>1</sup>	$2.0 \times 10^{2}$	1.7x10 <sup>2</sup>	1.9x10 <sup>1</sup>	$1.4 \times 10^{3}$
Twelve-Year-Old	$3.0 \times 10^{2}$	$4.8 \times 10^{0}$	$9.1 \times 10^{2}$	$1.1 \times 10^{\frac{1}{4}}$	$2.1 \times 10^{2}$	$1.9 \times 10^{2}$	1.9x10 <sup>1</sup>	$1.6 \times 10^{3}$
Nine-Year-Old	$3.7 \times 10^{2}$	$6.2 \times 10^{0}$	$1.1 \times 10^{3}$	1.4x10 <sup>1</sup>	$2.4 \times 10^{2}$	$2.3 \times 10^{2}$	$2.3 \times 10^{1}$	$2.0 \times 10^{3}$
Six-Year-Old	$4.5 \times 10^{2}$	8.0x10 <sup>0</sup>	$1.3 \times 10^{3}$	1.6x10 <sup>1</sup>	$2.8 \times 10^{2}$	$2.7 \times 10^{2}$	2.6x101	$2.4 \times 10^{3}$
One-Year-Old	9.5x10 <sup>2</sup>	1.7x10 <sup>1</sup> .	$2.8 \times 10^{3}$	3.4x101	5.8x10 <sup>2</sup>	5.7x10 <sup>2</sup>	5.7x101	$5.0 \times 10^{3}$
Newborn	4.9x101	8.3x10 <sup>-1</sup>	1.4x10 <sup>2</sup>	1.8x100	3.3x10 <sup>1</sup>	2.3x10 <sup>1</sup>	3.1x100	2.5x10 <sup>2</sup>
In Utero, 3rd tri.	1.3×10 <sup>2</sup>	2.1x10 <sup>0</sup>	3.8x10 <sup>2</sup>	4.4x10 <sup>0</sup>	8.4x10 <sup>1</sup>	7.2x10 <sup>1</sup>	7.8x10 <sup>0</sup>	6.8x10 <sup>2</sup>
			Sifo Islan	nd, rada				•
Adult Male	6.7x10 <sup>1</sup>	2.0x100	1.5x10 <sup>2</sup>	1.6x100	2.8x101	2.9x101	3.8x100	2.8x10 <sup>2</sup>
Adult Female	$6.7 \times 10^{1}$	$2.3 \times 10^{0}$	1.6x10 <sup>2</sup>	1.5x10 <sup>0</sup>	$2.9 \times 10^{1}$	3.0x10 <sup>1</sup>	$4.0 \times 10^{0}$	2.9x10 <sup>2</sup>
Fourteen-Year-Old	$9.9x10^{1}$	$2.6 \times 10^{0}$	$2.2 \times 10^{2}$	2.2x10 <sup>0</sup>	$4.0 \times 10^{1}$	4.2x10 <sup>1</sup>	5.8x10 <sup>0</sup>	$4.1 \times 10^{2}$
Twe lve-Year-Old	1.1x10 <sup>2</sup>	$3.1 \times 10^{0}$	$2.4 \times 10^{2}$	$2.4 \times 10^{0}$	$4.4 \times 10^{1}$	$4.5 \times 10^{1}$	$5.9 \times 10^{0}$	$4.5 \times 10^{2}$
Nine-Year-Old	1.3x10 <sup>2</sup>	$4.0 \times 10^{0}$	$2.9 \times 10^{2}$	2.9x10 <sup>0</sup>	$4.9 \times 10^{1}$	5.3x10 <sup>1</sup>	$6.9 \times 10^{0}$	$5.4 \times 10^{2}$
Six-Year-Old	$1.5 \times 10^{2}$	5.2x10 <sup>0</sup>	$3.5 \times 10^{2}$	$3.5 \times 10^{0}$	$5.8 \times 10^{1}$	$6.3 \times 10^{1}$	$7.7 \times 10^{0}$	$6.4 \times 10^{2}$
One-Year-Old	$3.3 \times 10^{2}$	1.1x10 <sup>1</sup>	$7.1 \times 10^{2}$	$7.4 \times 10^{0}$	$1.2 \times 10^{2}$	$1.4 \times 10^{2}$	1.7x10 <sup>1</sup>	$1.3 \times 10^{3}$
In Utero, 2nd tri.	1.2x10 <sup>2</sup>	$3.4 \times 10^{0}$	$2.7 \times 10^{2}$	2.2x10 <sup>0</sup>	$4.3 \times 10^{1}$	4.4x10 <sup>1</sup>	6.1x10 <sup>0</sup>	$4.9 \times 10^{2}$
		<u> 1</u>	Jtirik Isla	and, rada				
Adult Male	7.8x10 <sup>0</sup>	_	8.3x10 <sup>1</sup>	1.4x10 <sup>0</sup>	3.2×10 <sup>1</sup>	2.4x10 <sup>1</sup>	2.7x10 <sup>0</sup>	1.5x10 <sup>2</sup>
Adult Female	8.0x10 <sup>0</sup>	-	8.7x101	1.5x10 <sup>0</sup>	$3.4 \times 10^{1}$	2.4x101	2.7x10 <sup>0</sup>	1.6x10 <sup>2</sup>
Fourteen-Year-Old	1.2x10 <sup>1</sup>	-	$1.2 \times 10^{2}$	2.1x10 <sup>0</sup>	4.8x101	3.5x10 <sup>1</sup>	$3.8 \times 10^{0}$	2.2x10 <sup>2</sup>
Twelve-Year-Old	1.2x101	-	1.3×10 <sup>2</sup>	2.3x100	5.2×101	3.8x101	$4.0 \times 10^{0}$	2.4x10 <sup>2</sup>
Nine-Year-Old	1.6x10 <sup>1</sup>	-	$1.7 \times 10^{2}$	2.8x100	$5.7 \times 10^{1}$	4.5x10 <sup>1</sup>	$4.7 \times 10^{0}$	$3.0 \times 10^{2}$
Six-Year-Old	1.8x101	-	$1.9 \times 10^{2}$	3.2x10 <sup>0</sup>	$6.7 \times 10^{1}$	5.2x101	5.5x10 <sup>0</sup>	$3.4 \times 10^{2}$
One-Year-Old	$3.9 \times 10^{\frac{1}{2}}$	-	$3.7 \times 10^{2}$	6.6x10 <sup>2</sup>	$1.4 \times 10^{2}$	$1.1 \times 10^{2}$	1.1x10 <sup>1</sup>	$6.6 \times 10^{2}$
Newborn	$1.9 \times 10^{0}$	-	$2.8 \times 10^{1}$	$4.3 \times 10^{-1}$	$9.8 \times 10^{0}$	7.7x10 <sup>0</sup>	$2.0 \times 10^{-1}$	4.8x101
In Utero, 3rd tri.	$5.0 \times 10^{0}$	-	$5.6 \times 10^{1}$	8.9x10 <sup>-1</sup>	$2.0 \times 10^{\frac{1}{4}}$	$1.5 \times 10^{1}$	$1.5 \times 10^{0}$	9.8x101
In Utero, 2nd tri.	1.4x10 <sup>1</sup>	-	$1.5 \times 10^{2}$	2.2x10 <sup>0</sup>	5.0x10 <sup>1</sup>	3.6x10 <sup>1</sup>	4.1x10 <sup>0</sup>	2.6x10 <sup>2</sup>

<sup>8</sup>Multiply by 0.01 to obtain Gy.

The contribution from the decay of each radioiodine nuclide to thyroid absorbed dose was dependent upon the time post-detonation and upon the fractionation of the isobaric chains giving rise to the radioiodines. Both factors influenced our estimate of thyroid absorbed dose. James assumed theoretical fission yields and that one third the ingestion intake occurred at ten hours and two thirds at 30 hours post-detonation. We assumed Bikini ash fractionation and that one third the ingestion intake occurred at 5.5 hours (lunch) and two thirds at 12 hours (dinner) post-detonation. James considered only <sup>131</sup>I, <sup>133</sup>I, and <sup>135</sup>I in the thyroid-dose estimate. We considered all likely iodine and tellurium nuclides. Additionally, James adjusted the thyroid dose downward to 10.5 gray (1050 rad) for a 3.5-year-old to account for the possibility that part of the intake was due to inhalation. We considered inhalation intake to be insignificant relative to ingestion intake and compared the James ingestion estimate to our ingestion estimate.

- c. Maximum Thyroid Absorbed Dose. We used several methods to estimata a range of fallout material ingested. One was to ingest known quantities of pha maceutical-grade CaCO3 with meals and subjectively arrive at descriptions of taste similar to those given by the Rongelap people at the time of evacuation in March 1954. A group of five adult white males at BNL reported that 200 mg of CaCO3 could not be sensed by taste when mixed with food. Another method was to assume that the range of weights associated with the contents of the stomach in . cases of sudden death corresponded to the range of activity intake (Ev66). This range - 0 to 380 g, mean 82 g - implies a maximum intake of about 5 times the mean value. Another method was to examine the range of 137Cs daily activity intake estimated from 1957 to 1983 for Rongelap and Utirik people (Le84). The intake rate was estimated from whole-body counting results. The range of 137Cs intake rate was about 5 times the mean value. Another method was to examine the range of 137Cs body burden exhibited by the population inhabiting Bikini Island from 1974 to 1978 (Mi83). The range was about 3.2 times the mean value. From the above range values, we assumed a value of 4 times the intake and thus 4 times the mean thyroid absorbed dose for estimates made here (see Table 23).
- d. External Sources of Thyroid Dose. External thyroid absorbed dose estimates were based on integrated photon exposure given previously and on an adjustment for living pattern in a variable exposure-rate environment. Further detail about the adjustment can be found in (Na80) and (Le84).

Some questions about the external beta radiation penetrating to the depth of the thyroid were expressed by Cronkite (Cr81). The thickness of tissue overlying the thyroid ranges from 0.4 to 2.0 cm, average 0.82 cm, and does not correlate well with age or body weight (ICRP74). A minimum beta energy of 1.8 MeV was estimated by us for penetration of 0.82 cm of tissue. At Rongelap Island, about 70% of the population had skin lesions on some part of the neck. The lesions appeared initially about 21 days post-exposure (Cr56). This sould imply a skin surface dose of tens of gray (several thousand rad). Only a small percent of the beta flux was above 1.8 MeV in kinetic energy. Of this higher energy flux, only a small fraction would penetrate 0.82 cm of tissue and deposit energy in the thyroid. Thus, we considered thyroid dose from this pathway to be insignificant.

Table 23

Total Thyroid Absorbed-Dose Estimate

# Average Estimate, rada

Age	Rongelap Island			S	ifo Island	<del></del>	Utirik Island		
	Internal	External	Total	Internal	External	Total	Internal	External	Total
Adult Male	1000	190	1200	280	110	400	150	11	160
Adult Female	1100	190	1300	290	110	410	160	11	170
Fourteen-Year-Old	1400	190	1600	410	110	530	220	11	230
Twe lve-Year-Old	1600	190	1800	450	110	570	240	11	250
Nine-Year-Old	2000	190	2200	540	110	660	300	11	310
Six-Year-Old	2400	190	2600	640	110	760	340	11	350
One-Year-Old	5000	190	5200	1300	110	1400	670	11	680
Newborn	250	190	440	-	<b>-</b> .	_	48	11	59
In Utero, 3rd tri.	680	190	870	-	_	-	98	11	110
In Utero, 2nd tri.	-	-		490	110	610	260	11	270
			Maxim	num Estimate	, rad				
Adult Male	4000	190	4200	1120	110	1200	600	11	610
Adult Female	4400	190	4600	1160	110	1300	640	11	650
Fourteen-Year-Old	5600	190	5800	1600	110	1700	880	11	890
Twelve-Year-Old	6400	190	6600	1800	110	1900	960	11	970
Nine-Year-Old	8000	190	8200	2200	110	2300	1200	11	1200
Six-Year-Old	9600	190	9800	2600	110	2700	1400	11	1400
One-Year-Old	20000	190	20000	5200	110	5300	2700	11	2700
Newborn	1000	190	1200	_	_	_	190	11	200
In Utero, 3rd tri.	2700	190	2900	-	_	_	390	11	400
In Utero, 2nd tri.	-	_		2000	110	2100	1000	11	1000

<sup>a</sup>Multiply by 0.01 to obtain Gy.

## III. THYROID NODULES AND THYROID CANCER RISK FROM FALLOUT

# A. Tabulation of Thyroid Effects and Age at Exposure

Medical records were reviewed by Adams of the Marshall Islands Medical Program for age at exposure and thyroid nodule data. Conard had performed a similar tabulation (Co80). Memoranda between the evacuation teams and their superiors were reviewed for age-at-exposure data (OC68). Data gathered by the Marshall Islands Radiological Safety Program related to age at the time of whole-body counting measurements were reviewed. When discrepancies between the three sources of age data became apparent (about April 1982) Medical Program records were assumed correct. Differences, between age groupings reported in Table 1 of the Conard report (Co80) and Tables 24 or 25 as reported here, exist because of the age-at-exposure discrepancies.

Two young Rongelap males with severe growth retardation and gradually developed atrophy of the thyroid gland were not included in Tables 24 and 25 because thyroid nodules would not develop in these individuals. Surgical examination of nodules detected by palpation in the field revealed four persons without nodules at the time of surgery (see Table 24). In addition, two persons too old to undergo surgery were included among those having nodules.

# B. Tabulation of Risk of Thyroid Cancer

The unexposed population incidence rate of thyroid cancer was higher at Rongelap and Utirik than for other sea-level populations, 2 cancers per hundred-thousand person-years observed at Singapore (Le82) versus 59 cancers per hundred-thousand person-years observed in the Marshall Islands comparison group. The comparison group makeup has been described previously by Conard (Co80). Thyroid-cancer in the United States has been diagnosed at the rate of 2.5 per hundred-thousand person-years observed (De75).

Our estimated value for thyroid cancer risk from fallout for the exposed population is 150 cancers per million person-gray-years at risk (1.5 cancers per million person-rad-years). This estimate was based on the Marshall Islands' comparison group incidence, thyroid doses estimated here, and thyroid observations in the exposed groups at Rongelap, Utirik, and Sifo Islands (see Table 25). It could be assumed that the larger studies of cancer gave a more accurate reflection of the spontaneous incidence rate of thyroid cancer at Rongelap and Utirik than the comparison group statistics. For a population of 251 people examined over 29 years, about 0.15 thyroid cancers would be expected on the basis of the rate given at Singapore (Le82). This value when incorporated into the estimate of cancer risk from radiation exposure leads to a Rongelap-Utirik-Sifo population value of 210 thyroid cancers per million person-gray-years at risk (2.1 thyroid cancers per million person-gray-years at risk (2.1 thyroid cancers per million person-gray-years at risk (2.1 thyroid cancers per million person-gray-years at risk), 40% higher than the value we estimated using Marshallese comparison statistics.

### C. Comparison to Other Estimates of Thyroid Cancer Risk

The value for the radiation-induced incidence of thyroid cancer was 147 per million person-gray-years (1.47 cancers per million person-rad-years) for

Table 24 Tabulation of Thyroid Results

		Surg			
Age Group	Number of Persons Studied	Number Undergoing Surgery	Number of Nodules at Surgery	Number Diagnosed as Carcinoma	Assumed Number of Nodules Detected
Rongelap					
In Utero <10 10-18 >18	3 19 <sup>a</sup> 12 31	2 15 3 5	2 15 3 3	0 1 1 2	2 15 3 3
Sifo					•
In Utero <10 10-18 >18	- 1 7 -	0 3 - 3	0 2 - 3	0 0 - 0	0 2 - 4d
Utirik					
In Utero <10 10-18 >18	8 56 19 84	0 4 4 9	0 4 4 8	0 1 2 1	0 4 4 9d
Unexposed					
<10 10-18 >18	229 79 292	ND ND	6 6 26 <sup>c</sup>	2 1 2	6 6 26

aDoes not include two boys with thyroid atrophy.

bNo data.

CFinal diagnosis pending on three people.

dIncludes one person too old for surgery.

Table 25 Summary of Thyroid Results

Age at Exposure	Total Number	Nodu les <sup>a</sup>	No. with Carcinoma	Expected Nodules <sup>b, c</sup>	Expected Cancers <sup>b</sup> , c	Mean Adsorbed Dose, rads	Mean Nodule Time at Risk (Cancer), years	Mean Nodule Risk, No. per 106 person-rad- years <sup>d</sup>	Mean Cancer Risk, No. per 106 person-rad- years <sup>d</sup>
Rongelap					<del></del>		·		
In Utero	3	2	0	0.079	0.026	640	23(-)	43	-
<10	19e	15	1	0.50	0.17	4000	13(15)	15	0.73
10-18	12	3	1	0.92	0.15	1700	17(22)	6.0	1.9
>18	31	3	2	2.7	0.21	1300	17(13)	0.44	3.4
All Ages	65	23	4	4.2	0.56	2100	15(16)	9.2	1.6
Sifo									
In Uterc	1	0	0	0.026	0.0087	610	-(-)	-	-
<10	7	2	0	0.18	0.061	1100	22(-)	11	_
10-18	-	-	-	-	-	-	-(-)	••	_
>18	11	4	0	0.98	0.075	410	18(-)	37	_
All Ages	19	6	0	1.2	0.15	670	19(-)	20	-
Utirik									
In Utero	8	0	0	0.21	0.070	130	-(-)	_	-
<10	56	4	1	1.5	0.49	490	25(21)	3.6	0.89
10-18	19	4	2	1.4	0.24	220	22(22)	27	19.
>18	84	9	1	7.5	0.58	170	22(22)	4.8	1.3
All Ages	167	17	4	11	1.4	280	23(22)	5.9	2.5
All Exposed									
In Utero	12	2	0	0.32	0.10	290	23(-)	21	_
<10	82	21	2	2.2	0.72	1400	16(18)	10	0.65
10-18	31	7	3	2.3	0.39	790	20(22)	9.6	5.1
>18	126	16	3	11	0.87	470	20(16)	4.4	2.2
All Ages	251	46	8	16	2.1	800	18(19)	8.3	1.5

<sup>\*</sup>Includes some cases not surgically treated.

bBased on prevalence in unexposed Marshallese.

CIn utero values based on age less than ten prevalence.

dMultiply by 100 to obtain number per 106 person-gray-years.

eDoes not include two boys with thyroid atrophy.

Nagasaki persons who received greater than 50 rad (CBEIR80). A value of 220 per million person-gray-years (2.2 cancers per million person-rad-years) was reported for individuals exposed at Hiroshima (CBEIR80). A group of 2611 people who were irradiated during the first year of life for presumed enlargement of the thymus gland exhibited an incidence of 290 per million person-gray-years (2.9 cancers per million person-rad-years) (CBEIR80). The University of Chicago head and neck irradiation sample of 100 children irradiated at about 4.5 years of age resulted in a risk of thyroid cancer of about 400 per million persongray-years (4 cancers per million person-rad-years) (CBEIR80). The Michael Reese Hospital head and neck irradiation sample of 2109 people irradiated during infancy, childhood, or adolescence exhibited a thyroid cancer risk of 210 per million person-gray-years (2.1 cancers per million person-rad-years) (CBIER80). A person-weighted average of the above values gives a combined risk of about 200 per million person-gray-years (2 thyroid cancers per million person-rad-years). Thus, the comparison of risk from Marshall Islands fallout studies to external irradiation studies involving instantaneous doses to the thyroid showed no significant difference.

Scalp irradiation of over 10,000 Jewish children resulted in an absolute risk estimate of 630 per million person-gray-years (6.3 thyroid cancers per million person-rad-years) (CBEIR80). Another study of 261 Jewish persons irradiated during infancy for presumed enlargement of the thymus resulted in a risk of 480 per million person-gray-years (4.8 thyroid cancers per million person-rad-years) (CBEIR80). Comparison of our value to Jewish populations showed no statistically significant difference due to variations in doses estimated in either of the exposed groups (Ha52).

Studies of children exposed to fallout radioiodine in Utah and Nevada have not revealed any excess thyroid cancers (CBEIR80). There is no evidence to demonstrate a carcinogenic effect in people following intake of  $^{131}$ I for treatment of hyperthyroidism (CBEIR80). No value of risk can be estimated for  $^{131}$ I exposure on the basis of Marshall Islands experience. This is because the internal dose to the Marshallese thyroids from  $^{131}$ I amounted to about 10 to 20% of the total thyroid dose. The beta to gamma dose ratio from the BRAVO mixture of iodines plus external radiation was not similar to  $^{131}$ I, 3.5 versus 7.5 respectively. Another major difference between  $^{131}$ I exposure and the Marshallese exposure was dose rate.

### D. Estimate of the Uncertainty in the Derived-Risk Estimate

In order to estimate the uncertainty in the derived risk estimate the following argument was used.

Risk = 
$$\frac{\text{# of effects}}{\text{dose x # of years at risk}} = \frac{a}{b c}$$
. (1)

The uncertainty in the risk,  $\Delta$  Risk, is approximately the sum of the products of the uncertainties in a, b or c times the effect that a, b or c have on the value of risk (Be69).

$$\Delta \operatorname{Risk} = \Delta a \left( \frac{\partial \operatorname{Risk}}{\partial a} \right) + \Delta b \left( \frac{\partial \operatorname{Risk}}{\partial b} \right) + \Delta c \left( \frac{\partial \operatorname{Risk}}{\partial c} \right) . \tag{2}$$

The terms in parenthesis are the partial derivatives of risk with respect to a, b or c. We assumed the partial derivatives were constant over the ranges of a, b and c. For our purposes Eq. 2 reduces to

$$\frac{\Delta \text{ Risk}}{\text{Risk}} = \frac{\Delta a}{a} + \frac{\Delta b}{b} + \frac{\Delta c}{c} . \tag{3}$$

We do not know the actual uncertainty  $\Delta a$ ,  $\Delta b$  or  $\Delta c$ , however, we know the standard deviation,  $\sigma$ , which is characteristic of the probable uncertainty. Bevington (Be69) develops the use of standard deviation to estimate the uncertainty with the result that for our application

$$\sigma_{Risk}^{2} = \sigma_{a}^{2} \left(\frac{\partial Risk}{\partial a}\right)^{2} + \sigma_{b}^{2} \left(\frac{\partial Risk}{\partial b}\right)^{2} + \sigma_{c}^{2} \left(\frac{\partial Risk}{\partial c}\right)^{2}$$
(4)

Here we have assumed the fluctuations in a, b and c are uncorrelated. Applying Eq. 4 to Eq. 1 yields

$$\frac{\sigma_{Risk}^{2}}{Risk^{2}} = \frac{\sigma_{a}^{2}}{a^{2}} + \frac{\sigma_{b}^{2}}{b^{2}} + \frac{\sigma_{c}^{2}}{c^{2}}$$
 (5)

The standard deviation in the number of effects,  $\sigma_a$ , was assumed to be equal to the square root of the number of excess nodules, that is,  $\sigma_a = 5.5$  and a = 30. Thus the relative standard deviation equals 0.18 (i.e.  $\sigma_a/a = 0.18$ ). This is in fair agreement with the fact that out of 48 persons undergoing surgery for nodules only 44 had nodules. In the reverse sense nodules could have gone undetected.

The standard deviation in the number of years at risk,  $\sigma_c$ , was taken as equal to the standard deviation associated with the mean years at risk, which we reported in Table 25. Thus,  $\sigma_c$  equals 5.5 years and  $\sigma_c/c$  equals 0.30.

The standard deviation in absorbed dose to the thyroid,  $\sigma_b$ , was estimated from the standard deviations associated with 1) the urine result, 2) the  $^{131}$ I intake estimate, 3) the absorbed dose from  $^{131}$ I and 4) the ratio of  $^{131}$ I dose to total thyroid dose. Each of these was assigned a relative standard deviation equal to 0.7.

The assigned value of 0.7 for each of the relative standard deviations of 1 through 4 above was based on the following. The observed value for 90 Sr urine activity was nearly 0.7 (Le84). This uncertainty in urine activity excreted is largely from two sources, the measurement technique and the day-to-day metabolism changes in adults. It was assumed that the relative standard deviation associated with 90 Sr activity in urine applied to 1311 activity in urine as well. The uncertainty associated with transforming a urine result into an intake estimate comes from uncertainty in the true excretion function for iodine in adults and from not knowing the true time of intake. Assigning a relative standard deviation of 0.7 was thought to be conservative. The uncertainty

associated with absorbed dose in the thyroid per unit intake of  $^{131}$ I was reported by Dunning (Du81). The uncertainty associated with the ratio of  $^{131}$ I dose to total thyroid dose comes from not knowing the true composition of the BRAVO fallout (see Ja64, Ph82) and from not knowing the true time of intake. We assigned the value of 0.7 for the relative standard deviation of this quantity.

Since total dose was related to 1 through 4 above by either multiplication or division, the relative standard deviation for absorbed dose was taken as

$$\frac{\sigma_b}{b} = \sqrt{(0.7)^2 + (0.7)^2 + (0.7)^2 + (0.7)^2} = 1.4.$$

The relative standard deviation was estimated for risk based on the above values for  $\sigma_a/a$ ,  $\sigma_b/b$  and  $\sigma_c/c$ . Thyroid absorbed dose, number of years at risk, and number of effects are related to risk by multiplication and division. The relative standard deviation in risk was calculated in a similar way as was done for absorbed dose. We estimate the mean and standard deviation of thyroid cancers per million person-gray-years at risk to be equal to  $150 \pm 230$  ( $1.5 \pm 2.3$  cancers per million person-rad-years at risk). Our estimate of the nodule risk rate and standard deviation was  $830 \pm 1200$  nodules per million person-gray-years at risk ( $8.3 \pm 12$  nodules per million person-rad-years at risk).

#### REFERENCES

- Balo Bateman, H., 1910, "The Solution of a System of Differential Equations Occurring in the Theory of Radioactive Transformations,"

  Proceedings of the Cambridge Philosophical Society, 15, 423.
- Beef7 Berman, M., 1967, "The Iodine Pool," in: Compartments Pools and Spaces in Medical Physiology, U.S. Atomic Energy Commission Report, Symposium Series II, Washington, D.C.
- Bee Bevington, P.R., 1969, <u>Data Reduction and Error Analysis for the Physical Sciences</u>, McGraw-Hill Book Company, New York.
- Beso Beck, H. L., 1980, Exposure Rate Conversion Factors for Radionuclides Deposited on the Ground, Environmental Measurements Laboratory Report, New York, EML-378.
- Bo56
  Borg, D.C., 1956, "Theoretical Calculations of the Gamma Radiation Spectrum from Initial and Fallout Radiations of Nuclear Weapons," in:

  The Shorter-Term Biological Hazards of a Fallout Field, U.S. Atomic Energy Commission Report, Washington, D.C.
- Brauer, F.P. Soldat, J.D., Tenny, H., and Strebin, R.S., 1974,
  "Natural Iodine and Iodine-129 in Mammalian Thyroids and Environmental Samples Taken From Locations in the United States," in: Environmental Surveillance Around Nuclear Installations II, International Atomic Energy Agency Report, IAEA-SM-180/34, Vienna.
- Br80 Brauer, F.P. and Naidu, J., 1980, 129I Analysis of Marshall Islands
  Environmental Samples, Analytical and Quality Assurance Procedures,
  Progress Report, Brookhaven National Laboratory, Upton, NY.
- CBEIR80 Committee on the Biological Effects of Ionizing Radiation, 1980, The Effects on Populations of Exposure to Low Levels of Ionizing Radiation: 1980, National Research Council Report, National Academy Press, Washington, D.C.
- Cole, R., 1972, Inhalation of Radioiodine from Fallout: Hazards and Countermeasures, Environmental Science Associates Report, Burlingame, CA, ESA-TR-72-01.
- Co74 Conard, R.A. et al., 1974, A Twenty Year Review of Medical Findings in a Marshallese Population Accidentally Exposed to Radioactive Fallout, Brookhaven National Laboratory, Upton, NY, BNL 50424.
- Conard, R.A. et al., 1980, Review of Medical Findings in a

  Marshallese Population Twenty Six Years After Accidental Exposure to
  Radioactive Fallout, Brookhaven National Laboratory, Upton, NY, BNL
  51261.

- Cronkite, E.P., Bond, V.P., and Dunham, C.L., 1956, "A Report on the Marshallese and Americans Accidentally Exposed to Radiation from Fallout and a Discussion of Radiation Injury in the Human Being," in:

  Some Effects of Ionizing Radiation on Human Beings, U.S. Atomic Energy Commission, Washington, DC, USAEC-TID 5358.
- Crocker, G.R., 1963, Estimates of Fission Product Yields of a Thermonuclear Explosion, United States Naval Radiological Defense Laboratory Report, San Francisco, CA, USNRDL-TR-642.
- Crocker, G. R. and Turner, T., 1965, Calculated Activities, Exposure Rates, and Gamma Spectra for Unfractionated Fission Products, United States Naval Radiological Defense Laboratory Report, San Francisco, CA, USNRDL-TR-1009.
- Cr81 Cronkite, E., 1981, Letter to Charles Sondhaus, University of California, Irvine, CA.
- De75 De Groot, L.J., 1975, "Thyroid Carcinoma," Med. Clin. N.A., 59, 1233.
- Dunning, G.M. and Hilcken, J.A. (eds.), 1956, The Shorter-Term Biological Hazards of a Fallout Field, Symposium, 12-14 December, U.S. Atomic Energy Commission and Department of Defense, Washington, DC.
- Dunning, D.E., Jr. and Schwarz, G., 1981, "Variability of Human Thyroid Characteristics and Estimates of Dose from Ingested <sup>131</sup>I,"

  Health Phys. 40, 661-675.
- Eve, I. S., 1966, "A Review of the Physiology of the Gastrointestinal Tract in Relation to Radiation Doses from Radioactive Materials," Health Phys. 12, 131-161.
- Fr61 Freiling, E. C., 1961, "Radionuclide Fractionation in Bomb Debris," Science 133, 1991-1998.
- Glasstone, S. (ed.), 1962, The Effects of Nuclear Weapons, Defense
  Atomic Support Agency, Department of Defense, U.S. Atomic Energy
  Commission, Washington, DC.
- Ha52 Hald, A., 1952, Statistical Theory with Engineering Applications, Wiley Publications, New York.
- Ha54

  Harris, P.S., 1954, A Summary of the Results of Urine Analyses on Rongelap Natives, Americans and Japanese Fisherman to Date, Los Alamos Scientific Laboratory, Internal Memorandum, Los Alamos, NM.
- Ha63 Harrison, J., 1963, "The Fate of Radioiodine Applied to Human Skin," Health Phys. 9, 993-1000.

- Ha79 Hawthorne, H.A., Editor, 1979, Compilation of Local Fallout Data from Test Detonations 1945-1962 Extracted from DASA 1251, Defense Nuclear Agency Report, DNA 1251-2-Ex, Santa Barbara, CA.
- He65 Held, E., 1965, Gamma Dose at Rongelap Atoll, 1954-1963, Laboratory of Radiation Biology, University of Washington, Seattle, WA, UWFLO-91.
- Hi81 Hicks, H.G., 1981, Results of Calculations of External Gamma-Radiaton Exposure Rates from Fallout and the Related Radionuclide Compositions, Lawrence Livermore National Laboratory Report, Livermore, CA, UCRL-53152.
- Ho63 Holland, J. Z., 1963, "Distribution and Physical-Chemical Nature of Fallout," Feder. Proc. 22, 1390-1397.
- International Commission on Radiological Protection, 1968, Report of
  Committee IV on Evaluation of Radiation Doses to Body Tissues from Internal Contamination Due to Occupational Exposure, ICRP Publication
  10 Pergamon Press, London.
- International Commission on Radiological Protection, 1972, Alkaline
  Earth Metabolism in Adult Men, ICRP Publication 20, Pergamon Press,
  Oxford.
- ICRP74 International Commission on Radiological Protection, 1974, Reference
  Man, ICRP Publication 23, Pergamon Press, Oxford.
- ICRP79 International Commission on Radiological Protection, 1979,
  Report of Committee II on Limits for Intakes of Radionuclides by
  Workers, ICRP Publication 30, Pergamon Press, Oxford.
- International Commission on Radiological Protection, 1980, The

  Computational Models and Transfer Coefficients for Dose Assessment,

  ICRP Draft Report for Committee IV, ICRP/80/C-4/02.
- Ishibasi, M., Shigematsu, T., Ishida, T., Okada, S., Nishi, T.,
  Takahashi, H., Matsumoto, C., Shimizu, S., Hyodo, T., Hirayama, F.,
  and Okamoto, S., 1956, "Radiochemical Analysis of the Bikini Ashes,"
  in: Research in the Effects and Influences of the Nuclear Bomb Test
  Explosions, Japan Society for the Promotion of Science, Tokyo.
- James, R.A., 1964, Estimate of Radiation Dose to Thyroids of Rongelap Children Following the BRAVO Event, Lawrence Radiation Laboratory Report, Livermore, CA, UCRL-12273.
- JCAE57 Joint Committee On Atomic Energy, 1957, The Nature of Radioactive Fall-Out and Its Effects on Man, Part 1, Washington, DC.

- JCCRRER56 Japan Committee for Compilation of Reports on Research in the Effects of Radioactivity, 1956, Research in the Effects and Influences of the Nuclear Bomb Test Explosions, Japan Society for Promotion of Science, Tokyo.
- Johnson, J.R., 1981, "Radioiodine Dosimetry," J. Radioanal. Chem. 65, 223-238.
- Johnson, J.R., 1982, "Fetal Thyroid Dose From Intakes of Radioiodine by the Mother," Health Phys. 43, 573-582.
- Kawahara, F. K., O'Conner, J. D., Lee, H., and Connors, M. A., 1966, Local Fallout From Nuclear Test Detonations, Vol. III, Defense Atomic Support Agency, San Francisco, CA, DASA 1251.
- Keisch, B., Koch, R.C., Levine, A.L., 1965, "Determination of Biospheric Levels of I-129 by Neutron-Activation Analysis," in: Modern Trends in Activation Analysis, Texas A&M University Report, College Station, TX.
- Kimura, K., 1956, "Radiochemical Studies on the Radioactive Dust Due to the Nuclear Detonation at the Bikini Atoll on 1st March, 1954," in: Research in the Effects and Influences of the Nuclear Bomb Test Explosions, Japan Society for the Promotion of Science, Tokyo.
- Ko80 Kocher, D., C., 1980, "Dose Rate Conversion Factors for External Exposure to Photon and Electron Radiation from Radionuclides Occurring in Routine Releases from Nuclear Fuel Cycle Facilities," Health Phys. 38, 543-621.
- Le82 Lee, Yoke-Sun, 1982, "Thyroid Cancers in Singapore 1968-'77," Trop. Geograph. Med. 34, 303-308.
- Lavrenchik, V. N., 1965, Global Fallout Products of Nuclear

  Explosions, Atomic Energy Commission Report, Washington, D.C., AECtr-6666.
- Lederer, C. M. and Shirley, V. S., Editors, 1978, <u>Table of The Isotopes</u>, Seventh Edition, John Wiley and Sons, Inc., NY.
- Le84 Lessard, E. T., Miltenberger, R. P., Cohn, S. H., Musolino, S. V., and Conard, R. A., 1984, "Protracted Exposure to Fallout: The Rongelap and Utirik Experience," Health Phys. 46(3), 511-527.
- Ma56 Mather, R.L., 1956, "Brief Summary of Gamma Radiation Spectra from Residual Radiation Sources Following a Nuclear Detonation," in: The Shorter-Term Biological Hazards of a Fallout Field, United States Atomic Energy Commission and Department of Defense Report, Washington, DC.

- Ma81 Mattson, Sorën et al., 1981, "Excretion of Radionuclides In Human Breast Milk Following Administration of I-125 Fibrinogen, Tc-99-MAA and Cr-51 EDTA," in: Third International Radiopharmaceutical Dosimetry Symposium, Conference Proceedings, Oak Ridge, TN, FDA 81-8166.
- Mi79 Miltenberger, R.P., Greenhouse, N.A., and Lessard, E.T., 1979, "Whole Body Counting Results from 1974 to 1979 for Bikini Island Residents," Health Phys. 39(3), 395-408.
- Mi83 Miltenberger, R. P. and Lessard, E. T., Editors, 1983, Body Burdens and Dose Assessment for Bikini Island Residents, Brookhaven National Laboratory Report, Upton, NY, BNL Draft.
- Na80 Naidu, J.R., Greenhouse, N.A., Knight, G., and Craighead, E.C., 1980,

  Marshall Islands: A Study of Diet and Living Patterns, Brookhaven National Laboratory, Upton, NY, BNL 51313.
- Norment, H. G., Schwenke, T. W., and Kohlberg, I., 1966, <u>Development</u>
  of an Improved Land-Surface Fallout Model, Technical Operations Research Report, Burlington, MA, TO-B 65-99.
- NNDC82 National Nuclear Data Center, 1982, Evaluated Nuclear Data Files, Brookhaven National Laboratory Report, Upton, NY, ENDF BIV.
- O'Conner, J.D. and Crocker, G.R., 1968, Local Fallout From Nuclear

  Test Detonations, Defense Atomic Support Agency, Naval Radiological

  Defense Laboratory, San Fransisco, CA, DASA 1251.
- Pe81 Peterson, K., 1981, Castle-Bravo Air Concentration and Deposition
  Patterns from a 3-D Particle-in-Cell Code, Lawrence Livermore National Laboratory Report, Livermore, CA, UASG 81-20.
- Ph82 Phillips, J.C., 1982, A Revised Estimate of the Internal Radiation
  Doses of American Military Personnel on Rongerik Atoll, Shot Bravo,
  Operation Castle, Science Applications, Inc. Draft Topical Report,
  Schaumburg, IL, DNA001-82-C-0012.
- RSIC73 Radiation Shielding Information Committee, 1973, <u>Data Library</u>
  Collection, <u>Radionuclide Gamma-Ray Energy and Intensity Compilation</u>,
  Oak Ridge National Laboratory Report, Oak Ridge, TN, ORNL-TM-4095.
- Sharp, R., and Chapman, W., 1957, Exposure of Marshall Islanders and American Military Personnel to Fallout, Naval Medical Research Institute, Bethesda, MD, WT-938.
- Sk75 Skrable, K., French, C., Chabot, G., Major, A., and Ward, K., 1974, "Kinetics Equation for Linear First-Order Nuclear Phenomena," Nucl. Safety 16, 337-344.

- Sondhaus, C.A. and Bond, V.P., 1955, Physical Factors and Dosimetry in the Marshall Islands Radiation Exposures, Naval Medical Research Institute Report, Bethesda, MD, WT-939.
- Studier, M., Postmus, H.C., Jr., Mech, J., Walters, R.R., and Sloth, E.N., 1962, "The Use of 129 I as an Isotopic Tracer and its Determination Along With Normal 127 I by Neutron Activation -- The Isolation of Iodine from a Variety of Materials," J. Inorg. Nucl. Chem. 24, 755.
- Suito, E., Tokiyama, K., and Uyeda, N., 1956, "Colloid Morphological and Crystalline Studies of Bikini Dust," in: Research in the Effects and Influences of the Nuclear Bomb Test Explosions, Japan Society for the Promotion of Science, Tokyo.
- Tsuzuki, M., 1955, "Erfahrungen uber Radioaktive Schadigung der japanische Fisher durch Bikini-asche," Muench. Med. Wochsch. 31, 988-994.
- USPHS59 United States Public Health Service, 1959, Report of the Public Health Service Off-Site Radiological Monitoring Data, Operation Hardtack Phase I 1958, publisher unknown, manuscript attached to letter from Lt. Colonel Belmont Evans, (USA) to Robert Conard, M.D., Brookhaven National Laboratory, Upton, NY.
- Ya56

  Yamatera, 1956, "Radiochemical Analysis of Dust Due To the Thermonuclear Test on March 1, 1954," in: Research in the Effects and Influences of the Nuclear Bomb Test Explosions, Japan Society for the Promotion of Science, Tokyo.

소U.S. GOVERNMENT PRINTING OFFICE: 1985 515 034 10021